

[MS-VGSP]:

Visio Graphics Service Protocol

Intellectual Property Rights Notice for Open Specifications Documentation

- **Technical Documentation.** Microsoft publishes Open Specifications documentation for protocols, file formats, languages, standards as well as overviews of the interaction among each of these technologies.
- **Copyrights.** This documentation is covered by Microsoft copyrights. Regardless of any other terms that are contained in the terms of use for the Microsoft website that hosts this documentation, you may make copies of it in order to develop implementations of the technologies described in the Open Specifications and may distribute portions of it in your implementations using these technologies or your documentation as necessary to properly document the implementation. You may also distribute in your implementation, with or without modification, any schema, IDL's, or code samples that are included in the documentation. This permission also applies to any documents that are referenced in the Open Specifications.
- **No Trade Secrets.** Microsoft does not claim any trade secret rights in this documentation.
- **Patents.** Microsoft has patents that may cover your implementations of the technologies described in the Open Specifications. Neither this notice nor Microsoft's delivery of the documentation grants any licenses under those or any other Microsoft patents. However, a given Open Specification may be covered by Microsoft [Open Specification Promise](#) or the [Community Promise](#). If you would prefer a written license, or if the technologies described in the Open Specifications are not covered by the Open Specifications Promise or Community Promise, as applicable, patent licenses are available by contacting iplg@microsoft.com.
- **Trademarks.** The names of companies and products contained in this documentation may be covered by trademarks or similar intellectual property rights. This notice does not grant any licenses under those rights. For a list of Microsoft trademarks, visit www.microsoft.com/trademarks.
- **Fictitious Names.** The example companies, organizations, products, domain names, e-mail addresses, logos, people, places, and events depicted in this documentation are fictitious. No association with any real company, organization, product, domain name, email address, logo, person, place, or event is intended or should be inferred.

Reservation of Rights. All other rights are reserved, and this notice does not grant any rights other than specifically described above, whether by implication, estoppel, or otherwise.

Tools. The Open Specifications do not require the use of Microsoft programming tools or programming environments in order for you to develop an implementation. If you have access to Microsoft programming tools and environments you are free to take advantage of them. Certain Open Specifications are intended for use in conjunction with publicly available standard specifications and network programming art, and assumes that the reader either is familiar with the aforementioned material or has immediate access to it.

Preliminary Documentation. This Open Specification provides documentation for past and current releases and/or for the pre-release version of this technology. This Open Specification is final documentation for past or current releases as specifically noted in the document, as applicable; it is preliminary documentation for the pre-release versions. Microsoft will release final documentation in connection with the commercial release of the updated or new version of this technology. As the documentation may change between this preliminary version and the final version of this technology, there are risks in relying on preliminary documentation. To the extent that you incur additional

development obligations or any other costs as a result of relying on this preliminary documentation,
you do so at your own risk.

Preliminary

Revision Summary

| Date | Revision History | Revision Class | Comments |
|------------|------------------|----------------|--|
| 7/13/2009 | 0.1 | Major | Initial Availability |
| 8/28/2009 | 0.2 | Editorial | Revised and edited the technical content |
| 11/6/2009 | 0.3 | Editorial | Revised and edited the technical content |
| 2/19/2010 | 1.0 | Major | Updated and revised the technical content |
| 3/31/2010 | 1.01 | Editorial | Revised and edited the technical content |
| 4/30/2010 | 1.02 | Editorial | Revised and edited the technical content |
| 6/7/2010 | 1.03 | Editorial | Revised and edited the technical content |
| 6/29/2010 | 1.04 | Editorial | Changed language and formatting in the technical content. |
| 7/23/2010 | 1.04 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 9/27/2010 | 1.04 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 11/15/2010 | 1.04 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 12/17/2010 | 1.04 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 3/18/2011 | 1.04 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 6/10/2011 | 1.5 | Minor | Clarified the meaning of the technical content. |
| 1/20/2012 | 2.0 | Major | Significantly changed the technical content. |
| 4/11/2012 | 2.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 7/16/2012 | 2.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 9/12/2012 | 2.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 10/8/2012 | 3.0 | Major | Significantly changed the technical content. |
| 2/11/2013 | 3.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 7/30/2013 | 3.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 11/18/2013 | 3.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 2/10/2014 | 3.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |
| 4/30/2014 | 3.0 | No Change | No changes to the meaning, language, or formatting of the technical content. |

| Date | Revision History | Revision Class | Comments |
|-----------|------------------|----------------|---|
| 7/31/2014 | 3.1 | Minor | Clarified the meaning of the technical content. |
| 8/24/2015 | 4.0 | Major | Significantly changed the technical content. |

Preliminary

Table of Contents

| | |
|---|-----------|
| 1 Introduction | 9 |
| 1.1 Glossary | 9 |
| 1.2 References | 11 |
| 1.2.1 Normative References | 12 |
| 1.2.2 Informative References | 12 |
| 1.3 Overview | 13 |
| 1.3.1 Web Drawing | 13 |
| 1.3.2 Drawing Page..... | 13 |
| 1.3.2.1 Foreground Page..... | 13 |
| 1.3.3 Shape | 14 |
| 1.3.4 Shape Data..... | 14 |
| 1.3.5 Comment | 14 |
| 1.4 Relationship to Other Protocols | 14 |
| 1.5 Prerequisites/Preconditions | 14 |
| 1.6 Applicability Statement | 15 |
| 1.7 Versioning and Capability Negotiation | 15 |
| 1.8 Vendor-Extensible Fields | 15 |
| 1.9 Standards Assignments..... | 15 |
| 2 Messages..... | 16 |
| 2.1 Transport | 16 |
| 2.2 Common Message Syntax | 16 |
| 2.2.1 Namespaces | 16 |
| 2.2.2 Messages..... | 17 |
| 2.2.3 Elements | 17 |
| 2.2.3.1 VisioGraphicsServiceFault | 17 |
| 2.2.4 Complex Types..... | 17 |
| 2.2.4.1 AddonDataSource | 18 |
| 2.2.4.2 ArrayOfAddonDataSource..... | 18 |
| 2.2.4.3 BaseRequestContract | 19 |
| 2.2.4.4 DiagramBase | 19 |
| 2.2.4.5 VisioGraphicsServiceFault | 20 |
| 2.2.5 Simple Types | 21 |
| 2.2.5.1 FaultCode | 21 |
| 2.2.6 Attributes | 24 |
| 2.2.7 Groups | 24 |
| 2.2.8 Attribute Groups..... | 24 |
| 2.2.9 Common Data Structures | 24 |
| 2.2.9.1 ShapeInfo | 25 |
| 2.2.9.1.1 Page | 25 |
| 2.2.9.1.2 Pages..... | 27 |
| 2.2.9.1.3 PageInfo | 27 |
| 2.2.9.1.4 ShapeInfo | 27 |
| 2.2.9.1.5 Hyperlinks | 29 |
| 2.2.9.1.6 Hyperlink..... | 29 |
| 2.2.9.1.7 ShapeDataItems | 30 |
| 2.2.9.1.8 ShapeData | 31 |
| 2.2.9.1.9 Shapes..... | 31 |
| 2.2.9.1.10 Shape | 31 |
| 2.2.9.1.11 Path..... | 31 |
| 2.2.9.2 Comments | 32 |
| 2.2.9.2.1 Comments..... | 32 |
| 2.2.9.2.2 CommentEntry..... | 32 |
| 2.2.9.3 CommentData | 33 |
| 2.2.9.3.1 Comment | 33 |

| | | |
|-------------|--|-----------|
| 2.2.9.4 | CommentResult | 34 |
| 2.2.9.4.1 | Comment | 34 |
| 3 | Protocol Details..... | 36 |
| 3.1 | Common Details | 36 |
| 3.1.1 | Abstract Data Model..... | 38 |
| 3.1.2 | Timers | 38 |
| 3.1.3 | Initialization..... | 38 |
| 3.1.4 | Message Processing Events and Sequencing Rules | 38 |
| 3.1.4.1 | GetRasterDiagram..... | 39 |
| 3.1.4.1.1 | Messages | 40 |
| 3.1.4.1.1.1 | IVisioGraphicsService_GetRasterDiagram_InputMessage | 41 |
| 3.1.4.1.1.2 | IVisioGraphicsService_GetRasterDiagram_OutputMessage | 41 |
| 3.1.4.1.1.3 | IVisioGraphicsService_GetRasterDiagram_VisioGraphicsServiceFaultFaultMessage | 41 |
| 3.1.4.1.2 | Elements | 41 |
| 3.1.4.1.2.1 | GetRasterDiagram | 41 |
| 3.1.4.1.2.2 | GetRasterDiagramResponse | 42 |
| 3.1.4.1.3 | Complex Types | 42 |
| 3.1.4.1.3.1 | RasterDiagramRequestContract | 42 |
| 3.1.4.1.3.2 | RasterDiagram | 42 |
| 3.1.4.1.4 | Simple Types | 43 |
| 3.1.4.1.5 | Attributes | 43 |
| 3.1.4.1.6 | Groups..... | 44 |
| 3.1.4.1.7 | Attribute Groups..... | 44 |
| 3.1.4.2 | GetVectorDiagram..... | 44 |
| 3.1.4.2.1 | Messages | 44 |
| 3.1.4.2.1.1 | IVisioGraphicsService_GetVectorDiagram_InputMessage | 45 |
| 3.1.4.2.1.2 | IVisioGraphicsService_GetVectorDiagram_OutputMessage | 45 |
| 3.1.4.2.1.3 | IVisioGraphicsService_GetVectorDiagram_VisioGraphicsServiceFaultFaultMessage | 45 |
| 3.1.4.2.2 | Elements..... | 45 |
| 3.1.4.2.2.1 | GetVectorDiagram | 46 |
| 3.1.4.2.2.2 | GetVectorDiagramResponse | 46 |
| 3.1.4.2.3 | Complex Types | 46 |
| 3.1.4.2.3.1 | VectorDiagramRequestContract | 47 |
| 3.1.4.2.3.2 | VectorDiagram | 47 |
| 3.1.4.2.3.3 | RenderedPage | 47 |
| 3.1.4.2.3.4 | ArrayOfDiagramResource..... | 48 |
| 3.1.4.2.3.5 | DiagramResource..... | 48 |
| 3.1.4.2.4 | Simple Types | 49 |
| 3.1.4.2.5 | Attributes | 49 |
| 3.1.4.2.6 | Groups..... | 49 |
| 3.1.4.2.7 | Attribute Groups..... | 49 |
| 3.1.4.3 | GetRasterPage..... | 49 |
| 3.1.4.3.1 | Messages | 50 |
| 3.1.4.3.1.1 | IVisioGraphicsService_GetRasterPage_InputMessage | 50 |
| 3.1.4.3.1.2 | IVisioGraphicsService_GetRasterPage_OutputMessage | 51 |
| 3.1.4.3.1.3 | IVisioGraphicsService_GetRasterPage_VisioGraphicsServiceFaultFaultFaultMessage | 51 |
| 3.1.4.3.2 | Elements..... | 51 |
| 3.1.4.3.2.1 | GetRasterPage..... | 51 |
| 3.1.4.3.2.2 | GetRasterPageResponse | 51 |
| 3.1.4.3.3 | Complex Types | 52 |
| 3.1.4.3.3.1 | RasterPageRequest | 52 |

| | | |
|--|---|----|
| 3.1.4.3.3.2 | RasterPageResponse | 53 |
| 3.1.4.3.3.3 | RasterPageTag | 54 |
| 3.1.4.3.3.4 | RasterPageInfo | 55 |
| 3.1.4.3.4 | Simple Types | 55 |
| 3.1.4.3.4.1 | RasterPageResponseCode | 55 |
| 3.1.4.3.5 | Attributes | 56 |
| 3.1.4.3.6 | Groups | 56 |
| 3.1.4.3.7 | Attribute Groups | 56 |
| 3.1.4.4 | GetRasterPageItem | 56 |
| 3.1.4.4.1 | Messages | 57 |
| 3.1.4.4.1.1 | IVisioGraphicsService_GetRasterPageItem_InputMessage | 57 |
| 3.1.4.4.1.2 | IVisioGraphicsService_GetRasterPageItem_OutputMessage | 57 |
| 3.1.4.4.1.3 | IVisioGraphicsService_GetRasterPageItem_VisioGraphicsServiceFaultFaultMessage | 57 |
| 3.1.4.4.2 | Elements | 57 |
| 3.1.4.4.2.1 | GetRasterPageItem | 58 |
| 3.1.4.4.2.2 | GetRasterPageItemResponse | 58 |
| 3.1.4.4.3 | Complex Types | 58 |
| 3.1.4.4.3.1 | RasterPageItemRequest | 59 |
| 3.1.4.4.3.2 | RasterPageItemTag | 60 |
| 3.1.4.4.3.3 | RasterPageItemResponse | 60 |
| 3.1.4.4.4 | Simple Types | 61 |
| 3.1.4.4.4.1 | RasterPageItemResponseCode | 61 |
| 3.1.4.4.5 | Attributes | 62 |
| 3.1.4.4.6 | Groups | 62 |
| 3.1.4.4.7 | Attribute Groups | 62 |
| 3.1.4.5 | SaveComments | 62 |
| 3.1.4.5.1 | Messages | 63 |
| 3.1.4.5.1.1 | IVisioGraphicsService_SaveComments_InputMessage | 63 |
| 3.1.4.5.1.2 | IVisioGraphicsService_SaveComments_OutputMessage | 63 |
| 3.1.4.5.1.3 | IVisioGraphicsService_SaveComments_VisioGraphicsServiceFaultFaultMessage | 63 |
| 3.1.4.5.2 | Elements | 64 |
| 3.1.4.5.2.1 | SaveComments | 64 |
| 3.1.4.5.2.2 | SaveCommentsResponse | 64 |
| 3.1.4.5.3 | Complex Types | 64 |
| 3.1.4.5.4 | Simple Types | 64 |
| 3.1.4.5.5 | Attributes | 64 |
| 3.1.4.5.6 | Groups | 65 |
| 3.1.4.5.7 | Attribute Groups | 65 |
| 3.1.5 | Timer Events | 65 |
| 3.1.6 | Other Local Events | 65 |
| 4 Protocol Examples | 66 | |
| 4.1 | GetRasterDiagram | 66 |
| 4.2 | GetVectorDiagram | 71 |
| 4.3 | GetVectorDiagram with AddonDataSource | 73 |
| 4.4 | GetRasterPage | 87 |
| 4.5 | GetRasterPageItem | 88 |
| 4.6 | SaveComments | 91 |
| 5 Security | 93 | |
| 5.1 | Security Considerations for Implementers | 93 |
| 5.2 | Index of Security Parameters | 93 |
| 6 Appendix A: Full WSDL | 94 | |
| 7 Appendix B: Full XML Schema | 98 | |

| | | |
|-----------|---|------------|
| 7.1 | http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer Schema | 98 |
| 7.2 | http://schemas.microsoft.com/2003/10/Serialization/Arrays Schema | 102 |
| 7.3 | http://schemas.microsoft.com/2003/10/Serialization/ Schema | 102 |
| 7.4 | http://tempuri.org/ Schema | 103 |
| 8 | Appendix C: Product Behavior | 105 |
| 9 | Change Tracking..... | 106 |
| 10 | Index..... | 108 |

Preliminary

1 Introduction

The Visio Graphics Service Protocol enables a protocol client to communicate with a protocol server to retrieve information about a [web drawing](#) that is stored in a document repository.

Sections 1.8, 2, and 3 of this specification are normative and can contain the terms MAY, SHOULD, MUST, MUST NOT, and SHOULD NOT as defined in [\[RFC2119\]](#). Sections 1.5 and 1.9 are also normative but do not contain those terms. All other sections and examples in this specification are informative.

1.1 Glossary

The following terms are specific to this document:

Coordinated Universal Time (UTC): A high-precision atomic time standard that approximately tracks Universal Time (UT). It is the basis for legal, civil time all over the Earth. Time zones around the world are expressed as positive and negative offsets from UTC. In this role, it is also referred to as Zulu time (Z) and Greenwich Mean Time (GMT). In these specifications, all references to UTC refer to the time at UTC-0 (or GMT).

data connection: A collection of information, such as the type and location, that defines how to connect to an external data source, such as a database, web service, SharePoint list, or XML file.

data provider: A known data source that is specific to a target type and that provides data to a collector type.

data source: A database, web service, disk, file, or other collection of information from which data is queried or submitted. Supported data sources vary based on application and data provider.

domain: A set of users and computers sharing a common namespace and management infrastructure. At least one computer member of the set must act as a domain controller (DC) and host a member list that identifies all members of the domain, as well as optionally hosting the Active Directory service. The domain controller provides authentication (2) of members, creating a unit of trust for its members. Each domain has an identifier that is shared among its members. For more information, see [\[MS-AUTHSODI\]](#) section 1.1.1.5 and [\[MS-ADTS\]](#).

drawing: A collection of drawing objects, such as shapes, curves, or WordArt, that are viewed together as a single image.

embedded object: An object that is created by using one application and is hosted in a document that was created by using another application. Embedding an object, rather than inserting or pasting it, ensures that the object retains its original format. Users can double-click an embedded object and edit it with the toolbars and menus from the application that was used to create it. See also Object Linking and Embedding (OLE).

endpoint: A communication port that is exposed by an application server for a specific shared service and to which messages can be addressed.

Extensible Application Markup Language (XAML): A declarative XML-based language that is used to represent a tree of objects. XAML markup is stored in .xaml files or, for workflow schemas, .xoml files.

font: An object that defines the graphic design, or formatting, of a collection of numbers, symbols, and letters. A font specifies the style (such as bold and strikeout), size, family (a typeface such as Times New Roman), and other qualities to describe how the collection is drawn.

fully qualified class name: A class name that includes namespace information. Use of a fully qualified class name ensures that the class name is treated as unique.

globally unique identifier (GUID): A term used interchangeably with universally unique identifier (UUID) in Microsoft protocol technical documents (TDs). Interchanging the usage of these terms does not imply or require a specific algorithm or mechanism to generate the value. Specifically, the use of this term does not imply or require that the algorithms described in [\[RFC4122\]](#) or [\[C706\]](#) must be used for generating the **GUID**. See also universally unique identifier (UUID).

hyperlink: A relationship between two anchors, as described in [\[RFC1861\]](#).

Hypertext Transfer Protocol (HTTP): An application-level protocol for distributed, collaborative, hypermedia information systems (text, graphic images, sound, video, and other multimedia files) on the World Wide Web.

Hypertext Transfer Protocol Secure (HTTPS): An extension of HTTP that securely encrypts and decrypts web page requests. In some older protocols, "Hypertext Transfer Protocol over Secure Sockets Layer" is still used (Secure Sockets Layer has been deprecated). For more information, see [\[SSL3\]](#) and [\[RFC5246\]](#).

JavaScript Object Notation (JSON): A text-based, data interchange format that is used to transmit structured data, typically in Asynchronous JavaScript + XML (AJAX) web applications, as described in [\[RFC4627\]](#). The JSON format is based on the structure of ECMAScript (Jscript, JavaScript) objects.

list: A container within a SharePoint site that stores list items. A list has a customizable schema that is composed of one or more fields.

Office data connection (ODC) file: A file that stores information about a connection to a data source, such as an Access database, worksheet, or text file. This file facilitates data source administration.

pixel: A discrete unit of display on a computer display device.

Portable Network Graphics (PNG): A bitmap graphics file format that uses lossless data compression and supports variable transparency of images (alpha channels) and control of image brightness on different computers (gamma correction). PNG-format files have a .png file name extension.

primary key: A field or set of fields that uniquely identifies each record in a table. A primary key cannot contain a null value.

row: A single set of data that is displayed horizontally in a worksheet or a table.

SOAP: A lightweight protocol for exchanging structured information in a decentralized, distributed environment. **SOAP** uses XML technologies to define an extensible messaging framework, which provides a message construct that can be exchanged over a variety of underlying protocols. The framework has been designed to be independent of any particular programming model and other implementation-specific semantics. SOAP 1.2 supersedes SOAP 1.1. See [\[SOAP1.2-1/2003\]](#).

SOAP action: The HTTP request header field used to indicate the intent of the **SOAP** request, using a **URI** value. See [\[SOAP1.1\]](#) section 6.1.1 for more information.

SOAP body: A container for the payload data being delivered by a SOAP message to its recipient. See [\[SOAP1.2-1/2007\]](#) section 5.3 for more information.

SOAP fault: A container for error and status information within a SOAP message. See [\[SOAP1.2-1/2007\]](#) section 5.4 for more information.

Status-Code: A 3-digit integer result code in an HTTP response message, as described in [\[RFC2616\]](#).

Transmission Control Protocol (TCP): A protocol used with the Internet Protocol (IP) to send data in the form of message units between computers over the Internet. TCP handles keeping track of the individual units of data (called packets) that a message is divided into for efficient routing through the Internet.

Uniform Resource Identifier (URI): A string that identifies a resource. The URI is an addressing mechanism defined in Internet Engineering Task Force (IETF) Uniform Resource Identifier (URI): Generic Syntax [\[RFC3986\]](#).

Uniform Resource Locator (URL): A string of characters in a standardized format that identifies a document or resource on the World Wide Web. The format is as specified in [\[RFC1738\]](#).

view: See form view (Microsoft InfoPath), list view (SharePoint Products and Technologies), or View (Microsoft Business Connectivity Services).

Web Services Description Language (WSDL): An XML format for describing network services as a set of endpoints that operate on messages that contain either document-oriented or procedure-oriented information. The operations and messages are described abstractly and are bound to a concrete network protocol and message format in order to define an endpoint. Related concrete endpoints are combined into abstract endpoints, which describe a network service. WSDL is extensible, which allows the description of endpoints and their messages regardless of the message formats or network protocols that are used.

WSDL message: An abstract, typed definition of the data that is communicated during a **WSDL operation** [\[WSDL\]](#). Also, an element that describes the data being exchanged between web service providers and clients.

WSDL operation: A single action or function of a web service. The execution of a WSDL operation typically requires the exchange of messages between the service requestor and the service provider.

XML namespace: A collection of names that is used to identify elements, types, and attributes in XML documents identified in a URI reference [\[RFC3986\]](#). A combination of XML namespace and local name allows XML documents to use elements, types, and attributes that have the same names but come from different sources. For more information, see [\[XMLNS-2ED\]](#).

XML namespace prefix: An abbreviated form of an **XML namespace**, as described in [\[XML\]](#).

XML schema: A description of a type of XML document that is typically expressed in terms of constraints on the structure and content of documents of that type, in addition to the basic syntax constraints that are imposed by XML itself. An XML schema provides a view of a document type at a relatively high level of abstraction.

zoom level: The degree to which a portion of an image, document, or other screen object is made to appear closer or farther away relative to its default appearance. This value is usually expressed as a percentage of the default appearance.

MAY, SHOULD, MUST, SHOULD NOT, MUST NOT: These terms (in all caps) are used as defined in [\[RFC2119\]](#). All statements of optional behavior use either MAY, SHOULD, or SHOULD NOT.

1.2 References

Links to a document in the Microsoft Open Specifications library point to the correct section in the most recently published version of the referenced document. However, because individual documents in the library are not updated at the same time, the section numbers in the documents may not match. You can confirm the correct section numbering by checking the [Errata](#).

1.2.1 Normative References

We conduct frequent surveys of the normative references to assure their continued availability. If you have any issue with finding a normative reference, please contact dochelp@microsoft.com. We will assist you in finding the relevant information.

[MS-DSDIFFGRAM] Microsoft Corporation, "[SharePoint Web Services: DataSet DiffGram Structure](#)".

[MS-SLXV] Microsoft Corporation, "[Silverlight XAML Vocabulary Specification 2008](#)".

[MS-SPSTWS] Microsoft Corporation, "[SharePoint Security Token Service Web Service Protocol](#)".

[MS-VGSFF] Microsoft Corporation, "[Visio Graphics Service File Format \(.vdw\) Specification](#)".

[MS-VSDX] Microsoft Corporation, "[Visio Graphics Service VSDX File Format](#)".

[MS-WSSTS] Microsoft Corporation, "[Windows SharePoint Services](#)".

[RFC1738] Berners-Lee, T., Masinter, L., and McCahill, M., Eds., "Uniform Resource Locators (URL)", RFC 1738, December 1994, <http://www.ietf.org/rfc/rfc1738.txt>

[RFC1980] Seidman, J., "A Proposed Extension to HTML : Client-Side Image Maps", RFC 1980, August 1996, <http://www.rfc-editor.org/rfc/rfc1980.txt>

[RFC2083] Boutell, T., et al., "PNG (Portable Network Graphics) Specification Version 1.0", RFC 2083, March 1997, <http://www.ietf.org/rfc/rfc2083.txt>

[RFC2119] Bradner, S., "Key words for use in RFCs to Indicate Requirement Levels", BCP 14, RFC 2119, March 1997, <http://www.rfc-editor.org/rfc/rfc2119.txt>

[RFC2616] Fielding, R., Gettys, J., Mogul, J., et al., "Hypertext Transfer Protocol -- HTTP/1.1", RFC 2616, June 1999, <http://www.rfc-editor.org/rfc/rfc2616.txt>

[RFC4627] Crockford, D., "The application/json Media Type for JavaScript Object Notation (JSON)", RFC 4627, July 2006, <http://www.ietf.org/rfc/rfc4627.txt>

[SOAP1.1] Box, D., Ehnebuske, D., Kakivaya, G., et al., "Simple Object Access Protocol (SOAP) 1.1", May 2000, <http://www.w3.org/TR/2000/NOTE-SOAP-20000508/>

[SOAP1.2/1] Gudgin, M., Hadley, M., Mendelsohn, N., Moreau, J., and Nielsen, H.F., "SOAP Version 1.2 Part 1: Messaging Framework", W3C Recommendation, June 2003, <http://www.w3.org/TR/2003/REC-soap12-part1-20030624>

[WSDL] Christensen, E., Curbera, F., Meredith, G., and Weerawarana, S., "Web Services Description Language (WSDL) 1.1", W3C Note, March 2001, <http://www.w3.org/TR/2001/NOTE-wsdl-20010315>

[XMLNS] Bray, T., Hollander, D., Layman, A., et al., Eds., "Namespaces in XML 1.0 (Third Edition)", W3C Recommendation, December 2009, <http://www.w3.org/TR/2009/REC-xml-names-20091208/>

[XMLSCHEMA1] Thompson, H., Beech, D., Maloney, M., and Mendelsohn, N., Eds., "XML Schema Part 1: Structures", W3C Recommendation, May 2001, <http://www.w3.org/TR/2001/REC-xmleschema-1-20010502/>

[XMLSCHEMA2] Biron, P.V., Ed. and Malhotra, A., Ed., "XML Schema Part 2: Datatypes", W3C Recommendation, May 2001, <http://www.w3.org/TR/2001/REC-xmleschema-2-20010502/>

1.2.2 Informative References

[MS-SPTWS] Microsoft Corporation, "[Service Platform Topology Web Service Protocol](#)".

[RFC1952] Deutsch, P., "GZIP file format specification version 4.3", RFC 1952, May 1996, <http://www.rfc-editor.org/rfc/rfc1952.txt>

[RFC2818] Rescorla, E., "HTTP Over TLS", RFC 2818, May 2000, <http://www.rfc-editor.org/rfc/rfc2818.txt>

[RFC3629] Yergeau, F., "UTF-8, A Transformation Format of ISO 10646", STD 63, RFC 3629, November 2003, <http://www.ietf.org/rfc/rfc3629.txt>

[SOAP1.2/2] Gudgin, M., Hadley, M., Mendelsohn, N., Moreau, J., and Nielsen, H.F., "SOAP Version 1.2 Part 2: Adjuncts", W3C Recommendation, June 2003, <http://www.w3.org/TR/2003/REC-soap12-part2-20030624>

1.3 Overview

The protocol enables a protocol client to request and receive a drawing page (section 1.3.2) of a [web drawing](#) from the protocol server in either raster or vector format. The supported raster format is the **Portable Network Graphics (PNG)** format, as described in [RFC2083]. The supported vector format is **Extensible Application Markup Language (XAML)**, as described in [MS-SLXVI].

Additionally, the protocol enables a protocol client to add, edit, or delete [comments](#) associated with a drawing page or its [shapes](#).

A typical scenario for using this protocol is an application that retrieves and displays web drawings, and collects collaborative content feedback in comments. Typically a web drawing is contained in a file stored in a document repository.

1.3.1 Web Drawing

A **web drawing** is a collection of drawings page (section 1.3.2), [shapes](#), resources, [comments](#), and information that can be rendered as a [drawing](#) in a web browser. Based on the format of the file that contains the web drawing, the protocol makes the distinction between the following types of web drawings.

| Type | Description |
|-------|---|
| VGSFF | A web drawing contained in a file that conforms to the format specified in [MS-VGSFF] section 2.2.1 |
| VSDX | A web drawing contained in a file that conforms to the format specified in [MS-VSDX] section 2.2.1 |

1.3.2 Drawing Page

A **drawing page** is a collection of shapes (section 1.3.3) that are viewed together.

Drawing pages of **VGSFF** web drawings (section 1.3.1) are specified in [MS-VGSFF] section 2.2.2.

Drawing pages of **VSDX** web drawings are specified in [MS-VSDX] section 2.2.2.

1.3.2.1 Foreground Page

Foreground pages of **VSDX** [web drawings](#) are specified in [MS-VSDX] section 2.2.2.4.

1.3.3 Shape

A **shape** is a collection of geometry, formatting, text, images, hyperlinks, and shape data in a drawing page (section [1.3.2](#)).

Shapes contained in **VGSFF** web drawings are specified in [\[MS-VGSFF\]](#) section 2.2.3.

Shapes contained in **VSDX** web drawings are specified in [\[MS-VSDX\]](#) section 2.2.3.

1.3.4 Shape Data

A shape (section [1.3.3](#)) can have data associated with it that provides information about its meaning. Shape data (section 1.3.4) can come from information stored in the file refreshed from **data providers** or from recalculations of an evaluated formula. The shape data is also formatted for display.

Shape data items contained in **VGSFF** web drawings (section 1.3.1) are specified in [\[MS-VGSFF\]](#) section 2.2.3.5

Shape data items contained in **VSDX** web drawings are specified in [\[MS-VSDX\]](#) section 2.2.3.6.

1.3.5 Comment

A **comment** is a plain text annotation in a [web drawing](#). Each comment specifies an author, and a relationship with a drawing page (section [1.3.2](#)) or a specific [shape](#) on the drawing page.

Comments contained in **VSDX** web drawings are specified in [\[MS-VSDX\]](#) section 2.2.9.

Comments are not contained in **VGSFF** web drawings.

1.4 Relationship to Other Protocols

This protocol uses the **SOAP** message protocol for formatting request and response messages, as described in [\[SOAP1.1\]](#), [\[SOAP1.2/1\]](#) and [\[SOAP1.2/2\]](#). It transmits those messages by using **HTTP**, as described in [\[RFC2616\]](#), or **Hypertext Transfer Protocol over Secure Sockets Layer (HTTPS)**, as described in [\[RFC2818\]](#).

The following diagram shows the underlying messaging and transport stack used by the protocol:




Figure 1: This protocol in relation to other protocols

1.5 Prerequisites/Preconditions

This protocol operates against a protocol server that exposes one or more **endpoint URIs** that are known by protocol clients. The endpoint URI of the protocol server and the transport that is used by

the protocol server are either known by the protocol client or obtained by using the discovery mechanism that is described in [\[MS-SPTWS\]](#).

The protocol client obtains the requisite ApplicationClassId and ApplicationVersion values and the endpoint URI of the protocol server that provides the discovery mechanism, as described in [\[MS-SPTWS\]](#), by means that are independent of either protocol.

This protocol requires the protocol client to have appropriate permission to call the methods on the protocol server.

The protocol client implements the token-based security mechanisms that are required by the protocol server and related security protocols, as described in [\[MS-SPSTWS\]](#).

1.6 Applicability Statement

This protocol is designed to support retrieval of [web drawings](#), and collecting collaborative content feedback in [comments](#).

1.7 Versioning and Capability Negotiation

This specification covers versioning issues in the following areas:

- **Supported Transports:** This protocol can be implemented by using transports that support sending Simple Object Access Protocol (SOAP) messages, as specified in section 2.1.
- **Protocol Versions:** This protocol is not versioned.

Capability Negotiation: This protocol does not support version negotiation.

1.8 Vendor-Extensible Fields

None.

1.9 Standards Assignments

None.

2 Messages

In the following sections, the schema definition might be less restrictive than the processing rules imposed by the protocol. The **WSDL** in this specification matches the WSDL that shipped with the product and provides a base description of the schema. The text that introduces the WSDL specifies additional restrictions that reflect actual Microsoft product behavior. For example, the schema definition might allow for an element to be empty, null, or not present but the behavior of the protocol as specified restricts the same elements to being non-empty, not null, and present.

2.1 Transport

Protocol servers MUST support Simple Object Access Protocol (SOAP) over Hypertext Transfer Protocol (HTTP), Hypertext Transfer Protocol over Secure Sockets Layer (HTTPS), or **TCP**.

All protocol messages MUST be transported by using HTTP or TCP bindings at the transport level.

Protocol messages MUST be formatted as specified in either [\[SOAP1.1\]](#) section 4 or [\[SOAP1.2/1\]](#) section 5. Protocol server faults MUST be returned by using HTTP status codes, as specified in [\[RFC2616\]](#) section 10, or **SOAP faults**, as specified in [\[SOAP1.1\]](#) section 4.4 or [\[SOAP1.2/1\]](#) section 5.4.

If the HTTPS transport is used, a server certificate MUST be deployed.

This protocol MAY transmit an additional SOAP header, the **ServiceContext** header, as specified in [\[MS-SPSTWS\]](#).

This protocol does not define any means for activating a protocol server or protocol client. The protocol server MUST be configured and begin listening in an implementation-specific way. In addition, the protocol client MUST know the format and transport that is used by the server, for example, the SOAP format over an HTTP transport.

2.2 Common Message Syntax

This section contains common definitions that are used by this protocol. The syntax of the definitions uses **XML schema**, as specified in [\[XMLSCHEMA1\]](#) and [\[XMLSCHEMA2\]](#), and WSDL, as specified in [\[WSDL\]](#).

2.2.1 Namespaces

This specification defines and references various **XML namespaces** using the mechanisms specified in [\[XMLNS\]](#). Although this specification associates a specific **XML namespace prefix** for each XML namespace that is used, the choice of any particular XML namespace prefix is implementation-specific and not significant for interoperability.

| Prefix | Namespace URI | Reference |
|--------|--|---------------------------|
| q1 | http://schemas.microsoft.com/2003/10/Serialization/Arrays | |
| soap | http://schemas.xmlsoap.org/wsdl/soap/ | [SOAP1.1] |
| tns | http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer | |
| tns1 | http://schemas.microsoft.com/2003/10/Serialization/ | |
| tns2 | http://tempuri.org/ | |

| Prefi x | Namespace URI | Reference |
|------------|---|------------------------------|
| tns3 | http://tempuri.org/Imports | |
| wsaw | http://www.w3.org/2006/05/addressing/wsdl | |
| wsdl | http://schemas.xmlsoap.org/wsdl/ | [WSDL] |
| xs | http://www.w3.org/2001/XMLSchema | [XMLSCHEMA1] [XMLSCHEMA2] |

2.2.2 Messages

This specification does not define any common **WSDL message** definitions.

2.2.3 Elements

The following table summarizes the set of common XML schema element definitions defined by this specification. XML schema elements that are specific to a particular operation are described with the operation.

| Element | Description |
|----------------------------------|--|
| VisioGraphicsServiceFault | The VisioGraphicsServiceFault element, with complex type VisioGraphicsServiceFault (section 2.2.4.5), contains information about errors that occur during protocol server operations. |

2.2.3.1 VisioGraphicsServiceFault

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **VisioGraphicsServiceFault** element, with complex type **VisioGraphicsServiceFault** (section [2.2.4.5](#)), contains information about errors that occur during protocol server operations.

```
<xs:element name="VisioGraphicsServiceFault" nillable="true"
type="tns:VisioGraphicsServiceFault" xmlns:xs="http://www.w3.org/2001/XMLSchema"/>
```

2.2.4 Complex Types

The following table summarizes the set of common XML schema complex type definitions defined by this specification. XML schema complex type definitions that are specific to a particular operation are described with the operation.

| Complex type | Description |
|-------------------------------|---|
| AddonDataSource | The AddonDataSource complex type contains information about a data provider implemented by a protocol client and used in a web drawing . |
| ArrayOfAddonDataSource | The ArrayOfAddonDataSource complex type contains an array of |

| Complex type | Description |
|----------------------------------|---|
| | AddonDataSource elements (section 2.2.4.1). |
| BaseRequestContract | The BaseRequestContract complex type contains information used to specify the request parameters for a protocol server operation to retrieve a VGSFF web drawing. |
| DiagramBase | The DiagramBase complex type contains information used to specify response data for a protocol server operation to retrieve a VGSFF web drawing. |
| VisioGraphicsServiceFault | The VisioGraphicsServiceFault complex type contains information about errors that occur during protocol server operations. |

2.2.4.1 AddonDataSource

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **AddonDataSource** complex type contains information about a data provider implemented by a protocol client and used in a [web drawing](#).

```
<xs:complexType name="AddonDataSource" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="ConnectionString" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="Data" nillable="true">
      <xs:complexType>
        <xs:sequence>
          <xs:element ref="xs:schema"/>
          <xs:any/>
        </xs:sequence>
      </xs:complexType>
    </xs:element>
    <xs:element minOccurs="0" name="Id" type="xs:int"/>
    <xs:element minOccurs="0" name="QueryString" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>
```

ConnectionString: A string that specifies arguments that define the location of the data provider and how to connect to it. There MUST be exactly one instance of this element, and it MUST NOT be null. It MUST contain the **fully qualified class name** of the data provider.

Data: Specifies the data retrieved from the data provider. It MUST be encoded in the DiffGram [\[MS-DSDIFFGRAM\]](#) format, and it MUST NOT be null.

xs:schema: Specifies the schema for the **Data** element.

Id: An integer that specifies the identifier of this **AddonDataSource**. It MUST be greater than or equal to zero, and it MUST be unique across all the **AddonDataSource** elements in the containing **ArrayOfAddonDataSource** array (section [2.2.4.2](#)). There MUST be exactly one instance of this element.

QueryString: A string that specifies information used to call and retrieve data from the data provider. There MUST be exactly one instance of this element, and it MUST NOT be null.

2.2.4.2 ArrayOfAddonDataSource

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **ArrayOfAddonDataSource** complex type contains an array of **AddonDataSource** elements (section [2.2.4.1](#)).

```
<xs:complexType name="ArrayOfAddonDataSource" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" maxOccurs="unbounded" name="AddonDataSource" nillable="true"
      type="tns:AddonDataSource"/>
  </xs:sequence>
</xs:complexType>
```

AddonDataSource: Specifies an **AddonDataSource** element. This element MUST NOT be null.

2.2.4.3 BaseRequestContract

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **BaseRequestContract** complex type contains information used to specify the request parameters for a protocol server operation to retrieve a **VGSFF** [web drawing](#).

```
<xs:complexType name="BaseRequestContract" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="DataSources" nillable="true"
      type="tns:ArrayOfAddonDataSource"/>
    <xs:element minOccurs="0" name="DisableRefresh" type="xs:boolean"/>
    <xs:element minOccurs="0" name="FileUri" nillable="true" type="xs:anyURI"/>
    <xs:element minOccurs="0" name="PageNumber" type="xs:int"/>
    <xs:element minOccurs="0" name="TimeLastModified" type="xs:dateTime"/>
  </xs:sequence>
</xs:complexType>
```

DataSources: An **ArrayOfAddonDataSource** element (section [2.2.4.2](#)) that specifies the data providers implemented by a protocol client, and used in the web drawing. If there are no data providers, **DataSources** MUST have zero child elements. If **DataSources** has child elements, the **Data** field of each **AddonDataSource** element (section [2.2.4.1](#)) MUST NOT be null.

DisableRefresh: A Boolean that specifies whether the requested drawing page (section [1.3.2](#)) is refreshed by the protocol server. A value of "true" indicates that the returned drawing page is not refreshed; a value of "false" indicates that the returned drawing page is refreshed. There MUST be exactly one instance of this element.

FileUri: An **anyURI** element that specifies the **URL** of the file in a document repository that contains the **VGSFF** web drawing being requested. There MUST be exactly one instance of this element, and it MUST NOT be null.

PageNumber: An integer that specifies the one-based index of a drawing page in the web drawing. It MUST be greater than zero and less than or equal to the total number of drawing pages (section [1.3.2](#)) in the requested web drawing. There MUST be exactly one instance of this element.

TimeLastModified: An optional **dateTime** element that specifies the date and time, in **Coordinated Universal Time (UTC)** format, when the file in a document repository that contains the **VGSFF** web drawing was last modified. If the attribute is present, there MUST be exactly one instance of this element.

2.2.4.4 DiagramBase

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **DiagramBase** complex type contains information used to specify response data for a protocol server operation to retrieve a **VGSFF** [web drawing](#).

```
<xs:complexType name="DiagramBase" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="CacheAge" type="xs:int"/>
    <xs:element minOccurs="0" name="DataSources" nullable="true"
      type="tns:ArrayOfAddonDataSource"/>
  </xs:sequence>
</xs:complexType>
```

CacheAge: An integer that specifies the duration in minutes for which the processed drawing page (section [1.3.2](#)) is cached in memory by the protocol server. It MUST be greater than or equal to zero. There MUST be exactly one instance of this element.

DataSources: An **ArrayOfAddonDataSource** element (section [2.2.4.2](#)) that specifies the data providers implemented by a protocol client, and used in the web drawing. If there are no data providers, **DataSources** MUST have zero child elements. If **DataSources** has child elements, the **Data** field of each **AddonDataSource** element (section [2.2.4.1](#)) MUST NOT be empty.

2.2.4.5 VisioGraphicsServiceFault

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **VisioGraphicsServiceFault** complex type contains information about errors that occur during protocol server operations.

```
<xs:complexType name="VisioGraphicsServiceFault" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="Details" nullable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="Error" type="tns:FaultCode"/>
    <xs:element minOccurs="0" name="Flags" type="xs:int"/>
  </xs:sequence>
</xs:complexType>
```

Details: A string that specifies a detailed description of an error. There MUST be exactly one instance of this element.

Error: A **FaultCode** simple type (section [2.2.5.1](#)) that specifies the type of error. There MUST be exactly one instance of this element.

Flags: An integer that specifies additional information related to the **FaultCode**. A nonzero value indicates an error occurred during mapping **rows** of data to **shapes** when processing the request for a drawing page (section [1.3.2](#)) of a **VGSFF** [web drawing](#). There MUST be exactly one instance of this element. If **FaultCode** is not equal to **DataBindingConflict**, the value MUST be "0x00000000". If **FaultCode** is equal to **DataBindingConflict**, then the value MUST be a bitwise OR combination of one or more of the values in the following table, or the value "0x40000000", which indicates a generic data binding failure.

| Value | Description |
|------------|--|
| 0x00000001 | A column was deleted in the data source . |
| 0x00000002 | A column's data type was changed in the data source. |
| 0x00000004 | A row was deleted in the data source. |
| 0x00000008 | A duplicate row was found in the data source. |

| Value | Description |
|------------|---|
| 0x00000010 | A primary key column was deleted in the data source. |

2.2.5 Simple Types

The following table summarizes the set of common XML schema simple type definitions defined by this specification. XML schema simple type definitions that are specific to a particular operation are described with the operation.

| Simple type | Description |
|------------------|---|
| FaultCode | <p>The FaultCode simple type contains information about a specific error that occurs during a protocol operation.</p> <p>It MUST be a valid value as defined in the table in this section.</p> |

2.2.5.1 FaultCode

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **FaultCode** simple type contains information about a specific error that occurs during a protocol operation.

It MUST be a valid value as defined in the table in this section.

```

<xs:simpleType name="FaultCode" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:restriction base="xs:string">
    <xs:enumeration value="DataConnectivityError"/>
    <xs:enumeration value="DataSourceConnectionError"/>
    <xs:enumeration value="DataSourcePermissionError"/>
    <xs:enumeration value="EmptyRasterDiagramRequest"/>
    <xs:enumeration value="EmptyVectorDiagramRequest"/>
    <xs:enumeration value="OfficeDataConnectionFileNotFoundException"/>
    <xs:enumeration value="OfficeDataConnectionFileRetrievalError"/>
    <xs:enumeration value="OfficeDataConnection FileAccessDenied"/>
    <xs:enumeration value="IncompatibleDomain"/>
    <xs:enumeration value="WssViewAccessDenied"/>
    <xs:enumeration value="WssListAccessDenied"/>
    <xs:enumeration value="InvalidPageNumber"/>
    <xs:enumeration value="InvalidResolution"/>
    <xs:enumeration value="InvalidFileUrl"/>
    <xs:enumeration value="RasterizationError"/>
    <xs:enumeration value="InvalidFileExtension"/>
    <xs:enumeration value="EmptyServerData"/>
    <xs:enumeration value="OpenServerFileFailed"/>
    <xs:enumeration value="NoReadPermissionToFile"/>
    <xs:enumeration value="KeyNotFoundFromCollection"/>
    <xs:enumeration value="ExceededMaxDiagramSize"/>
    <xs:enumeration value="IncompatibleVersion"/>
    <xs:enumeration value="DataProviderNotTrusted"/>
    <xs:enumeration value="DataBindingConflict"/>
    <xs:enumeration value="UnableToGetExternalDataSourceCredentials"/>
    <xs:enumeration value="UnattendedAccountTypeMismatch"/>
    <xs:enumeration value="RecalcTimedOut"/>
    <xs:enumeration value="LicenseExpired"/>
    <xs:enumeration value="InvalidZoomLevel"/>
    <xs:enumeration value="VSDXFfileLoadGenericError"/>
  </xs:restriction>
</xs:simpleType>

```

```

<xs:enumeration value="VSDXFfileLoadPermissionError"/>
<xs:enumeration value="VSDXFfileSizeError"/>
<xs:enumeration value="WebPartConfigError"/>
<xs:enumeration value="EmptyRasterPageRequest"/>
<xs:enumeration value="EmptyRasterPageItemRequest"/>
<xs:enumeration value="VDWNotSupportExternalList"/>
<xs:enumeration value="ExternalListConfigurationNotSupported"/>
<xs:enumeration value="IncompatibleDomain_15"/>
<xs:enumeration value="FileNotLockedOnServer"/>
<xs:enumeration value="FileAlreadyCheckedOutOnServer"/>
<xs:enumeration value="FileAlreadyLockedOnServer"/>
<xs:enumeration value="DocumentCheckoutRequired"/>
<xs:enumeration value="ExcelFileNotInSharePoint"/>
<xs:enumeration value="PageDrawingAreaSizeUnsupported"/>
<xs:enumeration value="PageImageSizeUnsupported"/>
<xs:enumeration value="PageFailToRaster"/>
<xs:enumeration value="CannotRetrieveExternalListData"/>
</xs:restriction>
</xs:simpleType>

```

The following table specifies the allowable values for the **FaultCode** simple type.

| Value | Meaning |
|---|--|
| DataConnectivityError | An error occurred while trying to connect to data sources specified in the document. |
| DataSourceConnectionError | An error occurred while trying to connect to data sources specified in the VSDX Web drawing (section 1.3.1). |
| DataSourcePermissionError | The user does not have permission to connect to data sources specified in the VSDX Web drawing . |
| EmptyRasterDiagramRequest | A required argument to the GetRasterDiagram (section 3.1.4.2) WSDL operation is empty. |
| EmptyVectorDiagramRequest | A required argument to the GetVectorDiagram WSDL operation is empty. |
| OfficeDataConnectionFileNotFoundException | The Office data connection (ODC) file specified in the document could not be found. |
| OfficeDataConnectionFileRetrievalError | The Office data connection (ODC) file URL specified in the document is not a well formed URL as specified in [RFC1738] . |
| OfficeDataConnectionFileAccessDenied | Access to the Office data connection (ODC) file specified in the document was denied. |
| IncompatibleDomain | The specified VGSSF Web drawing is referring to a list data source that is not in a compatible domain . |
| WssViewAccessDenied | The user does not have permissions to the view used as external data source by the web drawing. |
| WssListAccessDenied | The user does not have permissions to the list used as external data source by the web drawing. |
| InvalidPageNumber | The page index is less than one. |
| InvalidResolution | The Resolution specified in RasterDiagramRequestContract (section 3.1.4.1.3.1) is invalid. |
| InvalidFileUrl | Unused and MUST be ignored. |

| Value | Meaning |
|--|---|
| RasterizationError | An error occurred during rasterization of the document. |
| InvalidFileExtension | The file reference does not refer to a file with a valid extension. |
| EmptyServerData | The data in the document is empty or invalid. |
| OpenServerFileFailed | The document could not be opened. |
| NoReadPermissionToFile | Access to the document was denied. |
| KeyNotFoundFromCollection | The names of drawing pages (section 1.3.2) cannot be retrieved from the document. |
| ExceededMaxDiagramSize | The document size exceeded the limit configured by the service administrator. |
| IncompatibleVersion | The document version is incompatible with the server. |
| DataProviderNotTrusted | The document requires a connection to data provider(s) that are not allowed by the service administrator. |
| DataBindingConflict | Unable to update the graphical elements that are mapped to data while processing a request for a drawing page (section 1.3.2) of a VGSFF Web drawing . |
| UnableToGetExternalDataSourceCredentials | Credentials required to connect to data sources (1) specified in the document could not be retrieved. |
| UnattendedAccountTypeMismatch | The default credentials used for connecting to data sources are of invalid type. |
| RecalcTimedOut | The document recalculation duration exceeded the limit configured by the service administrator. |
| LicenseExpired | Visio Graphics Service license has expired. |
| InvalidZoomLevel | Unused and MUST be ignored. |
| VSDXFileLoadGenericError | An error occurred opening the VSDX Web drawing . |
| VSDXFileLoadPermissionError | The user does not have permission to read the VSDX Web drawing . |
| VSDXFileSizeError | The VSDX document size exceeded the limit configured by the service administrator. |
| WebPartConfigError | An invalid request occurred for a VSDX Web drawing . |
| EmptyRasterPageRequest | The rasterPageRequestContract element of the GetRasterPage element (section 3.1.4.3.2.1) is null. |
| EmptyRasterPageItemRequest | The rasterPageItemRequestContract element of the GetRasterPageItem element (section 3.1.4.4.2.1) is null. |
| VDWNotSupportExternalList | A VGSFF Web drawing does not support an external list ([MS-WSSTS] section 2.1.2.7) data source. |
| ExternalListConfigurationNotSupported | The configuration of an external list ([MS-WSSTS] section 2.1.2.7) data source is not supported. |
| IncompatibleDomain_15 | The specified VSDX web drawing (section 1.3.1) is referring to a list ([MS-WSSTS] section 2.1.2.7) data source that is not in a compatible domain. |

| Value | Meaning |
|--------------------------------|---|
| FileNotLockedOnServer | The SaveComments operation (section 3.1.4.5) failed to acquire a lock on the target document. |
| FileAlreadyCheckedOutOnServer | The SaveComments operation (section 3.1.4.5) failed to acquire a lock on the target document because it was checked-out ([MS-WSSTS] section 2.1.2.11.1.3) by a different client. |
| FileAlreadyLockedOnServer | The SaveComments operation (section 3.1.4.5) failed because there is an already existing exclusive lock on the target document or a schema lock with a different schema lock identifier. |
| DocumentCheckoutRequired | The SaveComments operation (section 3.1.4.5) failed because the target document was not checked-out ([MS-WSSTS] section 2.1.2.11.1.3). |
| ExcelFileNotInSharePoint | An Excel file used as data source is not located in a document library ([MS-WSSTS] section 2.1.2.7.1) |
| PageDrawingAreaSizeUnsupported | The protocol server was unable to render the drawing page because it exceeds the supported size limit. |
| PageImageSizeUnsupported | The protocol server was unable to create an image item (section 3.1.1) because the image exceeds the supported size limit. |
| PageFailToRaster | An error has occurred while the protocol server was rendering the VSDX Web drawing . |
| CannotRetrieveExternalListData | The protocol server failed to retrieve data from an external list ([MS-WSSTS] section 2.1.2.7) data source. |

2.2.6 Attributes

This specification does not define any common XML schema attribute definitions.

2.2.7 Groups

This specification does not define any common XML schema group definitions.

2.2.8 Attribute Groups

This specification does not define any common XML schema attribute group definitions.

2.2.9 Common Data Structures

The following table summarizes the set of data structures specific to messages that are associated with **VSDX** web drawings.

| Data Structure | Description |
|-----------------------|---|
| ShapeInfo | A string that is an XML fragment containing information about shapes , drawing pages (section 1.3.2), and web drawing . |
| Comments | A string that is an XML fragment containing comments. |
| CommentData | A string that is an XML fragment containing the comment action input data. |

| Data Structure | Description |
|----------------|---|
| CommentResult | A string that is an XML fragment containing the result of a comment action. |

2.2.9.1 ShapeInfo

The **ShapeInfo** element is a string that specifies information about the shapes (section [1.3.3](#)), drawing pages (section [1.3.2](#)), and web drawing (section [1.3.1](#)) of a **VSDX** web drawing. [<1>](#) The syntax of this data structure is an XML fragment. Elements of this fragment are listed in the following sections.

The set of elements returned is determined by the contents of the **web drawing**, as described in the following table.

| Element | Description |
|----------------|---|
| Page | The information about the requested drawing page, and the information about additional pages in the web drawing. |
| Pages | A list of published foreground pages (section 1.3.2.1) in the web drawing. |
| PageInfo | The information about the identity of a drawing page in the web drawing. |
| ShapeInfo | The information about the relevant shape, including shape data (section 1.3.4), hyperlinks , text and identifying information . A relevant shape is selectable, as specified in [MS-VSDX] section 2.2.3.4, and contains hyperlinks, shape data items, or comments (section 1.3.5). |
| Hyperlinks | The list of each visible hyperlink element associated with a shape. |
| Hyperlink | The hyperlink associated with a shape. |
| ShapeDataItems | The list of visible shape data items associated with a shape. |
| ShapeData | The shape data item associated with a shape. |
| Shapes | The list of geometric outline information for each relevant shape in the web drawing. A relevant shape is selectable, as specified in [MS-VSDX] section 2.2.3.4, and contains hyperlinks, shape data items, or comments. |
| Shape | The geometric outline information for a shape. |
| Path | The geometric outline information in the form of a path. |

2.2.9.1.1 Page

The **Page** complex type specifies information about the shapes (section [1.3.3](#)) on a drawing page (section [1.3.2](#)) in a web drawing (section [1.3.1](#)). One element is returned for the web drawing.

```

<xss:complexType name="Page" xmlns:xss="http://www.w3.org/2001/XMLSchema">
  <xss:sequence>
    <xss:element name="Pages" minOccurs="1" maxOccurs="1" type="Pages"/>
    <xss:element name="ShapeInfo" minOccurs="0" maxOccurs="unbounded" type="ShapeInfo"/>
    <xss:element name="Shapes" minOccurs="0" maxOccurs="1" type="Shapes"/>
  </xss:sequence>
  <xss:attribute name="ContentBounds" type="xs:string" use="required"/>
  <xss:attribute name="DataBindingConflict" type="xs:boolean" use="required"/>
  <xss:attribute name="DocumentID" type="xs:string" use="required"/>

```

```

<xs:attribute name="DocumentTimestamp" type="xs:string" use="required"/>
<xs:attribute name="Name" type="xs:string" use="optional"/>
<xs:attribute name="ReadOnly" type="xs:boolean" use="required"/>
<xs:attribute name="RefreshWarning" type="xs:boolean" use="required"/>
<xs:attribute name="RequiresCheckout" type="xs:boolean" use="optional"/>
<xs:attribute name="UnsupportedFeatures" type="xs:int" use="optional"/>
<xs:attribute name="ViewOnly" type="xs:boolean" use="required"/>
</xs:complexType>

```

ContentBounds: A string that specifies the bounding rectangle of the drawing page as specified in the following table.

| Name | Description |
|--------|--|
| x | An integer that specifies the upper left x-coordinate of the bounding rectangle. |
| y | An integer that specifies the upper left y-coordinate of the bounding rectangle. |
| width | A positive integer that specifies the width of the bounding rectangle. |
| height | A positive integer that specifies the height of the bounding rectangle. |

The coordinates of a bounding rectangle MUST be relative to the top, left corner of the window that contains the drawing page. All the values MUST be specified in **pixels**.

The string MUST be formatted using the **JavaScript Object Notation (JSON)**, as specified in [\[RFC4627\]](#), as follows:

```
{"x":x-val,"y":y-val,"width":width-val,"height":height-val}
```

where **x-val**, **y-val**, **width-val**, and **height-val** are integers specifying the x, y, width, and height fields, respectively.

DataBindingConflict: A Boolean that specifies the status of retrieving data from data providers for the drawing page. The value MUST be one of the following:

| Value | Description |
|-------|--|
| 0 | The drawing page does not have any data binding conflicts. |
| 1 | The drawing page does have data binding conflicts. |

DocumentID: A string that specifies a **GUID** that identifies the file in a document repository that contains the web drawing being requested.

DocumentTimestamp: A string that specifies an opaque identifier for the version of the web drawing. The value MUST NOT be an empty string.

Name: A string that specifies the name of the drawing page. The value MUST NOT be an empty string. It MUST match the **Name** or **NameU** attribute of the **Page_Type** elements in the **Pages XML Part**, as specified in [\[MS-VSDX\]](#) section 2.2.2.1, of the web drawing. It MUST match a name in the **Name** attribute of one of the **PageInfo** child elements of the **Pages** element (section [2.2.9.1.2](#)).

ReadOnly: A Boolean that specifies the read-only state of the file in the document repository. A value of one indicates that the file is read-only; a value of zero indicates the file is not read-only.

RefreshWarning: An optional Boolean that specifies whether the drawing page was refreshed by the protocol server. A nonzero value indicates that data connections exist for the drawing page but that the drawing page was not refreshed from the data providers associated with these data connections.

RequiresCheckout: A Boolean that specifies whether or not the file requires check-out from the document repository. A value of one indicates that the file requires check-out; a value of zero indicates that the file does not require check-out.

UnsupportedFeatures: An integer that specifies features in the file that are not supported by the server. The value MUST be zero, or a bitwise or combination of one or more of the following values.

| Value | Description |
|-------|---|
| 0x01 | The file contains legacy ink. |
| 0x02 | The file contains one or more reviewer pages. |
| 0x04 | The file contains macros. |
| 0x08 | The file contains one or more embedded objects . |
| 0x10 | The file contains unsupported cell recalculations. |

ViewOnly: A Boolean that specifies whether or not the file can be viewed but not opened from the document repository. A value of one indicates that the file is view only and cannot be opened; a value of zero indicates the file can be viewed and opened.

2.2.9.1.2 Pages

The **Pages** complex type specifies all the foreground pages (section [1.3.2.1](#)) in a web drawing (section [1.3.1](#)). **One element is returned in the **Page** element of the web drawing.**

```
<xs:complexType name="Pages" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element name="PageInfo" minOccurs="1" maxOccurs="unbounded" type="PageInfo"/>
  </xs:sequence>
</xs:complexType>
```

2.2.9.1.3 PageInfo

The **Page Info** complex type specifies the identity of a drawing page (section [1.3.2](#)) in the web drawing (section [1.3.1](#)). **One element is returned for each foreground page** (section [1.3.2.1](#)) **within the **Pages** element** (section [2.2.9.1.2](#)).

```
<xs:complexType name="PageInfo" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:attribute name="ID" type="xs:unsignedLong" use="required"/>
  <xs:attribute name="Name" type="xs:string" use="required"/>
</xs:complexType>
```

ID: An unsigned long that specifies the identifier of the drawing page. The value MUST match the **ID** attribute of one of the **Page_Type** elements in the **Pages XML Part**, as specified in [\[MS-VSDX\]](#) section 2.2.2.1, of the web drawing.

Name: A string that specifies the name of the drawing page. The value MUST NOT be an empty string. It MUST match the **Name** or **NameU** attribute of the **Page_Type** elements in the **Pages XML Part**, as specified in [\[MS-VSDX\]](#) section 2.2.2.1, of the web drawing referenced by the **ID** attribute.

2.2.9.1.4 ShapeInfo

The **ShapeInfo** complex type specifies information about a [shape](#). One element is returned for each relevant shape in the [Page element of the web drawing](#).

```
<xs:complexType name="ShapeInfo" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element name="ShapeDataItems" minOccurs="0" maxOccurs="1" type="ShapeDataItems"/>
    <xs:element name="Hyperlinks" minOccurs="0" maxOccurs="1" type="Hyperlinks"/>
  </xs:sequence>
  <xs:attribute name="Name" type="xs:string" use="required"/>
  <xs:attribute name="DisplayName" type="xs:string" use="optional"/>
  <xs:attribute name="Guid" type="xs:string" use="optional"/>
  <xs:attribute name="Layout" type="xs:string" use="required"/>
  <xs:attribute name="ShapeText" type="xs:string" use="optional"/>
  <xs:attribute name="TabOrderString" type="xs:string" use="required"/>
</xs:complexType>
```

Name: A string that specifies the identifier of the shape. It MUST be the **ID** attribute of a shape, as specified in the ShapeSheet_Type, as specified in [\[MS-VSDX\]](#) section 2.3.4.2.88, of the web drawing. It MUST NOT be an empty string, and it MUST be unique amongst all the identifiers specified by the **Name** attribute of the **ShapeInfo** elements in the containing **Page** element.

DisplayName: A string that specifies the display name for the shape. It MUST be the **Name** attribute of a shape, as specified in the ShapeSheet_Type, as specified in [\[MS-VSDX\]](#) section 2.3.4.2.88, of the web drawing, of the shape specified by the **Name** attribute of this **ShapeInfo** element.

Guid : An optional string that specifies a GUID for the shape. If this attribute does not exist, the shape does not have a GUID. If this attribute exists, it MUST be the 32 letters and digits separated by hyphens contained in the **UniqueId** attribute of a shape, as specified in the ShapeSheet_Type, as specified in [\[MS-VSDX\]](#) section 2.3.4.2.88, of the web drawing, of the shape specified by the **Name** attribute of this **ShapeInfo** element.

Layout: A string that specifies the geometric location of the shape. If the shape is 2D, the string specifies the bounding rectangle of the shape on the drawing page as specified in the following table.

| Name | Description |
|--------|--|
| x | An integer that specifies the upper left x-coordinate of the bounding rectangle. |
| y | An integer that specifies the upper left y-coordinate of the bounding rectangle. |
| width | A positive integer that specifies the width of the bounding rectangle. |
| height | A positive integer that specifies the height of the bounding rectangle. |

The string MUST be formatted using the JavaScript Object Notation (JSON) as specified in [\[RFC4627\]](#) as follows:

```
{"type": "2D", "bounds": {"x": x-val, "y": y-val, "width": width-val, "height": height-val}}
```

where **x-val**, **y-val**, **width-val**, and **height-val** are integers specifying the x, y, width, and height fields, respectively.

If the shape is 1D, the string specifies the begin and end coordinates of the shape as specified in the following table.

| Name | Description |
|--------|---|
| beginX | A decimal that specifies the x-coordinate of the beginning of the 1D shape. |

| Name | Description |
|--------|---|
| beginY | A decimal that specifies the y-coordinate of the beginning of the 1D shape. |
| endX | A decimal that specifies the x-coordinate of the end of the 1D shape. |
| endY | A decimal that specifies the y-coordinate of the end of the 1D shape. |

The string MUST be formatted using the JavaScript Object Notation as specified in [RFC4627] as follows:

```
{"type": "1D", "points": {"beginX": beginx-val, "beginY": beginy-val, "endX": endx-val, "endY": endy-val}}
```

where **beginx-val**, **beginy-val**, **endx-val**, and **endy-val** specify the beginX, beginY, endX, and endY fields, respectively.

The coordinates MUST be relative to the top left corner of the window that contains the drawing page (section [1.3.2](#)). All the values MUST be specified in pixels.

ShapeText: An optional string that specifies a text element. If this attribute exists, it is composed of information from the document, shape data items, recalculations on shape data items and formatting information, for a shape.

TabOrderString: A string that specifies the tab order of this shape on the drawing page. The format of the string MUST be "rowIndex_columnIndex", where rowIndex and columnIndex are unsigned integer values separated by an underscore "_".

2.2.9.1.5 Hyperlinks

The **Hyperlinks** complex type specifies each **Hyperlink** element (section [2.2.9.1.6](#)) associated with a **shape**.

```
<xs:complexType name="Hyperlinks" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element name="Hyperlink" minOccurs="1" maxOccurs="unbounded" type="Hyperlink"/>
  </xs:sequence>
</xs:complexType>
```

2.2.9.1.6 Hyperlink

The **Hyperlink** complex type specifies a hyperlink associated with a shape (section [1.3.3](#)). One element is returned for each visible hyperlink associated with the shape within a **ShapeInfo** element (section [2.2.9.1](#)).

```
<xs:complexType name="Hyperlink" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:attribute name="Name" type="xs:string" use="required"/>
  <xs:attribute name="Value" type="xs:string" use="optional"/>
  <xs:attribute name="Description" type="xs:string" use="optional"/>
  <xs:attribute name="SubAddress" type="xs:string" use="optional"/>
  <xs:attribute name="SubAddressShape" type="xs:string" use="optional"/>
  <xs:attribute name="Zoom" use="optional">
    <xs:simpleType>
      <xs:union>
        <xs:simpleType>
          <xs:restriction base="xs:int">
            <xs:minExclusive value="0"/>
          </xs:restriction>
        </xs:simpleType>
      </xs:union>
    </xs:simpleType>
  </xs:attribute>
</xs:complexType>
```

```

<xs:simpleType>
  <xs:restriction base="xs:int">
    <xs:enumeration value="-2"/>
    <xs:enumeration value="-1"/>
  </xs:restriction>
</xs:simpleType>
</xs:union>
</xs:simpleType>
</xs:attribute>
<xs:attribute name="Default" type="xs:boolean" use="optional"/>
</xs:complexType>

```

Name: A string attribute that specifies an identifier for a hyperlink. It MUST NOT be an empty string, and it MUST be unique among the identifiers specified by the **Name** attribute of the hyperlink elements in this XML part.

Value: An optional string attribute that specifies the URI of an external resource referenced by the hyperlink. If this attribute exists, it MUST NOT be an empty string, and the **SubAddress**, **SubAddressShape**, and **Zoom** elements MUST be ignored. If this attribute does not exist, **SubAddress** MUST exist.

Description: An optional string attribute that specifies the description of the hyperlink. If this attribute does not exist, the hyperlink does not have a description.

SubAddress: An optional string attribute that specifies the identifier of the drawing page (section 1.3.2) referenced by this hyperlink within the web drawing (section 1.3.1). If this attribute exists, it MUST NOT be an empty string. If this attribute does not exist, the **SubAddressShape** and **Zoom** elements MUST be ignored.

SubAddressShape: An optional string attribute that specifies the identifier of the shape referenced by this hyperlink within the drawing page specified by **SubAddress**. If this attribute exists, it MUST NOT be an empty string. If this attribute does not exist, the hyperlink references the entire drawing page.

Zoom: An optional integer attribute that specifies the **zoom level** for the drawing page specified by **SubAddress**. If this attribute does not exist, the zoom level is 100%. If this attribute does exist, it MUST be a value from the following table.

| Value | Description |
|-------|--|
| -2 | The drawing page is zoomed to fit the width of the view. |
| -1 | The drawing page is zoomed to fit in the view. |
| n > 0 | The drawing page is zoomed to n%. n MUST be greater than zero. |

Default: An optional **Boolean** attribute that specifies the default hyperlink associated with the shape. It MUST be true if and only if this hyperlink is the default. Each shape MUST NOT have more than one default hyperlink.

2.2.9.1.7 ShapeDataItems

The **ShapeDataItems** complex type specifies a list of [shape](#) data items, as specified in [\[MS-VSDX\]](#) section 2.2.3.6. One element is returned for visible shape data items associated with a shape within a **ShapeInfo** element (section 2.2.9.1).

```

<xs:complexType name="ShapeDataItems" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element name="ShapeData" minOccurs="1" maxOccurs="unbounded" type="ShapeData"/>
  </xs:sequence>

```

```
</xs:complexType>
```

2.2.9.1.8 ShapeData

The **ShapeData** complex type specifies a [shape](#) data item, as specified in [MS-VSDX] section 2.2.3.6. One element is returned for each visible [shape data item associated with the shape with a ShapeInfo element](#) (section [2.2.9.1](#)).

```
<xs:complexType name="ShapeData" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:attribute name="Name" type="xs:string" use="required"/>
  <xs:attribute name="FormattedValue" type="xs:string" use="required"/>
  <xs:attribute name="Value" type="xs:string" use="optional"/>
  <xs:attribute name="Format" type="xs:string" use="optional"/>
</xs:complexType>
```

Name: A string that is determined by a combination of shape data row properties that specifies the label of the shape data item.

FormattedValue: A string representation of the value of the data formatted for display. It MUST NOT be an empty string.

Value: An optional string that specifies the value of the shape data item, as specified in [MS-VSDX] section 2.2.3.6.

Format: An optional string that specifies a vFormatString custom structure, as specified in [MS-VSDX] section 2.5.9.6. If this attribute exists, it is used to format the value for display.

2.2.9.1.9 Shapes

The **Shapes** complex type specifies the geometric outline information for multiple [shapes](#). One element is returned for the [web drawing](#).

```
<xs:complexType name="Shapes" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element name="Shape" minOccurs="1" maxOccurs="unbounded" type="Shape"/>
  </xs:sequence>
</xs:complexType>
```

2.2.9.1.10 Shape

The **Shape** complex type specifies the geometric outline information for a [shape](#). One element is returned for each relevant shape.

```
<xs:complexType name="Shape" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element name="Path" minOccurs="1" maxOccurs="1" type="Path"/>
  </xs:sequence>
  <xs:attribute name="Name" type="xs:string" use="required"/>
</xs:complexType>
```

Name: A string that specifies the identifier of the **ShapeInfo** element (section [2.2.9.1.1](#)) in the **Page** structure (section [2.2.9.1.1](#)) that this element represents. It MUST match exactly the **Name** of a **ShapeInfo** element in the **Pages** element of this **Page** structure.

2.2.9.1.11 Path

The **Path** complex type specifies the geometric outline information for a [shape](#). One element is returned for a **Shape** element.

```
<xs:complexType name="Path" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:attribute name="Shape" type="xs:string" fixed="poly"/>
  <xs:attribute name="Data" use="required">
    <xs:simpleType>
      <xs:restriction base="xs:string">
        <xs:pattern value="\d*,\d*\{3,\}" />
      </xs:restriction>
    </xs:simpleType>
  </xs:attribute>
</xs:complexType>
```

Shape: A string that specifies the type of outline. It MUST be equal to "poly".

Data: A string that specifies the Cartesian coordinates of the outline. It MUST have the following format:

x1,y1,x2,y2...xn,yn

The fields xn and yn MUST be integer values, and they MUST occur in pairs. Each xn,yn pair specifies the coordinates of a point that defines one vertex of the outline. The outline is formed by connecting the points in the order they appear in this string attribute. There MUST be at least 4 points. The first point MUST equal the last point. The coordinates MUST be measured in pixels relative to the top, left corner of the drawing page (section [1.3.2](#)) that contains the shape. All values MUST be separated by commas.

2.2.9.2 Comments

The **Comments** element is a string that specifies information about the [comments](#) in a drawing page (section [1.3.2](#)).[<2>](#) The syntax of this data structure is an XML fragment. Elements of this fragment are listed in the following sections.

2.2.9.2.1 Comments

The **Comments** complex type specifies all [comment](#) information for a drawing page (section [1.3.2](#)). There MUST be zero or exactly one instance of this element.

```
<xs:complexType name="comments" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="1" maxOccurs="unbounded" name="CommentEntry"/>
  </xs:sequence>
</xs:complexType>
```

The **Comments** element MUST contain one or more **CommentEntry** elements as specified in section [2.2.9.2.2](#).

2.2.9.2.2 CommentEntry

The **CommentEntry** complex type specifies a comment (section [1.3.5](#)) on a drawing page (section [1.3.2](#)).

```
<xs:complexType name="CommentEntry" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:simpleContent>
    <xs:extension base="xs:string">
```

```

<xs:attribute name="CommentID" type="xs:string" use="required"/>
<xs:attribute name="Author" type="xs:string" use="required"/>
<xs:attribute name="ShapeID" type="xs:string" use="required"/>
<xs:attribute name="CreationDate" type="xs:string" use="required"/>
<xs:attribute name="ModifiedDate" type="xs:string" use="required"/>
<xs:attribute name="Done" type="xs:string" use="required"/>
</xs:extension>
</xs:simpleContent>
</xs:complexType>

```

CommentID: An integer attribute that specifies the identifier of this comment. It MUST be greater than or equal to zero. It MUST be unique across all the **CommentEntry** elements in the containing **Comments** element (section [2.2.9.2](#)). It MUST match the value of a **CommentID** attribute in a **CommentEntry_Type** element, as specified in [MS-VSDX] section 2.3.4.2.9, in the containing drawing page.

Author: A string attribute that specifies the display name of the author of this comment. The value MUST match the value of the **Name** attribute of an **AuthorEntry_Type**, as specified [MS-VSDX] section 2.3.4.2.2.

ShapeID: An integer attribute that specifies the identifier of the shape (section [1.3.3](#)) this comment is associated with. If no **ShapeID** is specified or if **ShapeID** is zero, the comment refers to the drawing page. If the attribute exists and is not zero, it MUST match the value of the **ID** attribute of a shape, as specified in the **ShapeSheet_Type**, as specified in [MS-VSDX] section 2.3.4.2.88, of the web drawing (section [1.3.1](#)).

CreationDate: A **dateTime** attribute that specifies the date and time, in Coordinated Universal Time (UTC) format, of when the comment was created.

ModifiedDate: A **dateTime** attribute that specifies the date and time, in Coordinated Universal Time (UTC) format, of when the comment was last modified. This attribute MUST be greater than or equal to the value of **CreationDate**.

Done: A **Boolean** attribute that specifies the current state of the comment. A value of "true" indicates that the comment is completed; a value of "false" indicates that the comment is not completed.

2.2.9.3 CommentData

The **CommentData** attribute is a string that specifies a save comment action and the comment (section [1.3.5](#)) data for a shape (section [1.3.3](#)) or drawing page (section [1.3.2](#)) in the **VSDX** web drawing (section [1.3.1](#)).[**<3>**](#) The syntax of this data structure is an XML fragment. Elements of this fragment are listed in the following sections.

2.2.9.3.1 Comment

The **Comment** complex type specifies a comment (section [1.3.5](#)) for a shape or drawing page (section [1.3.2](#)) in a **VSDX** web drawing (section [1.3.1](#)). There MUST be exactly one instance of this element, and it MUST NOT be null.

The value of the **Comment** element is a string with the comment text. Additional attributes define properties and actions for the comment.

```

<xs:complexType name="Comment" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:simpleContent>
    <xs:extension base="xs:string">
      <xs:attribute name="Action" type="xs:string" use="required"/>
      <xs:attribute name="PageID" type="xs:integer" use="required"/>
      <xs:attribute name="ShapeID" type="xs:integer"/>
    </xs:extension>
  </xs:simpleContent>
</xs:complexType>

```

```

<xs:attribute name="CommentID" type="xs:integer"/>
<xs:attribute name="Author" type="xs:string"/>
<xs:attribute name="ModifiedDate" type="xs:dateTime"/>
</xs:extension>
</xs:simpleContent>
</xs:complexType>

```

Action: A string attribute that specifies the action to perform. This attribute MUST exist, and it MUST be one of the following values.

| Value | Description |
|----------|---|
| "Add" | Write a new comment into the file using the contents and attributes of this element. |
| "Edit" | Edit an existing comment by modifying the file using the contents and attributes of this element. |
| "Delete" | Remove a comment from the file. |
| "Done" | Mark an existing comment as complete in the file. |

PageID: An integer attribute that identifies the drawing page in the **VSDX** web drawing specified by **fileUrl** that the comment is on.

ShapeID: An integer attribute that specifies the identifier of the shape (section [1.3.3](#)), within the drawing page specified by **PageID**, this comment is associated with. If no **ShapeID** is specified or if **ShapeID** is zero, the comment refers to the drawing page specified by **PageID**.

CommentID: An integer attribute that specifies the identifier of the comment. If the **Action** value is "Edit", "Delete" or "Done", this attribute MUST exist, and the value MUST match the value of the **CommentID** attribute of a **CommentEntry_Type**, as specified in [\[MS-VSDX\]](#) section 2.3.4.2.9, in the **VSDX** web drawing specified by **fileUrl**.

Author: A string attribute that specifies the display name of the author of this comment. If the **Action** value is "Add" or "Edit", this attribute MUST exist, and it MUST NOT be empty.

ModifiedDate: A **dateTime** attribute that specifies the date and time, in Coordinated Universal Time (UTC) format, of when the comment was last modified. If the **Action** value is "Delete" or "Edit", this attribute MUST exist, and it MUST NOT be null.

2.2.9.4 CommentResult

The **CommentResult** element is a string that specifies the result of the **SaveComments** operation (section [3.1.4.5](#)). The syntax of this data structure is an XML fragment. Elements of this fragment are listed in the following sections.

2.2.9.4.1 Comment

The **Comment** complex type specifies the result of a comment action (section [1.3.5](#)) in the **VSDX** web drawing (section [1.3.1](#)). The value of the **Comment** element is a string with comment text. Additional attributes define the properties and actions for the comment response.

```

<xs:complexType name="Comment" xmlns:xs="http://www.w3.org/2001/XMLSchema">
<xs:simpleContent>
<xs:extension base="xs:string">
<xs:attribute name="Action" type="xs:string" use="required"/>
<xs:attribute name="ShapeID" type="xs:integer"/>
<xs:attribute name="CommentID" type="xs:integer"/>
<xs:attribute name="Author" type="xs:string"/>

```

```

<xs:attribute name="CreationDate" type="xs:dateTime"/>
<xs:attribute name="ModifiedDate" type="xs:dateTime"/>
<xs:attribute name="Done" type="xs:boolean"/>
</xs:extension>
</xs:simpleContent>
</xs:complexType>

```

Action: A string attribute that specifies the action performed. It MUST exist, and it MUST be one of the following values:

| Value | Description |
|----------|---------------------------------------|
| "Add" | Add a new comment. |
| "Edit" | Edit an existing comment. |
| "Delete" | Delete an existing comment. |
| "Done" | Mark an existing comment as complete. |

ShapeID: An integer attribute that specifies the identifier of a shape (section [1.3.3](#)) that this comment is associated with. If no **ShapeID** is specified or if **ShapeID** is zero, the comment refers to the drawing page (section [1.3.2](#)).

CommentID: An integer attribute that specifies the identifier of the comment. If the **Action** value is "Add" or "Edit", this attribute MUST exist, and the value MUST match the value of the **CommentID** attribute of a **CommentEntry_Type**, as specified in [\[MS-VSDX\]](#) section 2.3.4.2.9, in the **VSDX** web drawing specified by **fileUrl**.

Author: A string attribute that specifies the display name of the author of this comment. If the **Action** value is "Add", this attribute MUST exist, and it MUST NOT be empty.

CreationDate: A **dateTime** attribute that specifies the date and time, in Coordinated Universal Time (UTC) format, of when the comment was created. If the **Action** value is "Add" or "Edit", this attribute MUST exist, and it MUST NOT be null.

ModifiedDate: A **dateTime** attribute that specifies the date and time, in Coordinated Universal Time (UTC) format, of when the comment was last modified. If the **Action** value is "Delete" or "Edit", this attribute MUST exist, and it MUST NOT be null.

Done: A **Boolean** attribute that specifies the current state of the comment. If the **Action** value is "Done", this attribute MUST exist. A value of "true" indicates that the comment is completed; a value of "false" indicates that the comment has not been completed.

3 Protocol Details

In the following sections, the schema definition might differ from the processing rules imposed by the protocol. The WSDL in this specification matches the WSDL that shipped with the product and provides a base description of the schema. The text that introduces the WSDL might specify differences that reflect actual Microsoft product behavior. For example, the schema definition might allow for an element to be **empty**, **null**, or **not present** but the behavior of the protocol as specified restricts the same elements to being **non-empty**, **not null**, and **present**.

Except where specified, protocol clients MUST interpret HTTP **Status-Codes** returned by the protocol server as specified in [\[RFC2616\]](#) (section 10, Status Code Definitions).

This protocol allows protocol servers to notify protocol clients of application-level faults using SOAP faults. Except where specified, these SOAP faults are not significant for interoperability, and protocol clients can interpret them in an implementation-specific manner.

This protocol allows protocol servers to perform implementation-specific authorization checks, and notify protocol clients of authorization faults either using HTTP Status-Codes or using SOAP faults as specified previously in this section.

3.1 Common Details

The **GetRasterDiagram** (section [3.1.4.1](#)) and **GetVectorDiagram** (section [3.1.4.2](#)) WSDL operations are independent and stateless. The protocol server returns the requested drawing page (section [1.3.2](#)) of the specified **VGSFF web drawing** in raster and vector format, respectively. There are no interaction dependencies between instances of client and server.

The **GetRasterPage** (section [3.1.4.3](#)) and **GetRasterPageItem** (section [3.1.4.4](#)) WSDL operations are related and require client state. A drawing page (section [1.3.2](#)) of a **VSDX** web drawing in raster format is retrieved in full as a result of a message sequence, as illustrated in the following high-level sequence diagram:




Figure 2: Communication message sequence for retrieving a drawing page of a VSDX web drawing in raster format

First, the protocol client sends an **IVisioGraphicsService_GetRasterPage_InputMessage** request (section 3.1.4.3.1.1) WSDL message that MUST be unconditional, as specified in section 3.1.1. The protocol server initiates the process of retrieving or generating the drawing page. The client waits for the server to respond with the **IVisioGraphicsService_GetRasterPage_OutputMessage** (section 3.1.4.3.1.2) response WSDL message that contains drawing page information and includes a message sequence identifier. This message sequence identifier is set in the **SequenceId** element of the **RasterPageTag** complex type (section 3.1.4.3.3) and is contained in the **EntityTag** element of the **RasterPageResponse** complex type (section 3.1.4.3.2).

Then, the protocol client sends a sequence of **IVisioGraphicsService_GetRasterPageItem_InputMessage** request (section 3.1.4.4.1.1) WSDL messages, one for each item, as specified in section 3.1.1, of the drawing page. The client MUST set the value of the **SequenceId** element of the **RasterPageItemRequest** complex type (section 3.1.4.4.3.1), to the message sequence identifier obtained in the preceding **IVisioGraphicsService_GetRasterPage_OutputMessage** response WSDL message. These requests are independent and can be sent asynchronously in any order. The protocol server uses the message sequence identifier to match the requests with the drawing page retrieved or generated as result of the **IVisioGraphicsService_GetRasterPage_InputMessage** request WSDL message that initiated the conversation. The server responds to each of these requests with a corresponding **IVisioGraphicsService_GetRasterPageItem_OutputMessage** response (section 3.1.4.4.1.2) WSDL message that contains information about the requested item, as specified in section 3.1.1, of the drawing page.

The **SaveComments** WSDL operation (section [3.1.4.5](#)) is independent and stateless. The protocol server makes the requested [comment](#) updates and saves them to the specified web drawing. This web drawing file MUST conform to the format specified in [\[MS-VSDX\]](#) section 2.2.9.

3.1.1 Abstract Data Model

There is no abstract data model for a **VGSFF** [web drawing](#).

A drawing page (section [1.3.2](#)) of a **VSDX** web drawing in raster format is composed of 6 **items**: 4 images in Portable Network Graphics (PNG) format, as specified in [\[RFC2083\]](#), the [shape](#) information in XML format, as specified in section [2.2.9.1](#), and [comments](#) in XML format, as specified in section [2.2.9.2.<5>](#). Each image represents the drawing page in different sizes, as specified by the **ItemName** element of the **RasterPageItemRequest** complex type (section [3.1.4.4.3.1](#)).

An **IVisioGraphicsService_GetRasterPage_InputMessage** request (section [3.1.4.3.1.1](#)) or an **IVisioGraphicsService_GetRasterPageItem_InputMessage** request (section [3.1.4.4.1.1](#)) WSDL message is unconditional if the value of the **EntityTag** element of the corresponding complex types **RasterPageRequest** (section [3.1.4.3.3.1](#)) and **RasterPageItemRequest** (section [3.1.4.4.3.1](#)), respectively, is null or empty, as specified by the **RasterPageTag** complex type (section [3.1.4.3.3.3](#)) and the **RasterPageItemTag** complex type (section [3.1.4.4.3.2](#)) respectively. Otherwise, the requesting WSDL message is conditional. Message sequencing rules for conditional messages are specified in [3.1.4](#).

After the initial request for a drawing page of a **VSDX** web drawing is processed and before returning the result to the protocol client, the protocol server caches it for future use. Subsequent requests for the same drawing page are served directly from this cache. The protocol server assigns a unique identifier, **OutputETag** element, to each version of a drawing page in the cache. The protocol server also assigns a unique identifier, **FileETag** element, for the current version of the web drawing that contains this drawing page in the cache. The **OutputETag** and **FileETag** are included in the **EntityTag** element of the **RasterPageResponse** complex type (section [3.1.4.3.3.2](#)). The **EntityTag** received by a client can be used on subsequent conditional requests to determine if the version of the drawing page cached on the client needs to be updated. The protocol server compares the **FileETag** and **OutputETag** from the **EntityTag** of the conditional **RasterPageTag** with the current **FileETag** and **OutputETag**, respectively, of the cached drawing page. If both elements match, the server returns a **RasterPageResponse** having the response code "NotModified"; otherwise, it generates a new drawing page.

3.1.2 Timers

The **Recalculation Timeout** timer measures the time it takes for the protocol server to recalculate the drawing page (section [1.3.2](#)) of a [web drawing](#). This timeout is configured on the protocol server.

The **Message Sequence Timeout** timer measures the time it takes for the protocol server to receive an **IVisioGraphicsService_GetRasterPageItem_InputMessage** request (section [3.1.4.4.1.1](#)) WSDL message beginning when the **IVisioGraphicsService_GetRasterPage_OutputMessage** response (section [3.1.4.3.1.2](#)) WSDL message is sent, in the sequence of messages to retrieve a drawing page of a **VSDX** web drawing in raster format, as specified in section [3.1.<6>](#). This timeout is set to one minute, and it is not configurable on the protocol server.

3.1.3 Initialization

None.

3.1.4 Message Processing Events and Sequencing Rules

The protocol operations can be executed in any order with the following restrictions:

- To fully retrieve a drawing page (section 1.3.2) of a **VSDX** web drawing in raster format, the protocol client MUST follow the message sequence specified and illustrated in section 3.1.
- The protocol client can cache a fully retrieved drawing page of a **VSDX** web drawing in raster format. Furthermore, it can use the information set by the protocol server in the **EntityTag** element of the **RasterPageResponse** complex type (section 3.1.4.3.3.2) and send it back to the server in the **EntityTag** element of a subsequent **RasterPageRequest** complex type (section 3.1.4.3.3.1) in a conditional message. Based on that information, if the server decides that the drawing page has not changed, it responds with a **RasterPageResponse** having the response code "NotModified". Similarly the client can use the information set by the server in the **EntityTag** element of a **RasterPageItemResponse** complex type (section 3.1.4.4.3.3) and send it back to the server in the **EntityTag** element of a subsequent **RasterPageItemRequest** complex type (section 3.1.4.4.3.1) in a conditional message. If the server decides that the requested item, as specified in section 3.1.1, of the drawing page has not changed, it responds with a **RasterPageItemResponse** having the response code "NotModified". In these cases, the server expects the client will use the drawing page data that it cached previously. This mechanism reduces network traffic.
- If a **GetRasterPageItem** operation (section 3.1.4.4) is not preceded by a **GetRasterPage** operation (section 3.1.4.3) or the protocol server cannot match the value of the **SequenceId** element of the **RasterPageItemRequest**, as specified in section 3.1, it MUST return a **RasterPageItemResponse** with the response code "NotModified".

The following table summarizes the list of operations as defined by this specification.

| Operation | Description |
|--------------------------|--|
| GetRasterDiagram | The GetRasterDiagram operation retrieves a drawing page (section 1.3.2) from the VGSFF web drawing (section 1.3.1) rendered in a raster format. |
| GetRasterPage | The GetRasterPage operation retrieves information about a drawing page (section 1.3.2) of a VSDX web drawing rendered in raster format. <7> |
| GetRasterPageItem | The GetRasterPageItem operation retrieves an item, as specified in section 3.1.1, of a drawing page (section 1.3.2) of a VSDX web drawing rendered in raster format. <8> |
| GetVectorDiagram | The GetVectorDiagram operation retrieves a drawing page (section 1.3.2) from the VGSFF web drawing rendered in a vector format. |
| SaveComments | The SaveComments operation saves a comment to a VSDX web drawing in a document repository, in the form of a CommentEntry_Type element as specified [MS-VSDX] section 2.3.4.2.9. <9> |

3.1.4.1 GetRasterDiagram

The **GetRasterDiagram** operation retrieves a drawing page (section 1.3.2) from the **VGSFF** web drawing (section 1.3.1) rendered in a raster format.

The following is the WSDL port type specification of the **GetRasterDiagram** WSDL operation.

```
<wsdl:operation name="GetRasterDiagram" xmlns:wsdl="http://schemas.xmlsoap.org/wsdl/">
  <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterDiagram"
  message="tns2:IVisioGraphicsService_GetRasterDiagram_InputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:output
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterDiagramResponse"
  message="tns2:IVisioGraphicsService_GetRasterDiagram_OutputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
```

```

<wsdl:fault
wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterDiagramVisioGraphicsServiceFault"
name="VisioGraphicsServiceFaultFault"
message="tns2:IVisioGraphicsService_GetRasterDiagram_VisioGraphicsServiceFaultFault_FaultMessage"
xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
</wsdl:operation>

```

The protocol client sends an **IVisioGraphicsService_GetRasterDiagram_InputMessage** request (section [3.1.4.1.1.1](#)) WSDL message, and the protocol server MUST respond with an **IVisioGraphicsService_GetRasterDiagram_OutputMessage** response (section [3.1.4.1.1.2](#)) WSDL message as follows:

1. If the protocol server determines that an error occurred during the protocol server operation, the protocol server MUST respond with a **VisioGraphicsServiceFault** complex type (section [2.2.4.5](#)) SOAP fault with the **Error** field set to the correct **FaultCode** value (section [2.2.5.1](#)).
2. Otherwise, the protocol server MUST return a **RasterDiagram** complex type (section [3.1.4.1.3.2](#)).

If the requested drawing page contains data providers to be implemented by the protocol client, the following sequence of messages MUST be followed:

1. The protocol server MUST respond with an **IVisioGraphicsService_GetRasterDiagram_OutputMessage** response WSDL message. The data providers MUST be specified in the **DataSources** element of the **RasterDiagram** contained within this response. The **Image** element of this **RasterDiagram** MUST be null.
2. The protocol client MUST retrieve the data from the data providers and send another **IVisioGraphicsService_GetRasterDiagram_InputMessage** request WSDL message. This request MUST be identical to the original request except that the **DataSources** element of the **RasterDiagramRequestContract** complex type (section [3.1.4.1.3.1](#)) MUST NOT be null.
3. The protocol server MUST respond with an **IVisioGraphicsService_GetRasterDiagram_OutputMessage** response WSDL message. If no errors occurred, the response MUST contain a **RasterDiagram**, and the **Image** element of the **RasterDiagram** MUST NOT be null.

3.1.4.1.1 Messages

The following table summarizes the set of WSDL message definitions that are specific to this operation.

| Message | Description |
|---|---|
| IVisioGraphicsService_GetRasterDiagram_InputMessage | The request WSDL message for the GetRasterDiagram WSDL operation. |
| IVisioGraphicsService_GetRasterDiagram_OutputMessage | The response WSDL message for the GetRasterDiagram WSDL operation. |
| IVisioGraphicsService_GetRasterDiagram_VisioGraphicsServiceFaultFault_FaultMessage | The fault WSDL message for the GetRasterDiagram WSDL operation. |

| Message | Description |
|---------|-------------|
| | operation. |

3.1.4.1.1.1 IVisioGraphicsService_GetRasterDiagram_InputMessage

The request WSDL message for the **GetRasterDiagram** WSDL operation.

The **SOAP action** value is:

```
http://tempuri.org/IVisioGraphicsService/GetRasterDiagram
```

The **SOAP body** contains the **GetRasterDiagram** element.

3.1.4.1.1.2 IVisioGraphicsService_GetRasterDiagram_OutputMessage

The response WSDL message for the **GetRasterDiagram** WSDL operation.

The SOAP body contains the **GetRasterDiagramResponse** element.

3.1.4.1.1.3 IVisioGraphicsService_GetRasterDiagram_VisioGraphicsServiceFaultFaultMessage

The fault WSDL message for the **GetRasterDiagram** WSDL operation.

The SOAP body contains the **VisioGraphicsServiceFault** element.

3.1.4.1.2 Elements

The following table summarizes the XML schema element definitions that are specific to this operation.

| Element | Description |
|---------------------------------|---|
| GetRasterDiagram | The input data for the GetRasterDiagram WSDL operation. |
| GetRasterDiagramResponse | The result data for the GetRasterDiagram WSDL operation. |

3.1.4.1.2.1 GetRasterDiagram

The **GetRasterDiagram** element specifies the input data for the **GetRasterDiagram** WSDL operation.

```
<xs:element name="GetRasterDiagram" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        minOccurs="0" name="rasterDiagramRequestContract" nillable="true"
        type="tns:RasterDiagramRequestContract"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

rasterDiagramRequestContract: The request parameters for a **GetRasterDiagram** WSDL operation (section [3.1.4.1](#)). There MUST be exactly one instance of this element.

3.1.4.1.2.2 GetRasterDiagramResponse

The **GetRasterDiagramResponse** element specifies the result data for the **GetRasterDiagram** WSDL operation.

```
<xs:element name="GetRasterDiagramResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        minOccurs="0" name="GetRasterDiagramResult" nillable="true" type="tns:RasterDiagram"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

GetRasterDiagramResult: The results for a **GetRasterDiagram** WSDL operation (section [3.1.4.1](#)). There MUST be exactly one instance of this element.

3.1.4.1.3 Complex Types

The following table summarizes the XML schema complex type definitions that are specific to this operation.

| Complex type | Description |
|-------------------------------------|--|
| RasterDiagram | The response data from the GetRasterDiagram WSDL operation. |
| RasterDiagramRequestContract | The input data for the GetRasterDiagram WSDL operation. |

3.1.4.1.3.1 RasterDiagramRequestContract

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterDiagramRequestContract** complex type contains information used to specify the request parameters for a **GetRasterDiagram** WSDL operation (section [3.1.4.1](#)). This complex type inherits from the **BaseRequestContract** complex type, as specified in section [2.2.4.3](#), which specifies additional parameters.

```
<xs:complexType name="RasterDiagramRequestContract">
  xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexContent mixed="false">
    <xs:extension base="tns:BaseRequestContract">
      <xs:sequence>
        <xs:element minOccurs="0" name="Resolution" type="xs:int"/>
      </xs:sequence>
    </xs:extension>
  </xs:complexContent>
</xs:complexType>
```

Resolution: An integer that is unused, and MUST be equal to 1 or 2.

3.1.4.1.3.2 RasterDiagram

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterDiagram** complex type contains information used to specify the response for a **GetRasterDiagram** WSDL operation (section [3.1.4.1](#)). This complex type inherits from the **DiagramBase** complex type, as specified in section [2.2.4.4](#), which specifies additional parameters.

```

<xs:complexType name="RasterDiagram" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexContent mixed="false">
    <xs:extension base="tns:DiagramBase">
      <xs:sequence>
        <xs:element minOccurs="0" name="AreaMaps" nillable="true" type="xs:string"/>
        <xs:element minOccurs="0" name="Image" nillable="true" type="xs:base64Binary"/>
        <xs:element minOccurs="0" name="ShapeInfo" nillable="true" type="xs:string"/>
      </xs:sequence>
    </xs:extension>
  </xs:complexContent>
</xs:complexType>
```

AreaMaps: A string that specifies the geometric outline information of the shapes, as specified in section [1.3.3](#), in the raster image. The format of this data is specified in [\[RFC1980\]](#). There MUST be exactly one instance of this element.

Image: A base64Binary that specifies the drawing page, as specified in section [1.3.2](#), as a raster image in PNG format, as specified in [\[RFC2083\]](#). There MUST be exactly one instance of this element.

ShapeInfo: A string that specifies information about the shapes, as specified in section 1.3.3, in the drawing page, as specified in section 1.3.2. There MUST be exactly one instance of this element.

The syntax of this element is specified in [\[MS-VGSFF\]](#) section 2.4.8. The syntax of this element is also specified by additional attributes of the **CT_Page** element, as specified in [\[MS-VGSFF\]](#) section 2.4.8.2.8, that are listed in the following table.

| Attribute of CT_Page element | Description |
|------------------------------|---|
| Conflict | An optional integer that specifies the status of retrieving data from data providers for the drawing page (section 1.3.2). |
| DocumentID | A string that specifies a GUID that identifies the file in a document repository that contains the VGSFF web drawing that is being requested. |
| DocumentTimestamp | A long value that specifies the number of ticks (10,000 per millisecond) that elapsed between 12:00:00 midnight, January 1, 0001 and when the file in a document repository that contains the VGSFF web drawing was last modified in the document repository. |
| RefreshWarning | An optional integer that specifies whether the drawing page was refreshed by the protocol server. If this attribute is present, a value of one indicates that data connections exist for the drawing page, but that the drawing page was not refreshed from the data providers associated with these data connections. |

3.1.4.1.4 Simple Types

None.

3.1.4.1.5 Attributes

None.

3.1.4.1.6 Groups

None.

3.1.4.1.7 Attribute Groups

None.

3.1.4.2 GetVectorDiagram

The **GetVectorDiagram** operation retrieves a drawing page (section [1.3.2](#)) from the **VGSFF web drawing** rendered in a vector format.

The following is the WSDL port type specification of the **GetVectorDiagram** WSDL operation.

```
<wsdl:operation name="GetVectorDiagram" xmlns:wsdl="http://schemas.xmlsoap.org/wsdl/">
  <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetVectorDiagram"
  message="tns2:IVisioGraphicsService_GetVectorDiagram_InputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:output
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetVectorDiagramResponse"
  message="tns2:IVisioGraphicsService_GetVectorDiagram_OutputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:fault
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetVectorDiagramVisioGraphicsServiceFault"
  name="VisioGraphicsServiceFaultFault"
  message="tns2:IVisioGraphicsService_GetVectorDiagram_VisioGraphicsServiceFaultFault_FaultMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
</wsdl:operation>
```

The protocol client sends an **IVisioGraphicsService_GetVectorDiagram_InputMessage** request (section [3.1.4.2.1.1](#)) WSDL message, and the protocol server MUST respond with an **IVisioGraphicsService_GetVectorDiagram_OutputMessage** response (section [3.1.4.2.1.2](#)) WSDL message as follows:

1. If the protocol server determines that an error occurred during the protocol server operation, the protocol server MUST respond with a **VisioGraphicsServiceFault** complex type (section [2.2.4.5](#)) SOAP fault with the **Error** field set to the correct **FaultCode** value (section [2.2.5.1](#)).
2. Otherwise, the protocol server MUST return a **VectorDiagram** complex type (section [3.1.4.2.3.2](#)).

If the requested drawing page contains data providers to be implemented by the protocol client, the following sequence of messages MUST be followed:

1. The protocol server MUST respond with an **IVisioGraphicsService_GetVectorDiagram_OutputMessage** response WSDL message. The data providers MUST be specified in the **DataSources** element of the **VectorDiagram** contained within this response. The **OutputPage** element of this **VectorDiagram** MUST be null.
2. The protocol client MUST retrieve the data from the data providers and send another **IVisioGraphicsService_GetVectorDiagram_InputMessage** request WSDL message. This request MUST be identical to the original request except that the **DataSources** element of the **VectorDiagramRequestContract** complex type (section [3.1.4.2.3.1](#)) MUST NOT be null.
3. The protocol server MUST respond with an **IVisioGraphicsService_GetVectorDiagram_OutputMessage** response WSDL message. If no errors occurred, the response MUST contain a **VectorDiagram** and the **OutputPage** element of the **VectorDiagram** MUST NOT be null.

3.1.4.2.1 Messages

The following table summarizes the set of WSDL message definitions that are specific to this operation.

| Message | Description |
|---|---|
| IVisioGraphicsService_GetVectorDiagram_InputMessage | The request WSDL message for the GetVectorDiagram WSDL operation. |
| IVisioGraphicsService_GetVectorDiagram_OutputMessage | The response WSDL message for the GetVectorDiagram WSDL operation. |
| IVisioGraphicsService_GetVectorDiagram_VisioGraphicsServiceFaultFault_FaultMessage | The fault WSDL message for the GetVectorDiagram WSDL operation. |

3.1.4.2.1.1 **IVisioGraphicsService_GetVectorDiagram_InputMessage**

The request WSDL message for the **GetVectorDiagram** WSDL operation.

The SOAP action value is:

<http://tempuri.org/IVisioGraphicsService/GetVectorDiagram>

The SOAP body contains the **GetVectorDiagram** element.

3.1.4.2.1.2 **IVisioGraphicsService_GetVectorDiagram_OutputMessage**

The response WSDL message for the **GetVectorDiagram** WSDL operation.

The SOAP body contains the **GetVectorDiagramResponse** element.

3.1.4.2.1.3 **IVisioGraphicsService_GetVectorDiagram_VisioGraphicsServiceFaultFault_FaultMessage**

The fault WSDL message for the **GetVectorDiagram** WSDL operation.

The SOAP body contains the **VisioGraphicsServiceFault** element.

3.1.4.2.2 Elements

The following table summarizes the XML schema element definitions that are specific to this operation.

| Element | Description |
|---------------------------------|---|
| GetVectorDiagram | The input data for the GetVectorDiagram WSDL operation. |
| GetVectorDiagramResponse | The result data for the GetVectorDiagram WSDL operation. |

3.1.4.2.2.1 GetVectorDiagram

The **GetVectorDiagram** element specifies the input data for the **GetVectorDiagram** WSDL operation.

```
<xs:element name="GetVectorDiagram" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er" minOccurs="0" name="vectorDiagramRequest" nillable="true"
        type="tns:VectorDiagramRequestContract"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

vectorDiagramRequest: The request parameters for a **GetVectorDiagram** (section [3.1.4.2](#)) WSDL operation. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.2.2.2 GetVectorDiagramResponse

The **GetVectorDiagramResponse** element specifies the result data for the **GetVectorDiagram** WSDL operation.

```
<xs:element name="GetVectorDiagramResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er" minOccurs="0" name="GetVectorDiagramResult" nillable="true" type="tns:VectorDiagram"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

GetVectorDiagramResult: The results for a **GetVectorDiagram** (section [3.1.4.2](#)) WSDL operation. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.2.3 Complex Types

The following table summarizes the XML schema complex type definitions that are specific to this operation.

| Complex type | Description |
|-------------------------------------|--|
| ArrayOfDiagramResource | An array of resources information contained in the RenderedPage complex type (section 3.1.4.2.3.3). |
| DiagramResource | A font or an image required by a drawing page. |
| RenderedPage | The drawing page (section 1.3.2) information contained in the VectorDiagram complex type (section 3.1.4.2.3.2). |
| VectorDiagram | The response data from the GetVectorDiagram WSDL operation. |
| VectorDiagramRequestContract | The input data for the GetVectorDiagram (section 3.1.4.2) WSDL operation. |

3.1.4.2.3.1 VectorDiagramRequestContract

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **VectorDiagramRequestContract** complex type contains information used to specify the request parameters for a **GetVectorDiagram** (section [3.1.4.2](#)) WSDL operation. This complex type inherits from the **BaseRequestContract** complex type (section [2.2.4.3](#)), which specifies additional parameters.

```
<xs:complexType name="VectorDiagramRequestContract"
  xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexContent mixed="false">
    <xs:extension base="tns:BaseRequestContract">
      <xs:sequence/>
    </xs:extension>
  </xs:complexContent>
</xs:complexType>
```

3.1.4.2.3.2 VectorDiagram

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **VectorDiagram** complex type contains information used to specify the response for a **GetVectorDiagram** (section [3.1.4.2](#)) WSDL operation. This complex type inherits from **DiagramBase** complex type (section [2.2.4.4](#)), which specifies additional parameters.

```
<xs:complexType name="VectorDiagram" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexContent mixed="false">
    <xs:extension base="tns:DiagramBase">
      <xs:sequence>
        <xs:element minOccurs="0" name="OutputPage" nillable="true" type="tns:RenderedPage"/>
      </xs:sequence>
    </xs:extension>
  </xs:complexContent>
</xs:complexType>
```

OutputPage: A **RenderedPage** complex type (section [3.1.4.2.3.3](#)), that specifies the drawing page (section [1.3.2](#)) in vector format.

3.1.4.2.3.3 RenderedPage

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RenderedPage** complex type contains information that specifies a drawing page, as specified in section [1.3.2](#), in a vector format.

```
<xs:complexType name="RenderedPage" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="Resources" nillable="true"
      type="tns:ArrayOfDiagramResource"/>
    <xs:element minOccurs="0" name="ShapeInfo" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="Xaml" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>
```

Resources: An **ArrayOfDiagramResource**, as specified in section [3.1.4.2.3.4](#), that specifies all the resources used by the **Xaml** field. There MUST be exactly one instance of this element, and it MUST NOT be null.

ShapeInfo: A string that specifies information about the shapes, as specified in section [1.3.3](#), in the drawing page, as specified in section 1.3.2. There MUST be exactly one instance of this element, and it MUST NOT be null.

The syntax of this element is specified in [\[MS-VGSFF\]](#) section 2.4.8. The syntax of this element is also specified by additional attributes of the **CT_Page** element, as specified in [\[MS-VGSFF\]](#) section 2.4.8.2.8, that are listed in the following table.

| Attribute of CT_Page element | Description |
|------------------------------|---|
| Conflict | An integer that specifies the status of retrieving data from data providers for the drawing page (section 1.3.2). |
| DocumentID | A string that specifies a GUID that identifies the file in a document repository that contains the VGSFF web drawing being requested. |
| DocumentTimestamp | A long value that specifies the number of ticks (10,000 per millisecond) that elapsed between 12:00:00 midnight, January 1, 0001 and when the file in a document repository that contains the VGSFF web drawing was last modified in the document repository |
| RefreshWarning | An optional integer that specifies whether the drawing page was refreshed by the protocol server. If this attribute is present, a value of one indicates that data connections exist for the drawing page but that the drawing page was not refreshed from the data providers associated with these data connections. |

Xaml: A string that specifies the vector drawing page, as specified in section 1.3.2, in XAML format, as specified in [\[MS-SLXV\]](#). There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.2.3.4 ArrayOfDiagramResource

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **ArrayOfDiagramResource** complex type contains an array of **DiagramResource** complex types (section [3.1.4.2.3.5](#)).

```
<xs:complexType name="ArrayOfDiagramResource" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" maxOccurs="unbounded" name="DiagramResource" nillable="true"
      type="tns:DiagramResource"/>
  </xs:sequence>
</xs:complexType>
```

DiagramResource: A **DiagramResource** element that specifies the **fonts** and images required by a drawing page (section [1.3.2](#)). It MUST NOT be null.

3.1.4.2.3.5 DiagramResource

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **DiagramResource** complex type contains information that specifies either a font or an image required by a drawing page (section [1.3.2](#)).

```

<xs:complexType name="DiagramResource" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="ByteData" nillable="true" type="xs:base64Binary"/>
    <xs:element minOccurs="0" name="Name" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>

```

ByteData: A base64Binary that specifies the resource in the format of a stream of bytes. There MUST be exactly one instance of this element.

Name: A string that specifies the name for the resource as referenced by the **Xaml** field of the **RenderedPage** complex type (section [3.1.4.2.3.3](#)). It MUST refer to either a font as specified in [\[MS-VGSFF\]](#) section 2.1.6.2 or an image as a specified in [\[MS-VGSFF\]](#) section 2.1.6.3. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.2.4 Simple Types

None.

3.1.4.2.5 Attributes

None.

3.1.4.2.6 Groups

None.

3.1.4.2.7 Attribute Groups

None.

3.1.4.3 GetRasterPage

The **GetRasterPage** operation retrieves information about a drawing page (section [1.3.2](#)) of a **VSDX** [web drawing](#) rendered in raster format.[<10>](#)

The following is the WSDL port type specification of the **GetRasterPage** WSDL operation.

```

<wsdl:operation name="GetRasterPage" xmlns:wsdl="http://schemas.xmlsoap.org/wsdl/">
  <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPage"
  message="tns2:IVisioGraphicsService_GetRasterPage_InputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:output wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageResponse"
  message="tns2:IVisioGraphicsService GetRasterPage OutputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:fault
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageVisioGraphicsServiceFaultF
ault"
  name="VisioGraphicsServiceFaultFault"
  message="tns2:IVisioGraphicsService GetRasterPage VisioGraphicsServiceFaultFault FaultMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
</wsdl:operation>

```

The protocol client sends an **IVisioGraphicsService_GetRasterPage_InputMessage** request (section [3.1.4.3.1.1](#)) WSDL message, and the protocol server MUST respond with an **IVisioGraphicsService_GetRasterPage_OutputMessage** response (section [3.1.4.3.1.2](#)) WSDL message as follows:

1. If the protocol server determines that an error occurred during the protocol server operation, the protocol server MUST respond with a **VisioGraphicsServiceFault** complex type (section [2.2.4.5](#)) SOAP fault having the **Error** field set to the corresponding **FaultCode** value (section [2.2.5.1](#)).
2. If the protocol server determines that the drawing page requested by the protocol client has not changed, based on the information set in the **EntityTag** element of the **RasterPageRequest** complex type (section [3.1.4.3.3.1](#)), as described in the Messages and Event Sequence Rules in section [3.1.4](#), the protocol server MUST return a **RasterPageResponse** (section [3.1.4.3.3.2](#)) with the response code "NotModified".
3. If the requested drawing page contains data providers to be implemented by the protocol client, the protocol server MUST return a **RasterPageResponse** with the response code "DataSources" and the following sequence of messages MUST be followed:
 1. The protocol server MUST respond with an **IVisioGraphicsService_GetRasterPage_OutputMessage** response (section [3.1.4.3.1.2](#)) WSDL message. The data providers MUST be specified in the **DataSources** element of the **RasterPageResponse** complex type (section [3.1.4.3.3.2](#)) contained within this response.
 2. The protocol client MUST retrieve the data from the data providers and MUST send another **IVisioGraphicsService_GetRasterPage_InputMessage** request (section [3.1.4.3.1.1](#)) WSDL message. This request MUST be identical to the original request except that the **DataSources** element of the **RasterPageRequest** complex type (section [3.1.4.3.3.1](#)) MUST NOT be null.
 3. The protocol server MUST respond with an **IVisioGraphicsService_GetRasterPage_OutputMessage** response WSDL message. If no errors occurred, the response MUST contain a **RasterPageResponse** with the response code "OK".
4. Otherwise, the protocol server MUST return a **RasterPageResponse** with the response code **OK**.

3.1.4.3.1 Messages

The following table summarizes the set of WSDL message definitions that are specific to this operation.

| Message | Description |
|--|--|
| IVisioGraphicsService_GetRasterPage_InputMessage | The request WSDL message for the GetRasterPage WSDL operation. |
| IVisioGraphicsService_GetRasterPage_OutputMessage | The response WSDL message for the GetRasterPage WSDL operation. |
| IVisioGraphicsService_GetRasterPage_VisioGraphicsServiceFaultFault_FaultMessage | The fault WSDL message for the GetRasterPage WSDL operation. |

3.1.4.3.1.1 IVisioGraphicsService_GetRasterPage_InputMessage

The request WSDL message for the **GetRasterPage** WSDL operation.

The SOAP action value is:

```
http://tempuri.org/IVisioGraphicsService/GetRasterPage
```

The SOAP body contains the **GetRasterPage** element.

3.1.4.3.1.2 IVisioGraphicsService_GetRasterPage_OutputMessage

The response WSDL message for the **GetRasterPage** WSDL operation.

The SOAP body contains the **GetRasterPageResponse** element.

3.1.4.3.1.3 IVisioGraphicsService_GetRasterPage_VisioGraphicsServiceFaultFault_FaultMessage

The fault WSDL message for the **GetRasterPage** WSDL operation.

The SOAP body contains the **VisioGraphicsServiceFault** element.

3.1.4.3.2 Elements

The following table summarizes the XML schema element definitions that are specific to this operation.

| Element | Description |
|------------------------------|--|
| GetRasterPage | The input data for the GetRasterPage WSDL operation. |
| GetRasterPageResponse | The result data for the GetRasterPage WSDL operation. |

3.1.4.3.2.1 GetRasterPage

The **GetRasterPage** element specifies the input data for the **GetRasterPage** WSDL operation.

```
<xs:element name="GetRasterPage" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        minOccurs="0" name="rasterPageRequestContract" nillable="true"
        type="tns:RasterPageRequest"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

rasterPageRequestContract: A **RasterPageRequest** complex type (section [3.1.4.3.3.1](#)) that specifies the input data. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.3.2.2 GetRasterPageResponse

The **GetRasterPageResponse** element specifies the result data for the **GetRasterPage** WSDL operation.

```

<xs:element name="GetRasterPageResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        minOccurs="0" name="GetRasterPageResult" nillable="true" type="tns:RasterPageResponse"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>

```

GetRasterPageResult: A **RasterPageResponse** complex type (section [3.1.4.3.3.2](#)), that specifies the result data. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.3.3 Complex Types

The following table summarizes the XML schema complex type definitions that are specific to this operation.

| Complex type | Description |
|---------------------------|--|
| RasterPageInfo | The information about a drawing page of a VSDX web drawing . |
| RasterPageRequest | The set of elements that specifies the input data for a GetRasterPage (section 3.1.4.3) WSDL operation. |
| RasterPageResponse | A set of elements that specifies the result data for a GetRasterPage WSDL operation. |
| RasterPageTag | The set of elements that specifies opaque information assigned by the protocol server to a drawing page (section 1.3.2) of a VSDX web drawing when it is requested for the first time. It is used on subsequent requests to determine whether the same drawing page has changed since the initial request. |

3.1.4.3.3.1 RasterPageRequest

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageRequest** complex type contains the set of elements that specifies the input data for a **GetRasterPage** (section [3.1.4.3.2.1](#)) WSDL operation.

```

<xs:complexType name="RasterPageRequest" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="DataModeName" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="DataSources" nillable="true" type="tns:ArrayOfAddonDataSource"/>
    <xs:element minOccurs="0" name="EntityTag" nillable="true" type="tns:RasterPageTag"/>
    <xs:element minOccurs="0" name="FileUrl" nillable="true" type="xs:anyURI"/>
    <xs:element minOccurs="0" name="PageId" type="xs:long"/>
    <xs:element minOccurs="0" name="RefreshCookie" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>

```

DataModeName: A string that specifies whether the protocol server refreshes the requested drawing page (section [1.3.2](#)). There MUST be exactly one instance of this element, and it MUST be one of the following values.

| Value | Description |
|-------------|---|
| Static | The drawing page MUST NOT be updated, and contains only data embedded in the corresponding web drawing . |
| DynamicSafe | The protocol server will decide whether the refresh queries, specified by the Command attribute described in [MS-VSDX] section 2.3.4.2.37, are safe to execute in order to retrieve data from data providers. If all the queries are considered safe, or if RefreshCookie matches the current FileETag (section 3.1.1), as specified in the description of the RefreshCookie element, the drawing page MUST be updated with data retrieved from data providers, as specified in [MS-VSDX] section 2.2.10, and from the system, as specified in [MS-VSDX] section 2.2.11. Otherwise, the drawing page MUST NOT be refreshed, as specified by Static , and the Page element of the shape information XML, specified in section 3.1.1, MUST have the RefreshWarning attribute set to one, as specified in section 2.2.9.1.1. This allows the protocol client to implement a mechanism that requests permission from the user before executing queries that are not considered safe. |

DataSources: An **ArrayOfAddonDataSource** complex type (section 2.2.4.2) that specifies the data providers implemented by a protocol client and used in the requested drawing page. There MUST be exactly one instance of this element. It MUST have zero child elements if there are no data providers. If **DataSources** has child elements, the **Data** field of each **AddonDataSource** complex type (section 2.2.4.1) MUST NOT be null.

EntityTag: A **RasterPageTag** complex type (section 3.1.4.3.3.3) that specifies opaque information about the requested drawing page, and used by the protocol server to determine if the drawing page has changed since it was initially requested. There MUST be exactly one instance of this element. A null or empty value indicates an unconditional message as specified in section 3.1.1.

FileUrl: An **anyURI** that specifies the URL of the file in a document repository that contains the web drawing being requested. There MUST be exactly one instance of this element, and it MUST NOT be null.

PageId: A long that specifies the requested drawing page. If greater than or equal to zero it specifies the identifier of the drawing page. If less than zero it specifies the bitwise complement of the zero-based index of the drawing page. There MUST be exactly one instance of this element.

RefreshCookie: A string that specifies a version of the web drawing that contains the requested drawing page. There MUST be exactly one instance of this element. It MUST match the current **FileETag** (section 3.1.1), in order for the protocol server to refresh the drawing page, as specified in the description of the **DynamicSafe** value of the **DataModeName** element. The matching is performed through string comparison using ordinal sort rules, with the exception of the value "*", which matches any **FileETag**. It MUST be ignored if **DataModeName** is not **DynamicSafe**.

3.1.4.3.3.2 RasterPageResponse

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageResponse** complex type contains the set of elements that specifies the result data for a **GetRasterPage** (section 3.1.4.3) WSDL operation.

```

<xs:complexType name="RasterPageResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="DataSources" nillable="true"
      type="tns:ArrayOfAddonDataSource"/>
    <xs:element minOccurs="0" name="EntityTag" nillable="true" type="tns:RasterPageTag"/>
    <xs:element minOccurs="0" name="PageInfo" nillable="true" type="tns:Raster PageInfo"/>
    <xs:element minOccurs="0" name="ResponseCode" type="tns:RasterPageResponseCode"/>
  </xs:sequence>

```

```
</xs:complexType>
```

DataSources: An **ArrayOfAddonDataSource** complex type (section [2.2.4.2](#)) that specifies the data providers implemented by a protocol client and used in the requested drawing page. There MUST be exactly one instance of this element. It MUST have zero child elements, if there are no data providers. If **DataSources** has child elements, the **Data** field of each contained **AddonDataSource** complex type (section [2.2.4.1](#)) MUST NOT be empty. If the value of **ResponseCode** is "DataSources", it MUST NOT be null or empty. Otherwise, the **DataSources** element MUST be null.

EntityTag: A **RasterPageTag** complex type (section [3.1.4.3.3.3](#)), that specifies opaque information about the requested drawing page. There MUST be exactly one instance of this element. If the value of **ResponseCode** is "OK" or "NotModified", it MUST NOT be null. If the value of **ResponseCode** is "NotModified", it MUST be equal to the value of the **EntityTag** element of the corresponding **RasterPageRequest** complex type (section [3.1.4.3.3.1](#)). Otherwise, the **EntityTag** element MUST be null.

PageInfo: A **Raster PageInfo** complex type (section [3.1.4.3.3.4](#)) that specifies information about the requested drawing page. There MUST be exactly one instance of this element. If the value of **ResponseCode** is "OK", it MUST NOT be null. Otherwise, the **PageInfo** element MUST be null.

ResponseCode: A **RasterPageResponseCode** value (section [3.1.4.3.4.1](#)) that specifies the type of the response. There MUST be exactly one instance of this element.

3.1.4.3.3 RasterPageTag

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageTag** complex type contains the set of elements that specifies opaque information assigned by the protocol server to a drawing page of a **VSDX** [web drawing](#) when it is requested for the first time, and used on subsequent requests to determine whether the same drawing page has changed since the initial request. A **RasterPageTag** is empty if all its elements have default values.

```
<xs:complexType name="RasterPageTag" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="DataModeName" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="FileETag" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="OutputETag" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="SequenceId" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>
```

DataModeName: A string, that specifies whether the drawing page was refreshed by the protocol server. There MUST be exactly one instance of this element, and it MUST be one of the following values.

| Value | Description |
|---------|---|
| Static | The drawing page was not updated, and contains only data embedded in the corresponding web drawing. This is the default value. |
| Dynamic | The drawing page was updated with data retrieved from data providers, as specified in [MS-VSDX] section 2.2.10, or from the system, as specified in [MS-VSDX] section 2.2.11. |

FileETag: A string that specifies an opaque identifier for the version of the web drawing. There MUST be exactly one instance of this element. It MUST NOT be null if **OutputETag** or **SequenceId** is not null. The default value is null.

OutputETag: A string that specifies an opaque identifier for the entity that stores the drawing page in the protocol server's output cache, as described in the Messages and Event Sequence Rules in section [3.1.4](#). There MUST be exactly one instance of this element. It MUST NOT be null if **FileETag** or **SequenceId** is not null. The default value is null.

SequenceId: A string that specifies an identifier for the sequence of subsequent messages required to retrieve the items of the drawing page, as specified in section [3.1](#). There MUST be exactly one instance of this element. It MUST NOT be null if **FileETag** or **OutputETag** is not null. The default value is null.

3.1.4.3.3.4 RasterPageInfo

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageInfo** complex type contains information about a drawing page (section [1.3.2](#)) of a **VSDX** [web drawing](#) rendered in raster format.

```
<xs:complexType name="RasterPageInfo" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element xmlns:q1="http://schemas.microsoft.com/2003/10/Serialization/Arrays"
      minOccurs="0" name="ZoomValues" nillable="true" type="q1:ArrayOfint"/>
  </xs:sequence>
</xs:complexType>
```

ZoomValues: An **ArrayOfInt** that contains the zoom values for the items of a drawing page, as specified in section [3.1.1](#), which correspond to images. There MUST be exactly one instance of this element. The length of the array MUST be equal to 4. Each zoom value in the array MUST be an **integer** greater than or equal to 10, and less than or equal to 200.

3.1.4.3.4 Simple Types

The following table summarizes the XML schema simple type definitions that are specific to this operation.

| Simple type | Description |
|-------------------------------|--|
| RasterPageResponseCode | The possible types of response codes returned as an element of a GetRasterPage (section 3.1.4.3) WSDL operation. |

3.1.4.3.4.1 RasterPageResponseCode

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageResponseCode** simple type specifies the possible types of response codes returned as an element of a **GetRasterPage** (section [3.1.4.3](#)) WSDL operation.

```
<xs:simpleType name="RasterPageResponseCode" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:restriction base="xs:string">
    <xs:enumeration value="NotModified"/>
    <xs:enumeration value="OK"/>
    <xs:enumeration value="DataSources"/>
  </xs:restriction>
</xs:simpleType>
```

The following table specifies the allowable values for the **RasterPageResponseCode** simple type.

| Value | Meaning |
|-------------|--|
| NotModified | Specifies that the requested drawing page (section 1.3.2) has not changed since it was initially requested by the protocol client. |
| OK | Specifies that the response includes full information about the requested drawing page. |
| DataSources | Specifies that the response includes information about the data providers implemented by the protocol client and used by the requested drawing page. |

3.1.4.3.5 Attributes

None.

3.1.4.3.6 Groups

None.

3.1.4.3.7 Attribute Groups

None.

3.1.4.4 GetRasterPageItem

The **GetRasterPageItem** operation retrieves an item, as specified in section [3.1.1](#), of a drawing page (section [1.3.2](#)) of a **VSDX** [web drawing](#) rendered in raster format.[<11>](#)

The following is the WSDL port type specification of the **GetRasterPageItem** WSDL operation.

```

<wsdl:operation name="GetRasterPageItem" xmlns:wsdl="http://schemas.xmlsoap.org/wsdl/">
  <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageItem"
  message="tns2:IVisioGraphicsService_GetRasterPageItem_InputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:output
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageItemResponse"
  message="tns2:IVisioGraphicsService_GetRasterPageItem_OutputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:fault
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageItemVisioGraphicsServiceFault"
  name="VisioGraphicsServiceFault"
  message="tns2:IVisioGraphicsService_GetRasterPageItem_VisioGraphicsServiceFault_FaultMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
</wsdl:operation>

```

The protocol client sends an **IVisioGraphicsService_GetRasterPageItem_InputMessage** request (section [3.1.4.4.1.1](#)) WSDL message, and the protocol server MUST respond with an **IVisioGraphicsService_GetRasterPageItem_OutputMessage** response (section [3.1.4.4.1.2](#)) WSDL message as follows:

1. If the protocol server determines that an error occurred during the protocol server operation, then the protocol server SHOULD[<12>](#) respond with a **VisioGraphicsServiceFault** complex type (section [2.2.4.5](#)) SOAP fault with the **Error** field set to the correct **FaultCode** value (section [2.2.5.1](#)).
2. If the protocol server determines that the item specified by the protocol client has not changed based on the information set in the **EntityTag** element of the **RasterPageItemRequest** complex type (section [3.1.4.4.3.1](#)), as specified in section [3.1.4](#), the protocol server MUST return a

RasterPageItemResponse complex type (section [3.1.4.4.3.3](#)) with the response code "NotModified".

3. Otherwise, the protocol server MUST return a **RasterPageItemResponse** with the response code "OK".

3.1.4.4.1 Messages

The following table summarizes the set of WSDL message definitions that are specific to this operation.

| Message | Description |
|---|--|
| IVisioGraphicsService_GetRasterPageItem_InputMessage | The request WSDL message for the GetRasterPageItem WSDL operation. |
| IVisioGraphicsService_GetRasterPageItem_OutputMessage | The response WSDL message for the GetRasterPageItem WSDL operation. |
| IVisioGraphicsService_GetRasterPageItem_VisioGraphicsServiceFaultFault_Fault Message | The fault WSDL message for the GetRasterPageItem WSDL operation. |

3.1.4.4.1.1 **IVisioGraphicsService_GetRasterPageItem_InputMessage**

The request WSDL message for the **GetRasterPageItem** WSDL operation.

The SOAP action value is:

`http://tempuri.org/IVisioGraphicsService/GetRasterPageItem`

The SOAP body contains the **GetRasterPageItem** element.

3.1.4.4.1.2 **IVisioGraphicsService_GetRasterPageItem_OutputMessage**

The response WSDL message for the **GetRasterPageItem** WSDL operation.

The SOAP body contains the **GetRasterPageItemResponse** element.

3.1.4.4.1.3 **IVisioGraphicsService_GetRasterPageItem_VisioGraphicsServiceFaultFault_FaultMessage**

The fault WSDL message for the **GetRasterPageItem** WSDL operation.

The SOAP body contains the **VisioGraphicsServiceFault** element.

3.1.4.4.2 Elements

The following table summarizes the XML schema element definitions that are specific to this operation.

| Element | Description |
|----------------------------------|--|
| GetRasterPageItem | The input data for the GetRasterPageItem WSDL operation. |
| GetRasterPageItemResponse | The result data for the GetRasterPageItem WSDL operation. |

3.1.4.4.2.1 GetRasterPageItem

The **GetRasterPageItem** element specifies the input data for the **GetRasterPageItem** WSDL operation.

```
<xs:element name="GetRasterPageItem" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er" minOccurs="0" name="rasterPageItemRequestContract" nillable="true"
        type="tns:RasterPageItemRequest"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

rasterPageItemRequestContract: A **RasterPageItemRequest** complex type (section [3.1.4.4.3.1](#)), that specifies the input data. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.4.2.2 GetRasterPageItemResponse

The **GetRasterPageItemResponse** element specifies the result data for the **GetRasterPageItem** WSDL operation.

```
<xs:element name="GetRasterPageItemResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er" minOccurs="0" name="GetRasterPageItemResult" nillable="true"
        type="tns:RasterPageItemResponse"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

GetRasterPageItemResult: A **RasterPageItemReponse** complex type (section [3.1.4.4.3.3](#)), that specifies the result data. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.4.3 Complex Types

The following table summarizes the XML schema complex type definitions that are specific to this operation.

| Complex type | Description |
|------------------------------|---|
| RasterPageItemRequest | The set of elements that specifies the input data for the GetRasterPageItem (section 3.1.4.4) WSDL operation. |

| Complex type | Description |
|-------------------------------|--|
| RasterPageItemResponse | The set of elements that specifies the result data for the GetRasterPageItem WSDL operation. |
| RasterPageItemTag | The set of elements that specifies opaque information assigned by the protocol server to an item of a drawing page (section 1.3.2), as specified in section 3.1.1 , of a VSDX web drawing , when it is requested for the first time, and used on subsequent requests to determine whether the same item has changed since the initial request. |

3.1.4.4.3.1 RasterPageItemRequest

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageItemRequest** complex type contains a set of elements that specifies the input data for the **GetRasterPageItem** (section [3.1.4.4](#)) WSDL operation.

```
<xs:complexType name="RasterPageItemRequest" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="EntityTag" nillable="true" type="tns:RasterPageItemTag"/>
    <xs:element minOccurs="0" name="FileUrl" nillable="true" type="xs:anyURI"/>
    <xs:element minOccurs="0" name="ItemName" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="SequenceId" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>
```

EntityTag: A **RasterPageItemTag** complex type (section [3.1.4.4.3.2](#)) that specifies opaque information about the requested item of the drawing page (section [1.3.2](#)), as specified in section [3.1.1](#), and used by the protocol server to determine if it has changed since it was initially requested. There MUST be exactly one instance of this element. A null or empty value indicates an unconditional message as specified in section 3.1.1.

FileUrl: An **anyURI** that specifies the URL of the file in a document repository that contains the [web drawing](#) being requested. There MUST be exactly one instance of this element, and it MUST NOT be null.

ItemName: A string that specifies the name of the requested item in a drawing page, as specified in section 3.1.1. There MUST be exactly one instance of this element, and it MUST be one of the following values.

| Value | Description |
|-----------|---|
| Image0 | Specifies the requested item is a small image, in Portable Network Graphics (PNG) format as specified in [RFC2083] |
| Image1 | Specifies the requested item is a medium-small image, in Portable Network Graphics (PNG) format as specified in [RFC2083] |
| Image2 | Specifies the requested item is a medium-large image, in Portable Network Graphics (PNG) format as specified in [RFC2083] |
| Image3 | Specifies the requested item is a large image, in Portable Network Graphics (PNG) format as specified in [RFC2083] |
| ShapeInfo | Specifies the requested item is shape information in XML format, as specified in section 2.2.9.1 |

| Value | Description |
|----------|---|
| Comments | Specifies the requested item is comments in XML format, as specified in section 2.2.9.2 |

SequenceId: A string that specifies the message sequence identifier obtained in the **IVisioGraphicsService_GetRasterPage_InputMessage** request (section [3.1.4.3.1.1](#)) WSDL message that initiated the retrieval of a drawing page, as specified in section [3.1](#).

3.1.4.4.3.2 RasterPageItemTag

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageItemTag** complex type contains the set of elements that specifies opaque information assigned by the protocol server to an item of a drawing page (section [1.3.2](#)), as specified in section [3.1.1](#), of a **VSDX** [web drawing](#), when it is requested for the first time. The **RasterPageItemTag** is used on subsequent requests to determine whether the same item has changed since the initial request. A **RasterPageItemTag** is equal to the same element in **RasterPageItemRequest** (section [3.1.4.4.3.1](#)), if all its elements have default values.

```
<xs:complexType name="RasterPageItemTag" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="DataModeName" nillable="true" type="xs:string"/>
    <xs:element minOccurs="0" name="FileETag" nillable="true" type="xs:string"/>
  </xs:sequence>
</xs:complexType>
```

DataModeName: A string that specifies whether the drawing page was refreshed by the protocol server. There MUST be exactly one instance of this element, and it MUST be one of the following values.

| Value | Description |
|---------|---|
| Static | The drawing page was not updated and contains only data embedded in the corresponding web drawing. This is the default value. |
| Dynamic | The drawing page was updated with data retrieved from data providers, as specified in [MS-VSDX] section 2.2.10, or from the system, as specified in [MS-VSDX] section 2.2.11. |

FileETag: A string that specifies an opaque identifier for the version of the web drawing. There MUST be exactly one instance of this element. The default value is null.

3.1.4.4.3.3 RasterPageItemResponse

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageItemResponse** contains the set of elements that specifies the response data for the **GetRasterPageItem** (section [3.1.4.4](#)) WSDL operation.

```
<xs:complexType name="RasterPageItemResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:sequence>
    <xs:element minOccurs="0" name="EntityTag" nillable="true" type="tns:RasterPageItemTag"/>
    <xs:element minOccurs="0" name="ItemData" nillable="true" type="xs:base64Binary"/>
    <xs:element minOccurs="0" name="ResponseCode" type="tns:RasterPageItemResponseCode"/>
  </xs:sequence>
```

```
</xs:complexType>
```

EntityTag: A **RasterPageItemTag** complex type (section [3.1.4.4.3.2](#)) that specifies opaque information about the requested drawing page (section [1.3.2](#)) item, as specified in section [3.1.1](#). There MUST be exactly one instance of this element, and it MUST NOT be null. If the value of **ResponseCode** is "NotModified", it MUST be equal to the value of the **EntityTag** element of the corresponding **RasterPageItemRequest** complex type (section [3.1.4.4.3.1](#)).

ItemData: A base64Binary that specifies the drawing page item data. There MUST be exactly one instance of this element. The value of **ItemData** depends on the value of the **ItemName** element of the corresponding **RasterPageItemRequest**, according to the following table.

| Value of ItemName in RasterPageItemRequest | Value of ItemData |
|--|---|
| Image0 | A small image of the rendered drawing page, in Portable Network Graphics (PNG) format as specified in [RFC2083] . |
| Image1 | A medium-small image of the rendered drawing page, in Portable Network Graphics (PNG) format as specified in [RFC2083] . |
| Image2 | A medium-large image of the rendered drawing page, in Portable Network Graphics (PNG) format as specified in [RFC2083] . |
| Image3 | A large image of the rendered drawing page, in Portable Network Graphics (PNG) format as specified in [RFC2083] . |
| ShapeInfo | The shape information of the drawing page, in XML format, as specified in section 2.2.9.1 , and compressed using the GZIP format, as specified in [RFC1952] . |
| Comments | The comments of the drawing page, in XML format, as specified in section 2.2.9.2 , and encoded using UTF-8, as specified in [RFC3629] . |

ResponseCode: A **RasterPageItemResponseCode** value (section [3.1.4.4.1](#)), that specifies the type of the response. There MUST be exactly one instance of this element.

3.1.4.4.4 Simple Types

The following table summarizes the XML schema simple type definitions that are specific to this operation.

| Simple type | Description |
|-----------------------------------|--|
| RasterPageItemResponseCode | The possible types of response codes returned as an element of a GetRasterPageItem (section 3.1.4.4) WSDL operation. |

3.1.4.4.4.1 RasterPageItemResponseCode

Namespace: <http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer>

The **RasterPageItemResponseCode** simple type specifies the possible types of response codes returned as an element of a **GetRasterPageItem** (section [3.1.4.4](#)) WSDL operation.

```

<xs:simpleType name="RasterPageItemResponseCode" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:restriction base="xs:string">
    <xs:enumeration value="NotModified"/>
    <xs:enumeration value="OK"/>
  </xs:restriction>
</xs:simpleType>

```

The following table specifies the allowable values for the **RasterPageItemResponseCode** simple type.

| Value | Meaning |
|-------------|---|
| NotModified | Specifies that the requested drawing page (section 1.3.2) item, as specified in section 3.1.1 , has not changed since it was initially requested by the protocol client. |
| OK | Specifies that the response includes drawing page item data. |

3.1.4.4.5 Attributes

None.

3.1.4.4.6 Groups

None.

3.1.4.4.7 Attribute Groups

None.

3.1.4.5 SaveComments

The **SaveComments** operation saves a [comment](#) to a **VSDX** [web drawing](#) in a document repository, in the form of a **CommentEntry_Type** element as specified [\[MS-VSDX\]](#) section 2.3.4.2.9.[<13>](#)

The following is the WSDL port type specification of the **SaveComments** WSDL operation.

```

<wsdl:operation name="SaveComments" xmlns:wsdl="http://schemas.xmlsoap.org/wsdl/">
  <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/SaveComments"
  message="tns2:IVisioGraphicsService_SaveComments_InputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:output wsaw:Action="http://tempuri.org/IVisioGraphicsService/SaveCommentsResponse"
  message="tns2:IVisioGraphicsService_SaveComments_OutputMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
  <wsdl:fault
  wsaw:Action="http://tempuri.org/IVisioGraphicsService/SaveCommentsVisioGraphicsServiceFaultFa
ult" name="VisioGraphicsServiceFaultFault"
  message="tns2:IVisioGraphicsService_SaveComments_VisioGraphicsServiceFaultFault_FaultMessage"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl"/>
</wsdl:operation>

```

The protocol client sends an **IVisioGraphicsService_SaveComments_InputMessage** request (section [3.1.4.5.1.1](#)) WSDL message, and the protocol server MUST respond with an **IVisioGraphicsService_SaveComments_OutputMessage** response (section [3.1.4.5.1.2](#)) WSDL message as follows:

- If the protocol server determines that an error occurred during the protocol server operation, then the protocol server MUST respond with a **VisioGraphicsServiceFault** complex type (section [2.2.4.5](#)) SOAP fault with the **Error** field set to the correct **FaultCode** value (section [2.2.5.1](#)).
- Otherwise, the protocol server MUST return a **SaveCommentsResponse** element (section [3.1.4.5.2.2](#)).

3.1.4.5.1 Messages

The following table summarizes the set of WSDL message definitions that are specific to this operation.

| Message | Description |
|---|---|
| IVisioGraphicsService_SaveComments_InputMessage | The request WSDL message for the SaveComments WSDL operation. |
| IVisioGraphicsService_SaveComments_OutputMessage | The response WSDL message for the SaveComments WSDL operation. |
| IVisioGraphicsService_SaveComments_VisioGraphicsServiceFaultFault_FaultMessage | The fault WSDL message for the SaveComments WSDL operation. |

3.1.4.5.1.1 IVisioGraphicsService_SaveComments_InputMessage

The request WSDL message for the **SaveComments** WSDL operation.

The SOAP action value is:

`http://tempuri.org/IVisioGraphicsService/SaveComments`

The SOAP body contains the **SaveComments** element.

3.1.4.5.1.2 IVisioGraphicsService_SaveComments_OutputMessage

The response WSDL message for the **SaveComments** WSDL operation.

The SOAP body contains the **SaveCommentsResponse** element.

3.1.4.5.1.3 IVisioGraphicsService_SaveComments_VisioGraphicsServiceFaultFault_FaultMessage

The fault WSDL message for the **SaveComments** WSDL operation.

The SOAP body contains the **VisioGraphicsServiceFault** element.

3.1.4.5.2 Elements

The following table summarizes the XML schema element definitions that are specific to this operation.

| Element | Description |
|-----------------------------|---|
| SaveComments | The input data for the SaveComments WSDL operation. |
| SaveCommentsResponse | The result data for the SaveComments WSDL operation. |

3.1.4.5.2.1 SaveComments

The **SaveComments** element specifies the input data for the **SaveComments** WSDL operation.

```
<xs:element name="SaveComments" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element minOccurs="0" name="fileUrl" nillable="true" type="xs:anyURI"/>
      <xs:element minOccurs="0" name="commentData" nillable="true" type="xs:string"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

fileUrl: An **anyURI** that specifies the URL of the **VSDX** [web drawing](#) file in a document repository. There MUST be exactly one instance of this element, and it MUST NOT be null.

commentData: A string attribute that specifies data about a [comment](#), in XML format as specified in section [2.2.9.3](#), for a [shape](#) in the **VSDX** web drawing. There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.5.2.2 SaveCommentsResponse

The **SaveCommentsResponse** element specifies the result data for the **SaveComments** WSDL operation.

```
<xs:element name="SaveCommentsResponse" xmlns:xs="http://www.w3.org/2001/XMLSchema">
  <xs:complexType>
    <xs:sequence>
      <xs:element minOccurs="0" name="SaveCommentsResult" nillable="true" type="xs:string"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
```

SaveCommentsResult: A string that specifies the result of the **SaveComments** operation (section [3.1.4.5](#)), in XML format as specified in section [2.2.9.4](#). There MUST be exactly one instance of this element, and it MUST NOT be null.

3.1.4.5.3 Complex Types

None.

3.1.4.5.4 Simple Types

None.

3.1.4.5.5 Attributes

None.

3.1.4.5.6 Groups

None.

3.1.4.5.7 Attribute Groups

None.

3.1.5 Timer Events

The **Recalculation Timeout** timer event cancels the request for the drawing page, as specified in section [1.3.2](#), with a **VisioGraphicsServiceFault**, as specified in section [2.2.4.5](#). The **Error** field of **VisioGraphicsServiceFault** MUST be set to the "RecalcTimedOut" **FaultCode** value, as specified in section [2.2.5.1](#).

The **Message Sequence Timeout** timer event expires the entity cached on the protocol server that is used to match the sequence identifier of the message sequence initiated by an **IVisioGraphicsService_GetRasterPageItem_InputMessage** request (section [3.1.4.4.1.1](#)) WSDL message to retrieve a drawing page (section 1.3.2) of a **VSDX** [web drawing](#) in raster format, as specified in section [3.1.<14>](#)

3.1.6 Other Local Events

None.

4 Protocol Examples

The following sections contain examples of this protocol's usage.

4.1 GetRasterDiagram

In this scenario, the protocol client calls the **GetRasterDiagram** method (section [3.1.4.1](#)) on a protocol server named "ExampleServer". The protocol server responds with a **GetRasterDiagramResponse** element (section [3.1.4.1.2.2](#)). In this case, the drawing page (section [1.3.2](#)) does not contain data providers to be implemented by the protocol client.

To request the raster formatted drawing page, the protocol client constructs the following WSDL message:

```
<s:Envelope>
  <s:Header>
    <a:Action
      s:mustUnderstand="1">http://tempuri.org/IVisioGraphicsService/GetRasterDiagram</a:Action>
      <a:MessageID>urn:uuid:891be72c-aaaf-473a-a4f8-82c3da217414</a:MessageID>
      <a:ReplyTo>
        <a:Address>http://www.w3.org/2005/08/addressing/anonymous</a:Address>
      </a:ReplyTo>
      <a:To s:mustUnderstand="1">https://ExampleServer:
32844/69e08a7b0e904d1a95de6dbf31c51529/VisioGraphicsService.svc/secure</a:To>
      <o:Security>.....</o:Security>
    </s:Header>
    <s:Body>
      <GetRasterDiagram>
        <rasterDiagramRequestContract>
          <b:DataSources i:nil="true"/>
          <b:DisableRefresh>true</b:DisableRefresh>
          <b:FileUri>http://ExampleServer/BasicDiagram.vdw</b:FileUri>
          <b:PageNumber>1</b:PageNumber>
          <b:TimeLastModified>2009-05-20T17:42:20</b:TimeLastModified>
          <b:Resolution>1</b:Resolution>
        </rasterDiagramRequestContract>
      </GetRasterDiagram>
    </s:Body>
  </s:Envelope>
```

The protocol server responds with the following:

```
<s:Envelope xmlns:a="http://www.w3.org/2005/08/addressing"
  xmlns:s="http://www.w3.org/2003/05/soap-envelope">
  <s:Header>
    <a:Action
      s:mustUnderstand="1">http://tempuri.org/IVisioGraphicsService/GetRasterDiagramResponse</a:Action>
  </s:Header>
  <s:Body>
    <GetRasterDiagramResponse xmlns="http://tempuri.org/">
      <GetRasterDiagramResult
        xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
        <d4p1:CacheAge>60</d4p1:CacheAge>
        <d4p1:DataSources i:nil="true"></d4p1:DataSources>
        <d4p1:AreaMaps>
          <Page>
            <Shapes>
              <Shape Name="_1"
Layout="\{&#34;type&#34;:&#34;2D&#34;,&#34;bounds&#34;:\{&#34;x&#34;:&#34;192,&#34;y&#34;:&#34;192,&#34;
;width&#34;:&#34;285,&#34;height&#34;:&#34;285\}\}">
                <Path Shape="poly" Data="192,477,477,477,477,192,192,192,192,477"/>
              </Shapes>
            </Page>
          </AreaMaps>
        </d4p1:AreaMaps>
      </GetRasterDiagramResult>
    </GetRasterDiagramResponse>
  </s:Body>
</s:Envelope>
```

```
    </Shape>
  </Shapes>
</Page>
</d4p1:AreaMaps>
```

<d4p1:Image> iVBORw0KGgoAAAANSUhEUgAAZAAAAQgCAYAAA5ebkOABTr01EQVR4Xu3a0W1tRwgF0KQy1+ZSXcrLc yRXsAWYYVmK8VhZnqGZiv598/fv3/8ESBgaAABAgQIECBAYIPAd4DxR4AAQIECBAgQIAAgQ0C/2w4pDMSIECAAAECBA gQIEdg/97DAMBgQIECBAGAABAgS2CAGwByblnAQIECBAGAABAgQI+C8wfmgMECBAgQIAAAQIECOWr8F9g9sksZQkQIEC AAAECBAicFxGzv8EABAgQIAAAQIECBDYiYd7JmVxkIgQIAAAQIECB4LyDanP8JACBAGAABAgQIECWR0CA2TMrJyVA gAABAgQIECBWxkCAOf8TAECAAAECBAGQIEBjg4AAAs2dWtkqAAECBAGQIEdgvIAAC/4nAIAAAQIECBAgQIDAhEBzs+sn JQAAQIECBAgQIDAEQEB5vxPAABAgQIECBAGACBPQICz5ZOSkBAGQIECBAGACB8wICzPmfAAACBAGQIECAAAEcwQEmD 2zc1ICBAGQIECAAAE5wUEmPM/AQAECBAGQIAAAQIE9ggIMHtm5aQECBAGQIAAAQIEzgsIMod/AgAIECBAGAABAgQI7BE QYPbMykkJECBAGAABAgQInBcQYm7/BAAQIECAAAECBAGQ2CMgwOyzlZMSIECAAAECBAGQOC8gwJz/CQAgQIAAAQIECBAG sEdAgNzkYclQIAAAQIECBAGcF5AgDn/EwBAGAABAgQIECBAYI+AALNnvk5KgAABAgQIECBA4LyAAHP+JwCAAAECBAGQI ECAwB4BwBPrJyUAAECBAGQIECAwHkBAb8tWAAAQIECBAGQIAAgT0CasyeWTkpAQIECBAGQIAAgfMCAsz5nwAAAgQIECB AGAABAnSEBjg9s3JSAgQIECBAGAABAcFBFjzPwEABAgQIECAAAECBPYICDBz7uWkBAGQIECAAAECBM4LCDDnfwIACBAG gQIAAAQIECOWREGD2zMpJCRAGQIAAAQIECJwXEGDO/wQAECBAGAABAgQIENgjIMDsmZWTEiBAGAABAgQIEDgvIMCc/wkA IECAAAECBAGQILBHQIDZMysnJUCAAAECBAGQIHBeQIA5/xMAQIAAAQIECBAGQGCPgACzZ1ZosOAAAQIECBAGQOC8gAbZ/ icAgAABAgQIECBAGMmAeAQFmz6yc1AABAgQIECBAGMB5AQHm/E8AAACBAGQIECAAIE9agLMn1k5KQECBAGQIECAAIhZag LM+z8AAIECBAGQIAAAQJ7BASYPbNyUgIECBAGQIAAAQlnBQSY8z8BAAQIECBAGAABAgT2CAGwe2b1pAqIECBAGAABAgT OCwgw538CAGQIECAAAECBajzERB9g9szKSQkQIECAAAECBAGcFxGzv8EABAgQIAAAQIECBDYiYd7JmVxkIgQIAAAQIE CBA4LyDanP8JACBAGAABAgQIECWR0CA2TMrJyVAgAABAgQIECBWxkCAOf8TAECAAAECBAGQIEBjg4AAAs2dWtkqAAECB AgQIEdgvIAAC/4nAIAAAQIECBAGQIDAhEBzs+snJQAAQIECBAGQIDAEQEB5vxPAAABAgQIECBAGACBPQICz5ZOSkBAG QIECBAGACB8wICzPmfAAACBAGQIECAAAEcwQEmD2zc1ICBAGQIECAAAC5wUEmPM/AQAECBAGQIAAAQIE9ggIMHtm5aQ ECBAGQIAAAQIEzgsIMod/AgAIECBAGAABAgQI7BEQYpMykkJECBAGAABAgQInBcQYm7/BAAQIECAAAECBAGQ2CMgwOyz 1ZMSIECAAAECBAGQOC8gwJz/CQAgQIAAAQIECBAGsEdAgNzkYclQIAAAQIECBAGcF5AgDn/EwBAGAABAgQIECBAYI+AA LNnvk5KgAABAgQIECBA4LyAAHP+JwCAAAECBAGQIECAwB4BwBPrJyUAAECBAGQIECAwHkBAb8tWAAAQIECBAGQIAAgT 0CasyeWTkpAqIECBAGQIAAgfMCAsz5nwAAAgQIECBAGAABAnSEBjg9s3JSAgQIECBAGAABAcFBFjzPwEABAgQIECAAA CBPYICDBz7uWkBAGQIECAAAECBM4LCDDnfwIACBAGQIAAAQIECOWREGD2zMpJCRAGQIAAAQIECJwXEGDO/wQAECBAGAAB AgQIENgjIMDsmZWTEiBAGAABAgQIEDgvIMCc/wkAIECAAAECBAGQILBHQIDZMysnJUCAAAECBAGQIHBeQIA5/xMAQIAAA QIECBAGQOC8gwJz/CQAgQIAAAQIECBAGsEdAgNzkYclQIAAAQIECBAGQIAAAQJ7BASYPbNyUgIECBAGQIAAAQlnBQSY8z8 BAAQIECBAGAABAgT2CAGwe2b1pAqIECBAGAABAgTOCwgw538CAAGQIECAAECBAGsERB9g9szKSQkQIECAAAECBAGcFxG zv8EABAgQIAAAQIECBDYiYd7JmVxkIgQIAAAQIECBA4LyDanP8JACBAGAABAgQIECwROCA2TMrJyVAgAABAgQIECBwX kCAOf8TAECAAAECBAGQIEBjg4AAAs2dWtkqAAECBAGQIEDgvIAAC/4nAIAAAQIECBAGQIDAhEBzs+snJQAAQIECBAGQI DAEQEB5vxPAAABAgQIECBAGACBPQICz5ZOSkBAGQIECBAGACB8wICzPmfAAACBAGQIECAAAC5wUEmPM/AgAIECBAGAABAgQI 7BEQYpMykkJECBAGAABAgQInBcQYm7/BAAQIECAAAECBAGQ2CMgwOyzlZMSIECAAAECBAGQOC8gwJz/CQAgQIAAAQIECBAGs EdAgNzkYclQIAAAQIECBAGcF5AgDn/EwBAGAABAgQIECBAYI+AALNnvk5KgAABAgQIECBA4LyAAHP+JwCAAAECBAGQIA AgT0CasyeWTkpAqIECBAGQIAAgfMCAsz5nwAAAgQIECBAGAABAnSEBjg9s3JSAgQIECBAGAABAcFBFjzPwEABAgQIECAAA CBAGQIAAAQIECBA4LyAAHP+JwCAAAECBAGQIAAAQIECBAGQOC8gwJz/CQAgQIAAAQIECBAGsEdAgNzkYclQIAAAQIECBAGQ IENgjIMDsmZWTEiBAGAABAgQIEDgvIMCc/wkAIECAAAECBAGQILBHQIDZMysnJUCAAAECBAGQIHBeQIA5/xMAQIAAAQIECBAGQGCPgA Czz1ZosOAAAQIECBAGQOC8gAbZ/icAgAABAgQIECBAGMmAeAQFmz6yc1AABAgQIECBAGMB5AQHm/E/gLsDX19efz89P/zD w/GabaPsNFo8dfwQIECCQCQgwmZ/qxQLf4eXj46Pt4SiScyt+A7d/Az/7ZvHadHQCBAj8CgEB5leMwSeMbh4ekx099sRA 4J6AnXvN5m5MgECNgabT4+qrCwQ8JhYMyReJPCRGz5wd0TFCQGBUQIAZ5dd8UsBjY1Jfbwl3B0ycezN3yWIEagQEmBpXX 10g4DGxYE10SOAhATvnoW6GcgECowC1zCi/5pmCmhOT+noTuCdgy9ybunRsTfIajIMDuUprQAgGpIQVDCkQCDwnYQ8N01 7vgBegVEBG+TwFFPCyMNTxm8A9ATvn3zsdmACBGGEBpsBvV3cIeEwsGJ1jEnhIwM55AjiuQoDaQIaAM8qv+aSA8xSkvt4 E7gnYoFdm7sYECNCQICDA1r1r6QMBjYsGQHJHAQwJ2zpkD6BUCBEYFBjhFs0nBtWmJvX1JnBpwM65N3M3jkCgrkCaQxH1 1QUChhMLhuSIBB4SSHMeGqrECAwKiDAjPjRpPingMTGprzeBewJ2zr2ZuzEBAjUCAkyNq68ueEPcywdakryTwkicd89AwX YUAgVEBAWaUX/NJAY+JSX29CdwTsHPuzdyNCRCoERBgalx9dYGAx8SCITkgYce7JyHukqBaIMCggwo/yaTwp4TEzq60 3gnoCdc2/mbkyAQI2AAFPj6qsLBDwmFgzJEQk8JGDnPDRMvYFAYFRAgBn113xSwGNiU19vAvC7Jx7M3dJAgRqBASy1d fxSDgMbFGs1514CEBO+ehYb0KAQkAgLMKL/mkwIeE5P6e04J2Dn3Ju5GxmGUCMgwNs4+uoCAY+JBUNyRAIPcdg5Dw3T VQgQGBUQYeq5N2Z8U8JiY1NebwD0Bo+fezN2YAEaQGmxtVXFwh4TCWYkiMSejAznlomk5CgMCogAaZyqf5p1DhXks+3 gTuCdg592buxgQI1AgIMDwUvrpAwGNiWZACKbdAnB0Q8N0FQ1ERgUWFF+zScFPCyM9fUmcE/Azrk3czcmQKBGQ1Cpcf VBCQIeEwuG5IgEhwKwcx4pqsQDIAqIMC8ms+KeAxMamvN7F7AnbOvZm7MQUECNCQI12rr4Q8JhYMRHJCPCQgJz0DB dHQCBUOEbzpRf80kbj41Jfb0J3B0wc+7N310JEKqREGBqXH1qYDHxIIhQSKEbwTsnIeG6SoEciwKCDcj/JpPCnhtMTOrr

TeCegJ1zb+ZuTIBAjYAAU+PqqwsEPCYWMkRCTwkYoc8NExiUBgVECAgeXXfFLAY2JSX28C9wTsnHszd2MCBGoEBJgaV
 19dIOAxsWBijkjgIQE756FhugoBAqMCAswov+aTAh4Tk/p6E7gnYOfcm7kbEyBQIyDA1Lj66gIBj4kFQ3JEAg8J2DkPDd
 NVCBAYFRBgRvk1nxTwmJjU15vAPQE7597M3ZgAgRoBaabG1VcXChhMLBiSiXj4SMDoEwiYrkKawKiAADPkr/mkgMfEpL7
 eBO4J2Dn3Zu7GBAjUCAgwNa6+ukDAY2LBkByRwEMCds5Dw3QVAgrGBQSYUX7NJu8Jib19SzwT8DOuTdzNyZaoEZAgKlx
 9dUFAh4TC4bkiaQeErBzHqmqxAgMcogwIzyaz4p4DExa83gXscds69msxaQI1AgJMjauvLhDwmFgwJEck8JCAAnfPQM
 F2FAIFRAQFmlF/zSQGPiUl19vQncE7Bz7s3cJQkQqBEQYGpcfxWBgMFEGiE5IoGHBoych4bpKgQ1jAoIMKP8mk8KeExM6u
 tN4J6AnXnv5m5MgECNgABT4+qrCwQ8JhYMyREJPCRg5zw0TFchQGBUQIAZ5dd8usBjY1JfbwL3BOycezN3YwIEagQEmBp
 XX10g4DGxYEiOSOAhATvn0WG6CgECowICzCi/5pMCHhOT+noTuCdg59ybuRsTifaJIMDUuPrqAgGPIQVDckQCDwnYQ8N
 01UIEBgVEGBG+TWfFPCYmNTxm8A9ATvn3sdmACBggEBpsbVvxcieEwsGJ1jEnhIwM55aJiuQoDaqIAAM8qv+aSAx8Skv
 t4E7gnYOfdm7sYECNQICDA1rr66QMBjYsGQHJHAQwJ2zkdPdBUCEYFBjhRfs0nBTwmJvX1JnBpwM65N3M3JkCgRkCaQx
 H11QUChhMLhuSIBB4SsHMeGqarECAwKiDAjPjrpingMTGprzeBewJ2zr2ZuzEBAjUCAkyNq68uEPCYWDakRyTwkICd89A
 wXYUAgVEBAWAUX/NJAY+JSX29CdwTsHPuzdyNCRCERBgalx9dYGAx8SCITkigYcE7JyHukqBAiMCggwo/yaTwp4TEzq
 603gnoCdc2/mbkyAQI2AAFPj6qsLBDwmFgZjeQk8JGdnPDRMVyFAYFRAGBn113xSwGNiU19vAvce7Jx7M3djAgRqBASyG
 1dfXSDgMbfGSI514CEBO+ehYboKAQKjAgLMKL/mkwIeE5P6eho4J2Dn3Ju5GxMgUCMgwNs4+uoCAY+JBUNyRAIPcdg5Dw
 3TVQgQGBUQYEB5Nz8U8JiY1NebwD0Bo+fezN2YAIeAAGMxxtVxFwh4TCwYkiMsEejAznlomK5CgMcogAAzyq/5pIDhxKS
 +3gTuCdg592buxgQ11AgIMDwvvrpAwGniwZackcBDAnbQ8N0FQIERgUEmFF+zScFPCYm9fUmcE/Azrk3czcmQKBGQICp
 CfXVBQIeEwuG51gEHhKwxc4apqsQIDAQIMCM8ms+KeAxMamvN4F7AnbOvZm7MQECNQICIT2rry4Q8JhYMCRHJPCQgJ3z0
 DBdhQCBUQEBZpRf80kbj41Jfb0J3B0wc+7N3i0JEKgREGBqXH11gYDHxIIhOSKbhwtSnIeG6SoECIwKCDCj/JpPcnhMTO
 rrTeCegJ1zb+ZuTIBAjYAAU+PqqwsEPCYWMkRCTwkYoc8NExiUBgVECAgeXXfFLAY2JSX28C9wTsnHszd2MCBGoEBJg
 aV19dIOAxsWBijkjgIQE756FhugoBAqMCAswov+aTAh4Tk/p6E7gnYOfcm7kbEyBQIyDA1Lj66gIBj4kFQ3JEAg8J2DkP
 DdNVCBAYFRBgRvk1nxTwmJjU15vAPQE7597M3ZgAgRoBaabG1VcXChhMLBiSiXj4SMDoEwiYrkKawKiAADPkr/mkgMfEp
 L7eBO4J2Dn3Zu7GBAjUCAgwNa6+ukDAY2LBkByRwEMCds5Dw3QVAgrGBQSYUX7NJu8Jib19SzwT8DOuTdzNyZaoEZAgK
 1x9dUFAh4TC4bkiaQeErBzHqmqxAgMcogwIzyaz4p4DExa83gXscds69msxaQI1AgJMjauvLhDwmFgwJEck8JCAAnfP
 QMF2FAIFRAQFmlF/zSQGPiUl19vQncE7Bz7s3cJQkQqBEQYGpcfxWBgMFEGiE5IoGHBoych4bpKgQ1jAoIMKP8mk8KeExM
 6utN4J6AnXnv5m5MgECNgABT4+qrCwQ8JhYMyREJPCRg5zw0TFchQGBUQIAZ5dd8usBjY1JfbwL3BOycezN3YwIEagQEm
 BpXX10g4DGxYEiOSOAhATvn0WG6CgECowICzCi/5pMCHhOT+noTuCdg59ybuRsTifaJIMDUuPrqAgGPIQVDckQCDwnYQ0Q
 8N01UIEBgVEGBG+TWfFPCYmNTxm8A9ATvn3sdmACBggEBpsbVvxcieEwsGJ1jEnhIwM55aJiuQoDaqIAAM8qv+aSAx8
 kvt4E7gnYOfdm7sYECNQICDA1rr66QMBjYsGQHJHAQwJ2zkdPdBUCEYFBjhRfs0nBTwmJvX1JnBpwM65N3M3JkCgRkCA
 qXH11QUChhMLhuSIBB4SsHMeGqarECAwKiDAjPjrpingMTGprzeBewJ2zr2ZuzEBAjUCAkyNq68uEPCYWDakRyTwkICd8
 9AwXYUAgVEBAWAUX/NJAY+JSX29CdwTsHPuzdyNCRCERBgalx9dYGAx8SCITkigYcE7JyHukqBAiMCggwo/yaTwp4TE
 zq603gnoCdc2/mbkyAQI2AAFPj6qsLBDwmFgZjeQk8JGdnPDRMVyFAYFRAGBn113xSwGNiU19vAvce7Jx7M3djAgRqBAS
 YG1dfXSDgMbfGSI514CEBO+ehYboKAQKjAgLMKL/mkwIeE5P6eho4J2Dn3Ju5GxMgUCMgwNs4+uoCAY+JBUNyRAIPcdg5
 Dw3TVQgQGBUQYEB5Nz8U8JiY1NebwD0Bo+fezN2YAIeAAGMxxtVxFwh4TCwYkiMsEejAznlomK5CgMcogAAzyq/5pIDhx
 KS+3gTuCdg592buxgQ11AgIMDwvvrpAwGniwZackcBDAnbQ8N0FQIERgUEmFF+zScFPCYm9fUmcE/Azrk3czcmQKBGQI
 CpcfxVBQIeEwuG51gEHhKwxc4apqsQIDAQIMCM8ms+KeAxMamvN4F7AnbOvZm7MQECNQICIT2rry4Q8JhYMCRHJPCQgJ3
 z0DBdhQCBUQEBZpRf80kbj41Jfb0J3B0wc+7N3i0JEKgREGBqXH11gYDHxIIhOSKbhwtSnIeG6SoECIwKCDCj/JpPcnhM
 TOrrTeCegJ1zb+ZuTIBAjYAAU+PqqwsEPCYWMkRCTwkYoc8NExiUBgVECAgeXXfFLAY2JSX28C9wTsnHszd2MCBGoEB
 JgaV19dIOAxsWBijkjgIQE756FhugoBAqMCAswov+aTAh4Tk/p6E7gnYOfcm7kbEyBQIyDA1Lj66gIBj4kFQ3JEAg8J2D
 kPdDnVCBAYFRBgRvk1nxTwmJjU15vAPQE7597M3ZgAgRoBaabG1VcXChhMLBiSiXj4SMDoEwiYrkKawKiAADPkr/mkgMf
 EpL7eBO4J2Dn3Zu7GBAjUCAgwNa6+ukDAY2LBkByRwEMCds5Dw3QVAgrGBQSYUX7NJu8Jib19SzwT8DOuTdzNyZaoEZA
 gK1x9dUFAh4TC4bkiaQeErBzHqmqxAgMcogwIzyaz4p4DExa83gXscds69msxaQI1AgJMjauvLhDwmFgwJEck8JCA
 fPQMF2FAIFRAQFmlF/zSQGPiUl19vQncE7Bz7s3cJQkQqBEQYGpcfxWBgMFEGiE5IoGHBoych4bpKgQ1jAoIMKP8mk8KeE
 xM6utN4J6AnXnv5m5MgECNgABT4+qrCwQ8JhYMyREJPCRg5zw0TFchQGBUQIAZ5dd8usBjY1JfbwL3BOycezN3YwIEagQ
 EmBpXX10g4DGxYEiOSOAhATvn0WG6CgECowICzCi/5pMCHhOT+noTuCdg59ybuRsTifaJIMDUuPrqAgGPIQVDckQCDwnY
 Q0Q8N01UIEBgVEGBG+TWfFPCYmNTxm8A9ATvn3sdmACBggEBpsbVvxcieEwsGJ1jEnhIwM55aJiuQoDaqIAAM8qv+aSAx
 8Skvt4E7gnYOfdm7sYECNQICDA1rr66QMBjYsGQHJHAQwJ2zkdPdBUCEYFBjhRfs0nBTwmJvX1JnBpwM65N3M3JkCgRk
 CAqXH11QUChhMLhuSIBB4SsHMeGqarECAwKiDAjPjrpingMTGprzeBewJ2zr2ZuzEBAjUCAkyNq68uEPCYWDakRyTwkIC
 d89AwXYUAgVEBAWAUX/NJAY+JSX29CdwTsHPuzdyNCRCERBgalx9dYGAx8SCITkigYcE7JyHukqBAiMCggwo/yaTwp4
 TEzq603gnoCdc2/mbkyAQI2AAFPj6qsLBDwmFgZjeQk8JGdnPDRMVyFAYFRAGBn113xSwGNiU19vAvce7Jx7M3djAgRqB
 ASYGl1dfXSDgMbfGSI514CEBO+ehYboKAQKjAgLMKL/mkwIeE5P6eho4J2Dn3Ju5GxMgUCMgwNs4+uoCAY+JBUNyRAIPcd
 g5Dw3TVQgQGBUQYEB5Nz8U8JiY1NebwD0Bo+fezN2YAIeAAGMxxtVxFwh4TCwYkiMsEejAznlomK5CgMcogAAzyq/5pID
 HxKS+3gTuCdg592buxgQ11AgIMDwvvrpAwGniwZackcBDAnbQ8N0FQIERgUEmFF+zScFPCYm9fUmcE/Azrk3czcmQKBG
 QICpcfxVBQIeEwuG51gEHhKwxc4apqsQIDAQIMCM8ms+KeAxMamvN4F7AnbOvZm7MQECNQICIT2rry4Q8JhYMCRHJPCQg
 J3z0DBdhQCBUQEBZpRf80kbj41Jfb0J3B0wc+7N3i0JEKgREGBqXH11gYDHxIIhOSKbhwtSnIeG6SoECIwKCDCj/JpPcn
 hMTOrrTeCegJ1zb+ZuTIBAjYAAU+PqqwsEPCYWMkRCTwkYoc8NExiUBgVECAgeXXfFLAY2JSX28C9wTsnHszd2MCBGo
 EBJgaV19dIOAxsWBijkjgIQE756FhugoBAqMCAswov+aTAh4Tk/p6E7gnYOfcm7kbEyBQIyDA1Lj66gIBj4kFQ3JEAg8J
 2DkPdDnVCBAYFRBgRvk1nxTwmJjU15vAPQE7597M3ZgAgRoBaabG1VcXChhMLBiSiXj4SMDoEwiYrkKawKiAADPkr/mkg
 MfEpL7eBO4J2Dn3Zu7GBAjUCAgwNa6+ukDAY2LBkByRwEMCds5Dw3QVAgrGBQSYUX7NJu8Jib19SzwT8DOuTdzNyZaoE
 ZAgK1x9dUFAh4TC4bkiaQeErBzHqmqxAgMcogwIzyaz4p4DExa83gXscds69msxaQI1AgJMjauvLhDwmFgwJEck8JC
 AnfPQMF2FAIFRAQFmlF/zSQGPiUl19vQncE7Bz7s3cJQkQqBEQYGpcfxWBgMFEGiE5IoGHBoych4bpKgQ1jAoIMKP8mk8K
 eExM6utN4J6AnXnv5m5MgECNgABT4+qrCwQ8JhYMyREJPCRg5zw0TFchQGBUQIAZ5dd8usBjY1JfbwL3BOycezN3YwIEa
 gQEmBpXX10g4DGxYEiOSOAhATvn0WG6CgECowICzCi/5pMCHhOT+noTuCdg59ybuRsTifaJIMDUuPrqAgGPIQVDckQCDw
 nYQ0Q8N01UIEBgVEGBG+TWfFPCYmNTxm8A9ATvn3sdmACBggEBpsbVvxcieEwsGJ1jEnhIwM55aJiuQoDaqIAAM8qv+aS
 Ax8Skvt4E7gnYOfdm7sYECNQICDA1rr66QMBjYsGQHJHAQwJ2zkdPdBUCEYFBjhRfs0nBTwmJvX1JnBpwM65N3M3JkCg
 RkCAqXH11QUChhMLhuSIBB4SsHMeGqarECAwKiDAjPjrpingMTGprzeBewJ2zr2ZuzEBAjUCAkyNq68uEPCYWDakRyTwk
 ICd89AwXYUAgVEBAWAUX/NJAY+JSX29CdwTsHPuzdyNCRCERBgalx9dYGAx8SCITkigYcE7JyHukqBAiMCggwo/yaTw
 p4TEzq603gnoCdc2/mbkyAQI2AAFPj6qsLBDwmFgZjeQk8JGdnPDRMVyFAYFRAGBn113xSwGNiU19vAvce7Jx7M3djAgR
 qBASyGl1dfXSDgMbfGSI514CEBO+ehYboKAQKjAgLMKL/mkwIeE5P6eho4J2Dn3Ju5GxMgUCMgwNs4+uoCAY+JBUNyRAIP
 Cd5Dw3TVQgQGBUQYEB5Nz8U8JiY1NebwD0Bo+fezN2YAIeAAGMxxtVxFwh4TCwYkiMsEejAznlomK5CgMcogAAzyq/5p
 IDhxKS+3gTuCdg592buxgQ11AgIMDwvvrpAwGniwZackcBDAnbQ8N0FQIERgUEmFF+zScFPCYm9fUmcE/Azrk3czcmQK

BGQICpcfXVBQIEwuG5IgEHhKwcx4apqsQIDAqIMCM8ms+KeAxMamvN4F7AnbOvZm7MQECNQICT12rry4Q8JhYMCRHJPC
 QgJ3z0DBdhQCBUQEbzPf80kbj41Jfb0J3B0w+7N3I0JEKgREGBQxH11gYDHxIIhOSKBhwTsnIeG6SoECIwKCDCj/JpP
 CnhtMTorrTeCegJ1zb+ZuTIBAJYAAU+PqqwsEPCYWDmkRCTwkY0c8NExXIUBgVECAgExxxFLAY2JSX28C9wTsnHszd2MCB
 GoEBJgaV19dIOAxsWB1jkjgIQE756FhugoBaqMCAswov+aTAh4Tk/p6E7gnYOfcm7kbEyBQiyDA1Lj66gIBj4kFQ3JEAg
 8J2DkPdDnVCBAYFRBgvk1nxTwmJjU15vAPQE7597M3ZgAgRoBAabG1VcXChhMLBiS1xJ4SMDOeWiYrkKAwKiAADPkr/m
 kgMfEpL7eB04J2Dn3Zu7GBAjUCAgwNa6+ukDAY2LBkByRwEMCds5Dw3QVAgRGBQSYUX7NjwU8J1b19SzWt8D0uTdzNyZA
 oEZAgK1x9dUFAh4TC4bkiAQeErBzHhmqmxAgMCogwIzyaz4p4DEXqa83gXsCds69msxsAQI1AgJMjauvLhDwmFgwJEck8
 JCANfPQM2FAIFRAQfml/zSQGPiU19vQncE7Bz7s3cJQkQqBEQYgpcfxWBgMfEgiE5IogHBoych4bpKgQIjAoIMKp8mk
 8KeExM6utN4J6AnXnv5m5MgECNgABT4+qrCwQ8JhYMyREJPCRG5zw0TFchQGBUQIAZ5dd8UsBjY1JfbwL3B0OycezN3yWI
 EaqQEmBpXX10g4DGxYE1OSOAhATvn0WG6CgECowICzCi/5pMCHhOT+noTuCd59ybuRsTifaJIMDUuPrqAgGp1QVdcKQC
 DwnYOQ8N01UIEBgVEGBG+TwfPCYmNTxm8A9ATvn3szdmACBggEBpsbVxcieEwsGJ1jEnhIwM55aJiuQoDAqIAAM8qv+
 aSAx8Skv7e4T7gnYOfdm7sYECNQICDA1rr66QMBjYsGQHJHAQwJ2zKPDdBUCBeyFBjhRfs0nBtwmJvX1JnBpwM65N3EcJk
 CgRkCAqXH11QUCHhMlhusIBB4SShMeGqarEcAwKidaJpJrPingMTGrzeBewJ2zr2ZuzEBAjUCAkyNq68uEPCYWDakRyt
 wkICd89wxyUAqVEBAwUX/NJAY+JSX29CdwTsHPuzydNCRCoERBgalx9dYGAx8SCITkgYcE7JyHukqBAimCggwo/ya
 Twp4TEzq603gnoCdc2/mbkyAQI2AAFPj6gsLBDwmFgzJEQk8JGdnPDRMvYFAYFRAgBn113xSwGNiU19vAvce7Jx7M3dJA
 gRqBASyG1dfXSDgMbFgSi514CEBO+ehYbokAQKjAgLMKL/mkwIeE5P6eh04J2Dn3Ju5GxmGUCMgwNS4+uoCAY+jBUNyRA
 IPCdg5Dw3TVQgQGBUQYEB5Nz8U8JiY1NebwD0BO+fezN2YAIeAaQGmxtVXFwh4TCwYkiMsEjAznlomK5CgMCogAAzyq/
 5pIDHXKS+3gTuCdg592buxgQ1AgIMDwvRpAwGniwZAckcBDAboQ8N0FQIerGjEmFF+zScFPCYm9fUmcE/Azrk3czm
 QKBGQICpcfxVBQ1eBwG51gEHhKwcx4apgsQIDAqIMCM8ms+KeAxMamvN4F7AnbOvZm7MQECNQICT12rry4Q8JhYMCRHJ
 PCQgJ3z0DdbhQCBUQEbzPf80kbj41Jfb0J3B0w+7N3I0JEKgREGBQxH11gYDHxIIhOSKBhwTsnIeG6SoECIwKCDCj/J
 pPCnhMTorrTeCegJ1zb+ZuTIBAJYAAU+PqqwsEPCYWDmkRCTwkY0c8NExXIUBgVECAgExxxFLAY2JSX28C9wTsnHszd2M
 CBGoEBJgaV19dIOAxsWB1jkjgIQE756FhugoBaqMCAswov+aTAh4Tk/p6E7gnYOfcm7kbEyBQiyDA1Lj66gIBj4kFQ3JE
 Ag8J2DkPdDnVCBAYFRBgvk1nxTwmJjU15vAPQE7597M3ZgAgRoBAabG1VcXChhMLBiS1xJ4SMDOeWiYrkKAwKiAADPkr
 /mkMfEpL7eB04J2Dn3Zu7GBAjUCAgwna6+ukDAY2LBkByRwEMCds5Dw3QVAgRGBQSYUX7NjwU8J1b19SzWt8D0uTdzNy
 ZAOEZAgK1x9dUFAt+PiY+Pjz8/jwr//mTx9zfhd8C6gjfws28WrEdHEJCAwK8WEGB+9XgcrlLg6+vLY9WD3W/Ab6D1N/C
 9d/wRIECAQCYgwGR+qgkQIECAAECBAGaBQQYBqxtsJzAgAABAgQIECBAgBQYDI/1QOIECBAgAABAgQINAoIMI3YWhEg
 QIAAAQIECBAgAkIMJmfagIECBAgQIAAAQIEggUEmzsrQgQIECAAAECBAGQyAEEmMxPNQECBAGQIECAAAECjQICTCO2V
 gQIECBAgAABAgQIZAICtoanmgABAgQIECBAgACBrgEBphFbKwIECBAgQIAAAQIEmgEBjvnttyAAAQIECBAgQIBao4AA04
 itFQECBAgQIECAAECmYAAk/mpJkCAAAECBAGQIECgUJUCAactWigABAgQIECBAgACBTECAyfxUEyBAGAABAgQIECDQKCD
 ANGJrRYAAAQIECBAgQIBAJiDAZH6qCRAgQIAAAQIECBBofBBgGrG1IkCAAAECBAGQIEAgExBgmj/VBAgQIECAAECBAG0
 CggwjdaESBAGAABAgQIECCQCQgwM9gAgQIECBAgAABAgQaBQSYRmytCBAgQIAAAQIECBDIBASYzE81AQIECBAgQIAAA
 QKNAgJMI7ZWBAGQIECAAECBAGkAgJ5qeaaAECAgQIECAAIFGAQGMevsrAgQIECBAgAABAgQyAEEm81NngAABAgQIEC
 BAGECjgADTik0VAQIECBAgQIAAAQKZgACT+akmQIAAAQIECBAgQKBRQ1BpxNaKAAECBAGQIECAAIFMQ1D/FQTIECAAAE
 CBAGQINAoIMA0YmtFgAABAgQIECBAgEAmIMBkfqoJECBAGAABAgQIEGgUEGAbsUiQIAAAQIECBAgQcateGAYP9UECBAg
 QIAAAQIECDQKDCN2F0RIECAAECBAGQIJAJCDCZn2oCBAgQIECAAAECBBoFBjhGbK0IECBAgAABAgQIEmgEBjJMTzUBA
 gQIECBAgAABao0Cakwj1YECBAgQIAAAQIEGQCAkzmp5oAAQIECBAgQIAAgUYBaaYRWysCBAGQIECAAAECBDIBASbzU0
 2AAAECBAgQIECAQKOAA NOIrRUBAgQIECBAgAABAgPmAAJP5qsZAgAABAgQIECBAoffAgGne1ooAAQIECBAgQIAAgUxAgMn
 8VBMgQIAAAQIECBAg0CggwDr10WAAAECBAgQIECAQCYgwGR+qgkQIECAAAECBAGQaBQQYBqxtsJAgAABAgQIECBAIBMQ
 YDI/1QOIECBAgAABAgQINAoIMI3YWhEgQIAAAQIECBAgkAkIMJmfagQIECBAgQIAAAQIEgQeUmEsrsQgQIECAAECBAGQy
 AQEmMxPNQECBAGQIECAAECjQICTCO2VgQIECBAgAABAgQIZAICTOanmgABAgQIECBAgACBrgEBphFbKwIECBAgQIAAAQ
 IEMgEBjvnttyAAAQIECBAgQIBAJ0AA404itFQECBAgQIECAAECmYAAk/mpJkCAAAECBAGQIECgUUCACactWigABAgQIEC
 AgACBTECAyfxUEyBAGAABAgQIECDQKCDANGJrRYAAAQIECBAgQIBAJiDAZH6qCRAGQIAAAQIECBBofBBgGrGLIKCAAAEC
 BAGQIEAgExBgmj/VBAgQIECAAECBAG0CggwjdhESAgaABAgQIECQCQgwM9gAgQIECBAgAABAgQaBQSYRmytCBAgQ
 IAAQIECBDIBASYzE81AQIECBAgQIAAAQKNAGJMI7ZWBAGQIECAAECBAGhAgJ5qeaaAECAgQIECAAIFGAGQmEVsrAg
 QIECBAgAABAgQyAEEm81NngAABAgQIECBAgECjgADTik0VAQIECBAgQIAAAQKZgACT+akmQIAAAQIECBAgQKBRQ1BpxNa
 KAAECBAGQIECAAIFM01D/FQTIECAAECBAGQINAoIMA0YmtFgAABAgQIECBAgEAmIMBkfqoJECBAGAABAgQIEGgUEGAa
 sbUiQIAAAQIECBAgQcategAYP9UECBAgQIAAAQIECDQKDCN2F0RIECAAECBAGQIJAJCDCZn2oCBAgQIECAAECBBoFB
 JhGbK0IECBAgAABAgQIEmgEBjJMTzUBAqIECBAgAABAg0Cakwj1YECBAgQIAAAQIEGQCAkzmp5oAAQIECBAgQIAAGU
 YBAAyRWysCBAGQIECAAECBDIBASbzU02AAAECBAgQIECAQKOAA NOIrRUBAgQIECBAgAABAgPmAAJP5qsZAgAABAgQIEC
 BaoffAgGne1ooAAQIECBAgQIAAgUxAgMn8VBMgQIAAAQIECBAg0CggwDr10WAAAECBAgQIECAQCYgwGR+qgkQIECAAEC
 BAGQaBQQYBqxtsJAgAABAgQIECBAIBMQYDI/1QOIECBAgAABAgQINAoIMI3YWhEgQIAAAQIECBAgkAkIMJmfagIECBAgQ
 IAAQIEGgUEmEsrsQgQIECAAECBAGQyAEEmMxPNQECBAGQIECAAECjQICTCO2VgQIECBAgAABAgQIZAICTOanmgABAg
 QIECBAgACBrgEBphFbKwIECBAgQIAAAQIEmEgBjvnttyAAAQIECBAgQIBAO404itFQECBAgQIECAAECmYAAk/mpJkC
 AAAECBAGQIECgUUCAAactWigABAgQIECBAgACBTECAyfxUEyBAGAABAgQIECDQKCDANGJrRYAAAQIECBAgQIBAJiDAZ
 H6qCRAgQIAAAQIECBBofBBjhGbK0IECBAgAABAgQIEmgEBjJMTzUBAqIECBAgAABAg0Cakwj1YECBAgQI
 AAAQIEGQCAkzmp5oAAQIECBAgQIAAgUYBaaYRWysCBAGQIECAAECBAGQIECBAgQIAAAQIECBAgQIECAAECBBoFB
 IECBAgAABAgPmAAJP5qsZAgAABAgQIECBAoffAgGne1ooAAQIECBAgQIAAgUxAgMn8VBMgQIAAAQIECBAg0CggwDr10
 AAECBAGQIECAQCYgwGR+qgkQIECAAECBAGQaBQQYBqxtsJAgAABAgQIECBAIBMQYDI/1QOIECBAgAABAgQINAoIMI3Y
 WhEgQIAAAQIECBAgkAkIMJmfagIECBAgQIAAAQIEggUEmEsrsQgQIECAAECBAGQyAEEmMxPNQECBAGQIECAAECjQICTC
 O2VgQIECBAgAABAgQIZAICTOanmgABAgQIECBAgACBrgEBphFbKwIECBAgQIAAAQIEmgEBjvnttyAAAQIECBAgQIBAO4A
 A0404itFQECBAgQIECAAECmYAAk/mpJkCAAAECBAGQIECgUUCACactWigABAgQIECBAgACBTECAyfxUEyBAGAABAgQIECDQ
 KCDANGJrRYAAAQIECBAgQIBAJiDAZH6qCRAgQIAAAQIECBBofBBgGrG1IkCAAAECBAGQIEAgExBgmj/VBAgQIECAAECB
 Ag0CggwjdhESAgaABAgQIECBAgAABAgQIEGgUEGAbsUiQIAAAQIECBAgQcategAYP9UECBAgQIAAAQIECDQKDCN2F0RIE
 AAAQKNAGJMI7ZWBAGQIECAAECBAGQIAAAQKZgACT+akmQIAAAQIECBAgQKBRQ1BpxNaKAAECBAGQIECAAIFM01D/FQTIECA

QIECDQKCDANGJrRYAAAQIECBAgQIBAJiDAZH6qCRAGQIAAAQIECBBoFBBgGrG1IkCAAECBAGQIEAgExBgMj/VBAgQIEC
 AAAECBAG0CggwjdhAESBAGAABAgQIECCQCQgwM79qAgQIECBAGAABAgQaBQSRYmtCBAGQIAAAQIECBDIBASYzE81AQIE
 CBAGQIAAAQKNAgJMI7ZWBAGQIECAAAECBAhKAgJM5qeAAAEBCAgQIECAAIFGAQGmEVsrAgQIECBAGAABAgQyAQEM81NNg
 AABAgQIECBAGEcjgADTiK0VAQIECBAGQIAAAQKZgACT+akmQIAAAQIECBAGQKBQRIBpxNaKAAECBAGQIECAAIFMQIDJ/F
 QTIECAAAECBAGQINAoIMA0YmtFgAABAgQIECBAGeAmIMBkfqoJECBAGAABAgQyQIEGgUEGAsubuQiQIAAAQIECBAGQCATEGA
 yPUECBAGQIAAAQIECDQKDCN2FoRIECAAAECBAGQIJAJCDCZn2oCBAGQIECAAAECBBoFBjhGbK0IECBAGAABAgQIEMG
 BJMtzUBAgQIECBAGAABao0CAkwjt1YECBAGQIAAAQIECGQCakzmp5oAAQIECBAGQIAAgUYBAAyrWysCBAGQIECAAAECB
 DIBASbzU02AAAECBAGQIECAQKOANOIrRUBAgQIECBAGAABApMajP5qsZAgAABAgQIECBAGQIECBAGFFAgGne1ooAAQIECBAGQI
 AAAGuxAgMn8VBMgQIAAAQIECBAG0CggwDRia0WAAAECBAGQIECAQCYgwGR+qgkQIECAAAECBAGQaBQQYBqxtSJAgAABAgQ
 IECBAIBMQYDI/1QQIECBAGAABAgQINAoIMI3YwhEgQIAAAQIECBAGkAkIMJmfagIECBAGQIAAAQIEGGueMeZsrQgQIECA
 AAECBAGQyAQEmMxPNQECBAGQIECAAAECjQICTCO2VgQIECBAGAABAgQIZAICToanmgABAgQIECBAGACBRgEBphFbKwIEC
 BAQIAAAQIEMgEBJvNTTYAAAQIECBAGQIBAo4A04itFQECBAGQIECAAAECmYAAK/mpJkCAAECBAGQIECgJUUCAcTwig
 ABAgQIECBAGACBTECAyxFuEyBAGAABAgQIECDQKDCDANGJrRYAAAQIECBAGQIBAJiDAZH6qCRAGQIAAAQIECBBoFBGrg
 1IkCAAECBAGQIEAgExBgMj/VBAgQIECAAAECBAG0CggwjdaESBAGAABAgQIECCQCQgwM79qAgQIECBAGAABAgQaBQS
 RmytCBAGQIAAAQIECBDIBASYzE81AQIECBAGQIAAAQKNAgJMI7ZWBAGQIECAAAECBAGQIAAAQIECBAGQIECAAIFGA
 QGmEVsrAgQIECBAGAABAgQyAQEm81NNgAABAgQIECBAGEcjgADTiK0VAQIECBAGQIAAAQKZgACT+akmQIAAAQIECBAGQK
 BRQIBpxNaKAAECBAGQIECAAIFMQIDJ/FQTIECAAAECBAGQINAoIMA0YmtFgAABAgQIECBAGeAmIMBkfqoJECBAGAABAgQ
 IEggUEGAsubuQiQIAAAQIECBAGQyQATEGAYp9UECBAGQIAAAQIECDQKDCN2FoRIECAAAECBAGQIJAJCDCZn2oCBAGQIECA
 AAECBBoFBjhGbK0IECBAGAABAgQyQIEMgEBJjMTzUBAgQIECBAGAABao0CAkwjt1YECBAGQIAAAQIECGQCakzmp5oAAQIEC
 BAQAgQIAAgYBAAyrWysCBAGQIECAAAECBBoFBjhGbK0IECBAGQIAAAQIECBAGQyQIECBAGAABApMajP5qsZAgA
 ABAgQIECBAGFFAgGne1ooAAQIECBAGQIAAguxAgMn8VBMgQIAAAQIECBAG0CggwDRia0WAAAECBAGQIECAQCYgwGR+qgk
 QIECAAAECBAGQaBQQYBqxtSJAgAABAgQIECBAGQyAQEmMxPNQECBAGQIECAAAECjQICTCO2VgQIECBAGAABAgQIZAIC
 OanmgABAgQIECBAGACBRgEBphFbKwIECBAGQIAAAQIEMgEBJvNTTYAAAQIECBAGQIBAo4A04itFQECBAGQIECAAAECmY
 AAK/mpJkCAAECBAGQIECgJUUCAcTwigABAgQIECBAGACBTECAyxFuEyBAGAABAgQIECDQKDCDANGJrRYAAAQIECBAGQIB
 AJiDAZH6qCRAGQIAAAQIECBBoFBBgGrG1IkCAAECBAGQIEAgExBgMj/VBAgQIECAAAECBAGQIAggwDhAESBAGAABAgQI
 ECQCQgwM79qAgQIECBAGAABAgQaBQSRYmtCBAGQIAAAQIECBDIBASYzE81AQIECBAGQIAAAQKNAgJMI7ZWBAGQIECA
 AECBAGQIAAAQIECBAGQIECAAIFMQGmEVsrAgQIECBAGAABAgQyAQEm81NNgAABAgQIECBAGEcjgADTiK0VAQIECB
 AgQIAAAQKZgACT+akmQIAAAQIECBAGQKBQRIBpxNaKAAECBAGQIECAAIFM0IDJ/FQTIECAAAECBAGQINAoIMA0YmtFgAA
 BAQIECBAGeAmIMBkfqoJECBAGAABAgQyQIEGgUEGAsubuQiQIAAAQIECBAGQCATEGAYp9UECBAGQIAAAQIECDQKDCN2FoR
 IECAAAECBAGQIJAJCDCZn2oCBAGQIECAAAECBBoFBjhGbK0IECBAGAABAgQyQIECgJUUCAcTwigABAgQIECBAGAABAgQ
 IEggUEGAsubuQiQIAAAQIECGQCakzmp5oAAQIECBAGQyQIEAgYBAAyrWysCBAGQIECAAAECBBoFBjhGbK0IECBAGAABAgQ
 oirRUBAgQIECBAGAABApMajP5qsZAgAABAgQIECBAGFFAgGne1ooAAQIECBAGQIAAguxAgMn8VBMgQIAAAQIECBAG0C
 gwDRia0WAAAECBAGQIECAQCYgwGR+qgkQIECAAAECBAGQaBQQYBqxtSJAgAABAgQIECBAG4D72ibrKC1aEiAAAAAElF
 TkSuQmCC</d4p1:Image>
 <d4p1:ShapeInfo>
 <Page Name="Page-1" Zoom="-1.000000" OffsetX="407.142857" OffsetY="528.857143" DefaultUnitsText="50" DefaultUnitsAngle="81" DefaultUnitsDuration="44" DefaultUnitsPage="73" DocumentID="1360559653">
 <Pages>
 <Page Name="Page-1" />
 </Pages>
 <ShapeInfo Name="_1" DisplayName="Sheet.1" Layout="\" type="" :2D"; bounds="" :{"x:"191,"y:"191,"width:"287,"height:"287\}\}" />
 </Page>
 </d4p1:ShapeInfo>
 </GetRasterDiagramResult>
 </GetRasterDiagramResponse>
</s:Body>
</s:Envelope>

4.2 GetVectorDiagram

In this scenario, the protocol client calls the **GetVectorDiagram** method (section 3.1.4.2) on a protocol server named "ExampleServer". The protocol server responds with a **GetVectorDiagramResponse** element (section 3.1.4.2.2). In this case the drawing page (section 1.3.2) does not contain data providers to be implemented by the protocol client.

To request the vector formatted drawing page, the protocol client constructs the following WSDL message:

```
<s:Envelope xmlns:s="http://www.w3.org/2003/05/soap-envelope">
  <s:Header>
```

```

<a:Action s:mustUnderstand="1"
xmlns:a="http://www.w3.org/2005/08/addressing">http://tempuri.org/IVisioGraphicsService/GetVe
ctorDiagram</a:Action>
  <a:MessageID xmlns:a="http://www.w3.org/2005/08/addressing">urn:uuid:d6266798-5744-42ed-
9753-cc263fda28ae</a:MessageID>
  <a:ReplyTo xmlns:a="http://www.w3.org/2005/08/addressing">
    <a:Address>http://www.w3.org/2005/08/addressing/anonymous</a:Address>
  </a:ReplyTo>
  <a:To s:mustUnderstand="1"
xmlns:a="http://www.w3.org/2005/08/addressing">https://ExampleServer:32844/69e08a7b0e904d1a95
de6dbf31c51529/VisioGraphicsService.svc/secure</a:To>
  <o:Security xmlns:o="http://docs.oasis-open.org/wss/2004/01/oasis-200401-wss-wssecurity-
secext-1.0.xsd">.....</o:Security>
</s:Header>
<s:Body>
  <GetVectorDiagram xmlns="http://tempuri.org/">
    <vectorDiagramRequestContract
      xmlns:b="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer
" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
      <b:DataSources i:nil="true"></b:DataSources>
      <b:DisableRefresh>true</b:DisableRefresh>
      <b:FileUri>http://ExampleServer/BasicDiagram.vdw</b:FileUri>
      <b:PageNumber>1</b:PageNumber>
      <b:TimeLastModified>2009-05-20T17:42:20</b:TimeLastModified>
    </vectorDiagramRequestContract>
  </GetVectorDiagram>
</s:Body>
</s:Envelope>

```

The protocol server responds with the following:



```

<s:Envelope xmlns:a="http://www.w3.org/2005/08/addressing"
  xmlns:s="http://www.w3.org/2003/05/soap-envelope">
  <s:Header>
    <a:Action
      s:mustUnderstand="1">http://tempuri.org/IVisioGraphicsService/GetVectorDiagramResponse</a:Act
ion>
  </s:Header>
  <s:Body>
    <GetVectorDiagramResponse xmlns="http://tempuri.org/">
      <GetVectorDiagramResult
        xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsSer
ver" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
        <d4p1:CacheAge>60</d4p1:CacheAge>
        <d4p1:DataSources i:nil="true"></d4p1:DataSources>
        <d4p1:OutputPage>
          <d4p1:Resources></d4p1:Resources>
          <d4p1:ShapeInfo>
            <Page Name="Page-1" Zoom="-1.000000" OffsetX="407.142857" OffsetY="528.857143"
DefaultUnitsText="50" DefaultUnitsAngle="81" DefaultUnitsDuration="44" DefaultUnitsPage="73"
DocumentID="1360559653">
              <Pages>
                <Page Name="Page-1" />
              </Pages>
              <ShapeInfo Name=" 1" DisplayName="Sheet.1"
Layout="\\" type\":";" 2D\":";" bounds\":" :\\" x\":"191,\\" y\":"
;:191,\\" width\":"287,\\" height\":"287\\"\}" />
            </Page>
          </d4p1:ShapeInfo>
        <d4p1:Xaml>
          <Canvas Height="1056" Name="Workspace" Width="816"
            xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation">
            <!-- Page -->
            <Canvas Width="816" Height="1056" Name="D">
              <Canvas.Background>
                <SolidColorBrush Color="#FFFFFF"/>
              </Canvas.Background>
            </Canvas>
          </d4p1:Xaml>
        </GetVectorDiagramResult>
      </s:Body>
    </s:Envelope>

```

```

<Canvas
Tag="\{&#34;type&#34;:&#34;2D&#34;,&#34;bounds&#34;:\{&#34;x&#34;:192,&#34;y&#34;:192,&#34;wi
dth&#34;:285,&#34;height&#34;:285\}\}" 
    Name="_1" RenderTransform="1, 0, 0, 1, 192, -579">
        <Rectangle Canvas.Left="-0.5" Canvas.Top="770.5" Height="286"
Name=" 1 GO P0" Width="286" StrokeThickness="1"
        StrokeDashCap="Round" StrokeEndLineCap="Round"
        StrokeLineJoin="Round" StrokeStartLineCap="Round">
            <Rectangle.Stroke>
                <SolidColorBrush Color="#FF000000"/>
            </Rectangle.Stroke>
            <Rectangle.Fill>
                <SolidColorBrush Color="#FFFFFF"/>
            </Rectangle.Fill>
        </Rectangle>
    </Canvas>
</Canvas>
</d4p1:Xaml>
</d4p1:OutputPage>
</GetVectorDiagramResult>
</GetVectorDiagramResponse>
</s:Body>
</s:Envelope>

```

4.3 GetVectorDiagram with AddonDataSource

In this scenario, the protocol client calls the **GetVectorDiagram** method (section 3.1.4.2) on a protocol server named "ExampleServer". In this case the protocol client is requesting a drawing page (section 1.3.2) in a [web drawing](#) that is linked to data with a data provider to be implemented by the protocol client.

Initially the protocol client constructs the following WSDL message:

```

<s:Envelope xmlns:s="http://www.w3.org/2003/05/soap-envelope">
    <s:Header>
        <a:Action s:mustUnderstand="1"
            xmlns:a="http://www.w3.org/2005/08/addressing">http://tempuri.org/IVisioGraphicsService/GetVe
ctorDiagram</a:Action>
        <a:MessageID xmlns:a="http://www.w3.org/2005/08/addressing">urn:uuid:cd490d30-778d-447c-
91f3-c0b0ea0e5de4</a:MessageID>
        <a:ReplyTo xmlns:a="http://www.w3.org/2005/08/addressing">
            <a:Address>http://www.w3.org/2005/08/addressing/anonymous</a:Address>
        </a:ReplyTo>
        <a:To s:mustUnderstand="1"
            xmlns:a="http://www.w3.org/2005/08/addressing">https://ExampleServer:32844/69e08a7b0e904d1a95
de6dbf31c51529/VisioGraphicsService.svc/secure</a:To>
        <o:Security xmlns:o="http://docs.oasis-open.org/wss/2004/01/oasis-200401-wss-wssecurity-
secext-1.0.xsd">.....</o:Security>
    </s:Header>
    <s:Body>
        <GetVectorDiagram xmlns="http://tempuri.org/">
            <vectorDiagramRequestContract
                xmlns:b="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer
" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
                <b:DataSources i:nil="true"></b:DataSources>
                <b:DisableRefresh>false</b:DisableRefresh>
                <b:FileUri>http://ExampleServer/Data_Connected.vdw</b:FileUri>
                <b:PageNumber>1</b:PageNumber>
                <b:TimeLastModified>2009-05-22T16:24:27</b:TimeLastModified>
            </vectorDiagramRequestContract>
        </GetVectorDiagram>
    </s:Body>
</s:Envelope>

```

The protocol server responds with the following **GetVectorDiagramResponse** element (section [3.1.4.2.2.2](#)):

```
<s:Envelope xmlns:a="http://www.w3.org/2005/08/addressing"
xmlns:s="http://www.w3.org/2003/05/soap-envelope">
  <s:Header>
    <a:Action
s:mustUnderstand="1">http://tempuri.org/IVisioGraphicsService/GetVectorDiagramResponse</a:Action>
  </s:Header>
  <s:Body>
    <GetVectorDiagramResponse xmlns="http://tempuri.org/">
      <GetVectorDiagramResult
xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
        <d4p1:CacheAge>0</d4p1:CacheAge>
        <d4p1:DataSources>
          <d4p1:AddonDataSource>
            <d4p1:ConnectionString>datamodule=Microsoft.Office.Visio.Server.EcsDataHandler,
Microsoft.Office.Visio.Server, Version=14.0.0.0, Culture=neutral,
PublicKeyToken=71e9bce111e9429c;provider=Microsoft.ACE.OLEDB.12.0;user id=Admin;data
source=http://ExampleServer/sampledata.xlsx;mode=Read;extended
properties='HDR=YES;imex=1;maxscanrows=0;excel 12.0.';jet oledb:system database='';jet
oledb:registry path='';jet oledb:engine type=37;jet oledb:database locking mode=0;jet
oledb:global partial bulk ops=2;jet oledb:global bulk transactions=1;jet oledb:new database
password='';jet oledb:create system database=False;jet oledb:encrypt database=False;jet
oledb:don't copy locale on compact=False;jet oledb:compact without replica repair=False;jet
oledb:sfp=False;jet oledb:support complex data=False</d4p1:ConnectionString>
            <d4p1:Data>
              <xs:schema id="NewDataSet" xmlns="" xmlns:xs="http://www.w3.org/2001/XMLSchema"
xmlns:msdata="urn:schemas-microsoft-com:xml-msdata">
                <xs:element name="NewDataSet" msdata:IsDataSet="true" msdata:Locale="">
                  <xs:complexType>
                    <xs:choice minOccurs="0" maxOccurs="unbounded">
                      <xs:element name="Table1" msdata:Locale="">
                        <xs:complexType>
                          <xs:sequence>
                            <xs:element name="ID" type="xs:string"
minOccurs="0"></xs:element>
                            <xs:element name="FN" type="xs:string"
minOccurs="0"></xs:element>
                            <xs:element name="LN" type="xs:string"
minOccurs="0"></xs:element>
                          </xs:sequence>
                        </xs:complexType>
                      </xs:element>
                    </xs:choice>
                  </xs:complexType>
                </xs:element>
              </xs:schema>
              <diffgr:diffgram xmlns:msdata="urn:schemas-microsoft-com:xml-msdata"
xmlns:diffgr="urn:schemas-microsoft-com:xml-diffgram-v1"></diffgr:diffgram>
            </d4p1:Data>
            <d4p1:Id>1</d4p1:Id>
            <d4p1:QueryString>SheetName=Sheet1; RangeName=A1:C5;</d4p1:QueryString>
          </d4p1:AddonDataSource>
        </d4p1:DataSources>
        <d4p1:OutputPage i:nil="true"></d4p1:OutputPage>
      </GetVectorDiagramResult>
    </GetVectorDiagramResponse>
  </s:Body>
</s:Envelope>
```

To request the vector formatted drawing page (section 1.3.2) with an **AddonDataSource** complex type (section [2.2.4.1](#)), the protocol client now constructs the following WSDL message:

```

<s:Envelope xmlns:s="http://www.w3.org/2003/05/soap-envelope">
  <s:Header>
    <a:Action s:mustUnderstand="1"
      xmlns:a="http://www.w3.org/2005/08/addressing">http://tempuri.org/IVisioGraphicsService/GetVe
ctorDiagram</a:Action>
    <a:MessageID xmlns:a="http://www.w3.org/2005/08/addressing">urn:uuid:c22e255b-6923-496d-
a3f5-a2f3c45f4bbd</a:MessageID>
    <a:ReplyTo xmlns:a="http://www.w3.org/2005/08/addressing">
      <a:Address>http://www.w3.org/2005/08/addressing/anonymous</a:Address>
    </a:ReplyTo>
    <a:To s:mustUnderstand="1"
      xmlns:a="http://www.w3.org/2005/08/addressing">https://ExampleServer:32844/69e08a7b0e904d1a95
de6dbf31c51529/VisioGraphicsService.svc/secure</a:To>
    <o:Security xmlns:o="http://docs.oasis-open.org/wss/2004/01/oasis-200401-wss-wssecurity-
secext-1.0.xsd">.....</o:Security>
  </s:Header>
  <s:Body>
    <GetVectorDiagram xmlns="http://tempuri.org/">
      <vectorDiagramRequest
        xmlns:b="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer
" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
        <b:DataSources>
          <b:AddonDataSource>
            <b:ConnectionString>datamodule=Microsoft.Office.Visio.Server.EcsDataHandler,
Microsoft.Office.Visio.Server, Version=14.0.0.0, Culture=neutral,
PublicKeyToken=71e9bce111e9429c;provider=Microsoft.ACE.OLEDB.12.0;user id=Admin;data
source=http://ExampleServer/sampleddata.xlsx;mode=Read;extended
properties='HDR=YES;imex=1;maxscanrows=0;excel 12.0';jet oledb:system database='';jet
oledb:registry path='';jet oledb:engine type=37;jet oledb:database locking mode=0;jet
oledb:global partial bulk ops=2;jet oledb:global bulk transactions=1;jet oledb:new database
password='';jet oledb:create system database=False;jet oledb:encrypt database=False;jet
oledb:don't copy locale on compact=False;jet oledb:compact without replica repair=False;jet
oledb:sfp=False;jet oledb:support complex data=False</b:ConnectionString>
          <b>Data>
            <xss: schema id="NewDataSet" xmlns:xs="http://www.w3.org/2001/XMLSchema" xmlns="">
              <xss:msdata="urn:schemas-microsoft-com:xml-msdata">
                <xss:element name="NewDataSet" msdata:IsDataSet="true" msdata:Locale="">
                  <xss:complexType>
                    <xss:choice minOccurs="0" maxOccurs="unbounded">
                      <xss:element name="Table1">
                        <xss:complexType>
                          <xss:sequence>
                            <xss:element name="ID" type="xs:double"
minOccurs="0"></xss:element>
                            <xss:element name="FN" type="xs:string"
minOccurs="0"></xss:element>
                            <xss:element name="LN" type="xs:string"
minOccurs="0"></xss:element>
                          </xss:sequence>
                        </xss:complexType>
                      </xss:element>
                    </xss:choice>
                  </xss:complexType>
                </xss:element>
              </xss:msdata>
              <diffgr:diffgram xmlns:diffgr="urn:schemas-microsoft-com:xml-diffgram-v1"
xmlns:msdata="urn:schemas-microsoft-com:xml-msdata">
                <NewDataSet xmlns="">
                  <Table1 diffgr:id="Table1" msdata:rowOrder="0"
diffgr:hasChanges="inserted">
                    <ID>1</ID>
                    <FN>Happy</FN>
                    <LN>kitty</LN>
                  </Table1>
                  <Table1 diffgr:id="Table12" msdata:rowOrder="1"
diffgr:hasChanges="inserted">
                    <ID>2</ID>
                    <FN>Silly</FN>
                    <LN>dog</LN>
                  </Table1>
                </NewDataSet>
              </diffgr:diffgram>
            </xss: schema>
          </b>Data>
        </b:DataSources>
      </vectorDiagramRequest>
    </s:Body>
  </s:Envelope>

```

```

        </Table1>
        <Table1 diffgr:id="Table13" msdata:rowOrder="2"
diffgr:hasChanges="inserted">
            <ID>3</ID>
            <FN>Order</FN>
            <LN>Id</LN>
        </Table1>
        <Table1 diffgr:id="Table14" msdata:rowOrder="3"
diffgr:hasChanges="inserted">
            <ID>4</ID>
            <FN>green</FN>
            <LN>turtle</LN>
        </Table1>
        </NewDataSet>
    </diffgr:diffgram>
</b:Data>
<b:Id>1</b:Id>
<b:QueryString>SheetName=Sheet1; RangeName=A1:C5;</b:QueryString>
<b:AddonDataSource>
</b:DataSources>
<b:DisableRefresh>false</b:DisableRefresh>
<b:FileUri>http://ExampleServer/Data_Connected.vdw</b:FileUri>
<b:PageNumber>1</b:PageNumber>
<b:TimeLastModified>2009-05-22T16:24:27</b:TimeLastModified>
</vectorDiagramRequest>
</GetVectorDiagram>
</s:Body>
</s:Envelope>

```

Finally, the protocol server responds with the following **GetVectorDiagramResponse** element (section 3.1.4.2.2.2):



```

<s:Envelope xmlns:a="http://www.w3.org/2005/08/addressing"
xmlns:s="http://www.w3.org/2003/05/soap-envelope">
    <s:Header>
        <a:Action
s:mustUnderstand="1">http://tempuri.org/IVisioGraphicsService/GetVectorDiagramResponse</a:Action>
    </s:Header>
    <s:Body>
        <GetVectorDiagramResponse xmlns="http://tempuri.org/">
            <GetVectorDiagramResult
                xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
                xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
                    <d4p1:CacheAge>5</d4p1:CacheAge>
                    <d4p1:DataSources i:nil="true"></d4p1:DataSources>

                    <d4p1:OutputPage>
                        <d4p1:Resources></d4p1:Resources>
                        <d4p1:ShapeInfo>
                            <Page Name="Page-1" Zoom="1.192093" OffsetX="346.714286" OffsetY="769.714286"
DefaultUnitsText="50" DefaultUnitsAngle="81" DefaultUnitsDuration="44" DefaultUnitsPage="73"
Conflict="0" DocumentID="-1092095043">
                                <Pages>
                                    <Page Name="Page-1" />
                                </Pages>
                                <ShapeInfo Name="_1" DisplayName="Tagged process"
Layout="\{&quot;type&quot;\};\{&quot;2D&quot;\},\{&quot;bounds&quot;\}:\{&quot;x&quot;\}:132,&quot;y&quot;:276,&quot;width&quot;:222,&quot;height&quot;:75\}\\">
                                    <ShapeDataItems>
                                        <ShapeData Name="ID" FormattedValue="1" Value="1" Format="{0:0.####} {1}" Type="2" LangID="1033" UnitLabel="0" Unit="32" BindingID="1" />
                                        <ShapeData Name="FN" FormattedValue="Happy" Value="Happy" Format="{0}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="1" />
                                        <ShapeData Name="LN" FormattedValue="kitty" Value="kitty" Format="{0}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="1" />
                                    </ShapeDataItems>
                </d4p1:OutputPage>
            </GetVectorDiagramResult>
        </GetVectorDiagramResponse>
    </s:Body>
</s:Envelope>

```

```

        </ShapeInfo>
        <ShapeInfo Name="_9" DisplayName="Tagged process.9"
Layout="\{&quot;type&quot;:&quot;2D&quot;, &quot;bounds&quot;:\{&quot;x&quot;:96,&quot;y&quot;:
:456,&quot;width&quot;:222,&quot;height&quot;:75\}\}">
            <ShapeDataItems>
                <ShapeData Name="ID" FormattedValue="2" Value="2" Format="{0:0.####} {1}" Type="2" LangID="1033" UnitLabel="0" Unit="32" BindingID="2" />
                <ShapeData Name="FN" FormattedValue="Silly" Value="Silly" Format="{}0{}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="2" />
                <ShapeData Name="LN" FormattedValue="dog" Value="dog" Format="{}0{}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="2" />
            </ShapeDataItems>
        </ShapeInfo>
        <ShapeInfo Name="_17" DisplayName="Tagged process.17"
Layout="\{&quot;type&quot;:&quot;2D&quot;, &quot;bounds&quot;:\{&quot;x&quot;:120,&quot;y&quot;:
:648,&quot;width&quot;:222,&quot;height&quot;:75\}\}">
            <ShapeDataItems>
                <ShapeData Name="ID" FormattedValue="3" Value="3" Format="{0:0.####} {1}" Type="2" LangID="1033" UnitLabel="0" Unit="32" BindingID="3" />
                <ShapeData Name="FN" FormattedValue="Order " Value="Order" Format="{}0{}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="3" />
                <ShapeData Name="LN" FormattedValue="Id" Value="Id" Format="{}0{}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="3" />
            </ShapeDataItems>
        </ShapeInfo>
        <ShapeInfo Name="_25" DisplayName="Tagged process.25"
Layout="\{&quot;type&quot;:&quot;2D&quot;, &quot;bounds&quot;:\{&quot;x&quot;:480,&quot;y&quot;:
:492,&quot;width&quot;:222,&quot;height&quot;:75\}\}">
            <ShapeDataItems>
                <ShapeData Name="ID" FormattedValue="4" Value="4" Format="{0:0.####} {1}" Type="2" LangID="1033" UnitLabel="0" Unit="32" BindingID="4" />
                <ShapeData Name="FN" FormattedValue="green" Value="green" Format="{}0{}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="4" />
                <ShapeData Name="LN" FormattedValue="turtle" Value="turtle" Format="{}0{}" Type="0" LangID="1033" UnitLabel="0" Unit="105" BindingID="4" />
            </ShapeDataItems>
        </ShapeInfo>
    </Page>
</d4p1:ShapeInfo>
<d4p1:Xaml>
    <Canvas Height="1056" Name="Workspace" Width="816"
xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation">
    <!-- Page -->
    <Canvas Width="816" Height="1056" Name="D">
        <Canvas.Background>
            <SolidColorBrush Color="#FFFFFF" />
        </Canvas.Background>
        <Canvas
Tag="\{&quot;type&quot;:&quot;2D&quot;, &quot;bounds&quot;:\{&quot;x&quot;:132,&quot;y&quot;:
76,&quot;width&quot;:96,&quot;height&quot;:72\}\}" Name="_1" RenderTransform="1, 0, 0, 1,
132, -708">
            <Canvas Name=" 2">
                <Canvas Tag="Shdw" RenderTransform="1, 0, 0, 1, 1.92, 1.92">
                    <Path Name="S 2 G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 Z">
                        <Path.Stroke>
                            <SolidColorBrush Color="#7FDEDEDE" />
                        </Path.Stroke>
                        <Path.Fill>
                            <SolidColorBrush Color="#7FDEDEDE" />
                        </Path.Fill>
                    </Path>
                </Canvas>
                <Path Name=" 2 G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 Z">
                    <Path.Stroke>
                        <SolidColorBrush Color="#00404040" />

```

```

        </Path.Stroke>
    <Path.Fill>
        <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
            <LinearGradientBrush.GradientStops>
                <GradientStop Color="#00FF00FF" />
                <GradientStop Color="#00FF00FF" Offset="1" />
            </LinearGradientBrush.GradientStops>
        </LinearGradientBrush>
    </Path.Fill>
</Path>
</Canvas>
<Canvas Name="_3" RenderTransform="1, 0, 0, 1, 72, 0">
    <Path Name="_3_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
        StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
        L24 1056 L24 1032 L0 1056 Z">
        <Path.Stroke>
            <SolidColorBrush Color="#FF404040" />
        </Path.Stroke>
        <Path.Fill>
            <SolidColorBrush Color="#FF000000" />
        </Path.Fill>
    </Path>
</Canvas>
<Canvas Name="_5">
    <Canvas.RenderTransform>
        <MatrixTransform Matrix="1,0,0,1,102,-16.65076" />
    </Canvas.RenderTransform>
    <Path Name="_5_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
        1038.57080078125 L1.92 1038.57080078125 L1.92 1054.08 Z"></Path>
    <Path Name="_5_G1_P1" Data="M1.92 1054.08 L118.08 1054.08"></Path>
    <Path Name="_5_G0_P0 line" StrokeThickness="0.5" StrokeDashCap="Round"
        StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
        1054.08 L118.08 1054.08 L118.08 1038.57080078125 L1.92 1038.57080078125 L1.92 1054.08 Z">
        <Path.Stroke>
            <SolidColorBrush Opacity="0" Color="#FF404040" />
        </Path.Stroke>
    </Path>
    <Path Name="_5_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
        StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
        1054.08 L118.08 1054.08">
        <Path.Stroke>
            <SolidColorBrush Color="#FF404040" />
        </Path.Stroke>
    </Path>
    <TextBlock
        Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
        Height="0.201553942620754" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 0,
        96, 1.92, 1038.608582" TextWrapping="Wrap">
        <Run Name="txt_5_fld0" FontFamily="Calibri" FontSize="0.11111"
            Foreground="#FF000000">LN </Run>
    </TextBlock>
    <Canvas>
        <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
            BA71-4F2C-8263-66731F995C4B.odtf" OriginX="3.2534" OriginY="1049.5" UnicodeString="LN">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />
            </Glyphs.Fill>
        </Glyphs>
    </Canvas>
    <Canvas Name="_6">
        <TextBlock
            Tag="Right;Center;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888888
            9" Height="0.201553942620754" Visibility="Collapsed" Width="1.0386175337222"
            RenderTransform="96, 0, 0, 96, 18.372717, 1038.608582" TextWrapping="Wrap">
            <Run Name="txt_6_fld0" FontFamily="Calibri" FontSize="0.11111"
                Foreground="#FF000000">not kitty </Run>
        </TextBlock>
    </Canvas>
    <Canvas.RenderTransform>

```

```

        <MatrixTransform Matrix="96,0,0,96,18.3744,1038.571" />
    </Canvas.RenderTransform>
    <Glyphs UnicodeString="kitty" OriginX="0.825711078964174"
OriginY="0.111110001802444" FontUri="CommonFonts/4C1AABE5-BA71-4F2C-8263-66731F995C4B.odttf"
FontRenderingEmSize="0.111110001802444" Fill="#FF000000" Visibility="Visible" />
    </Canvas>
    </Canvas>
    </Canvas>
    <Canvas Name="_7">
        <Canvas.RenderTransform>
            <MatrixTransform Matrix="1,0,0,1,102,-36" />
        </Canvas.RenderTransform>
        <Path Name="_7_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.57080078125 L1.92 1038.57080078125 L1.92 1054.08 Z"></Path>
        <Path Name="_7_G1_P1" Data="M1.92 1054.08 L118.08 1054.08"></Path>
        <Path Name="_7_G0_P0_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.57080078125 L1.92 1038.57080078125 L1.92 1054.08 Z">
            <Path.Stroke>
                <SolidColorBrush Opacity="0" Color="#FF404040" />
            </Path.Stroke>
        </Path>
        <Path Name="7 G1 P1 line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
            <Path.Stroke>
                <SolidColorBrush Color="#FF404040" />
            </Path.Stroke>
        </Path>
        <TextBlock
            Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
Height="0.201553942620754" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 0,
96, 1.92, 1038.608582" TextWrapping="Wrap">
            <Run Name="txt_7 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">FN </Run>
        </TextBlock>
        <Canvas>
            <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="FN">
                <Glyphs.Fill>
                    <SolidColorBrush Color="#FF000000" />
                </Glyphs.Fill>
            </Canvas>
            <Canvas Name="_8">
                <TextBlock
                    Tag="Right;Center;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
Height="0.201553942620754" Visibility="Collapsed" Width="1.0342764082339"
RenderTransform="96, 0, 0, 96, 18.789465, 1038.608582" TextWrapping="Wrap">
                    <Run Name="txt_8 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">not Happy </Run>
                </TextBlock>
                <Canvas>
                    <Canvas.RenderTransform>
                        <MatrixTransform Matrix="96,0,0,96,18.7872,1038.571" />
                    </Canvas.RenderTransform>
                    <Glyphs UnicodeString="Happy" OriginX="0.787411080680788"
OriginY="0.111110001802444" FontUri="CommonFonts/4C1AABE5-BA71-4F2C-8263-66731F995C4B.odttf"
FontRenderingEmSize="0.111110001802444" Fill="#FF000000" Visibility="Visible" />
                </Canvas>
                <Canvas>
                    <Canvas Name="4">
                        <Path Name="_4_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
L72 1056 L96 984 L0 984 L0 1056 Z">
                            <Path.Stroke>
                                <SolidColorBrush Color="#FF404040" />
                            </Path.Stroke>

```

```

        <Path.Fill>
            <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
                <LinearGradientBrush.GradientStops>
                    <GradientStop Color="#FFFAFAFA" />
                    <GradientStop Color="#FFFFFF" Offset="1" />
                </LinearGradientBrush.GradientStops>
            </LinearGradientBrush>
        </Path.Fill>
    </Path>
</Canvas>
</Canvas>
<Canvas Name=" _9" RenderTransform="1, 0, 0, 1, 96, -528">
    <Canvas Name=" 10">
        <Canvas Tag="Shdw" RenderTransform="1, 0, 0, 1, 1.92, 1.92">
            <Path Name="S_10_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#7FDEDEDE" />
                </Path.Stroke>
                <Path.Fill>
                    <SolidColorBrush Color="#7FDEDEDE" />
                </Path.Fill>
            </Path>
        </Canvas>
        <Path Name=" 10 G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#00404040" />
                </Path.Stroke>
                <Path.Fill>
                    <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
                        <LinearGradientBrush.GradientStops>
                            <GradientStop Color="#00FF00FF" />
                            <GradientStop Color="#00FF00FF" Offset="1" />
                        </LinearGradientBrush.GradientStops>
                    </LinearGradientBrush>
                </Path.Fill>
            </Path>
        </Canvas>
        <Canvas Name=" 11" RenderTransform="1, 0, 0, 1, 72, 0">
            <Path Name=" 11 G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
L24 1056 L24 1032 L0 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#FF404040" />
                </Path.Stroke>
                <Path.Fill>
                    <SolidColorBrush Color="#FF000000" />
                </Path.Fill>
            </Path>
        </Canvas>
        <Canvas Name=" 13">
            <Canvas.RenderTransform>
                <MatrixTransform Matrix="1, 0, 0, 1, 102, -16.688582" />
            </Canvas.RenderTransform>
            <Path Name=" 13_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.61 L1.92 1038.61 L1.92 1054.08 Z"/>
            <Path Name=" 13_G1_P1" Data="M1.92 1054.08 L118.08 1054.08" />
            <Path Name=" 13_G0_P0_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.61 L1.92 1038.61 L1.92 1054.08">
                <Path.Stroke>
                    <SolidColorBrush Opacity="0" Color="#FF404040" />
                </Path.Stroke>
            </Path>
        </Canvas>
    </Canvas>

```

```

        </Path>
        <Path Name=" 13_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
            <Path.Stroke>
                <SolidColorBrush Color="#FF404040" />
            </Path.Stroke>
        </Path>
        <TextBlock
Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
Height="0.16116" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 0, 96, 1.92,
1038.608582" TextWrapping="Wrap">
            <Run Name="txt_13 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">LN </Run>
        </TextBlock>
        <Canvas
<Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="LN">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />
            </Glyphs.Fill>
        </Glyphs>
    </Canvas>
    <Canvas Name="_14">
        <TextBlock
Tag="Right;Center;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888888
9" Height="0.16116" Visibility="Collapsed" Width="1.0386" RenderTransform="96, 0, 0, 96,
18.372717, 1038.608582" TextWrapping="Wrap">
            <Run Name="txt 14 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">dog </Run>
        </TextBlock>
        <Canvas
<Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="100.5" OriginY="1049.5" UnicodeString="dog">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />
            </Glyphs.Fill>
        </Glyphs>
    </Canvas>
</Canvas>
<Canvas Name=" 15">
    <Canvas.RenderTransform>
        <MatrixTransform Matrix="1, 0, 0, 1, 102, -36" />
    </Canvas.RenderTransform>
    <Path Name=" 15_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.61 L1.92 1038.61 L1.92 1054.08 z" />
    <Path Name=" 15_G1_P1" Data="M1.92 1054.08 L118.08 1054.08" />
    <Path Name=" _15_G0_P0_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.61 L1.92 1038.61 L1.92 1054.08">
        <Path.Stroke>
            <SolidColorBrush Opacity="0" Color="#FF404040" />
        </Path.Stroke>
    </Path>
    <Path Name=" _15_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
        <Path.Stroke>
            <SolidColorBrush Color="#FF404040" />
        </Path.Stroke>
    </Path>
    <TextBlock
Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
Height="0.16116" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 0, 96, 1.92,
1038.608582" TextWrapping="Wrap">
            <Run Name="txt_15 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">FN </Run>
        </TextBlock>

```

```

        <Canvas>
            <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="FN">
                <Glyphs.Fill>
                    <SolidColorBrush Color="#FF000000" />
                </Glyphs.Fill>
            </Canvas>
            <Canvas Name="_16">
                <TextBlock
                    Tag="Right;Center;;1.2;0.013888888888889;0.013888888888889;0.013888888888889;0.013888888888888
9" Height="0.16116" Visibility="Collapsed" Width="1.0343" RenderTransform="96, 0, 0, 96,
18.789465, 1038.608582" TextWrapping="Wrap">
                    <Run Name="txt_16_fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">Silly </Run>
                </TextBlock>
            <Canvas>
                <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="84.559" OriginY="1049.5" UnicodeString="Silly">
                    <Glyphs.Fill>
                        <SolidColorBrush Color="#FF000000" />
                    </Glyphs.Fill>
                </Canvas>
            </Canvas>
            <Canvas Name="_12">
                <Path Name="_12_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
L72 1056 L96 1032 L96 984 L0 984 L0 1056 z">
                    <Path.Stroke>
                        <SolidColorBrush Color="#FF404040" />
                    </Path.Stroke>
                    <Path.Fill>
                        <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
                            <LinearGradientBrush.GradientStops>
                                <GradientStop Color="#FFFAFAFA" />
                                <GradientStop Color="#FFFFFF" Offset="1" />
                            </LinearGradientBrush.GradientStops>
                        </LinearGradientBrush>
                    </Path.Fill>
                </Path>
            </Canvas>
        </Canvas>
        <Canvas
            Tag="\{&quot;type&quot;:&quot;2D&quot;,&quot;bounds&quot;:\{&quot;x&quot;:120,&quot;y&quot;:6
48,&quot;width&quot;:96,&quot;height&quot;:72\}\}" Name="_17" RenderTransform="1, 0, 0, 1,
120, -336">
            <Canvas Name="_18">
                <Canvas Tag="Shdw" RenderTransform="1, 0, 0, 1, 1.92, 1.92">
                    <Path Name="S_18_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 z">
                        <Path.Stroke>
                            <SolidColorBrush Color="#7FDEDEDE" />
                        </Path.Stroke>
                        <Path.Fill>
                            <SolidColorBrush Color="#7FDEDEDE" />
                        </Path.Fill>
                    </Path>
                </Canvas>
                <Path Name="_18_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 z">
                    <Path.Stroke>
                        <SolidColorBrush Color="#00404040" />
                    </Path.Stroke>
                    <Path.Fill>
                        <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">

```

```

<LinearGradientBrush.GradientStops>
    <GradientStop Color="#00FF00FF" />
    <GradientStop Color="#00FF00FF" Offset="1" />
</LinearGradientBrush.GradientStops>
</LinearGradientBrush>
</Path.Fill>
</Path>
</Canvas>
<Canvas Name="_19" RenderTransform="1, 0, 0, 1, 72, 0">
    <Path Name="_19_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
L24 1056 L24 1032 L0 1056 Z">
        <Path.Stroke>
            <SolidColorBrush Color="#FF404040" />
        </Path.Stroke>
        <Path.Fill>
            <SolidColorBrush Color="#FF000000" />
        </Path.Fill>
    </Path>
</Canvas>
<Canvas Name="_21">
    <Canvas.RenderTransform>
        <MatrixTransform Matrix="1, 0, 0, 1, 102, -16.688582" />
    </Canvas.RenderTransform>
    <Path Name="_21_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.61 L1.92 1038.61 L1.92 1054.08 Z" />
        <Path Name="_21_G1_P1" Data="M1.92 1054.08 L118.08 1054.08" />
        <Path Name="_21_G0_P0_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.61 L1.92 1038.61 L1.92 1054.08">
            <Path.Stroke>
                <SolidColorBrush Opacity="0" Color="#FF404040" />
            </Path.Stroke>
        </Path>
        <Path Name="_21_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
            <Path.Stroke>
                <SolidColorBrush Color="#FF404040" />
            </Path.Stroke>
        </Path>
    <TextBlock
Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
Height="0.16116" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 0, 96, 1.92,
1038.608582" TextWrapping="Wrap">
        <Run Name="txt_21_fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">LN </Run>
    </TextBlock>
    <Canvas>
        <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="LN">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />
            </Glyphs.Fill>
        </Glyphs>
    </Canvas>
    <Canvas Name=" 22">
        <TextBlock
Tag="Right;Center;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.0138888888888888
9" Height="0.16116" Visibility="Collapsed" Width="1.0386" RenderTransform="96, 0, 0, 96,
18.372717, 1038.608582" TextWrapping="Wrap">
        <Run Name="txt_22_fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">Id </Run>
    </TextBlock>
    <Canvas>
        <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="103.67" OriginY="1049.5" UnicodeString="Id">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />

```

```

        </Glyphs.Fill>
    </Glyphs>
</Canvas>
</Canvas>
<Canvas Name=" 23">
    <Canvas.RenderTransform>
        <MatrixTransform Matrix="1, 0, 0, 1, 102, -36" />
    </Canvas.RenderTransform>
    <Path Name="_23_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.61 L1.92 1038.61 L1.92 1054.08 Z" />
    <Path Name="_23_G1_P1" Data="M1.92 1054.08 L118.08 1054.08" />
    <Path Name="_23_G0_P0_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.61 L1.92 1038.61 L1.92 1054.08">
        <Path.Stroke>
            <SolidColorBrush Opacity="0" Color="#FF404040" />
        </Path.Stroke>
    </Path>
    <Path Name="_23_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
        <Path.Stroke>
            <SolidColorBrush Color="#FF404040" />
        </Path.Stroke>
    </Path>
    <TextBlock
        Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
        Height="0.16116" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 0, 96, 1.92,
        1038.608582" TextWrapping="Wrap">
        <Run Name="txt 23 fld0" FontFamily="Calibri" FontSize="0.11111"
        Foreground="#FF000000">FN </Run>
    </TextBlock>
    <Canvas>
        <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
        BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="FN">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />
            </Glyphs.Fill>
        </Canvas>
        <Canvas Name=" 24">
            <TextBlock
                Tag="Right;Center;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888888
                9" Height="0.16116" Visibility="Collapsed" Width="1.0343" RenderTransform="96, 0, 0, 96,
                18.789465, 1038.608582" TextWrapping="Wrap">
                <Run Name="txt_24_fld0" FontFamily="Calibri" FontSize="0.11111"
                Foreground="#FF000000">Order </Run>
            </TextBlock>
            <Canvas>
                <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
                BA71-4F2C-8263-66731F995C4B.odttf" OriginX="93.242" OriginY="1049.5" UnicodeString="Order">
                    <Glyphs.Fill>
                        <SolidColorBrush Color="#FF000000" />
                    </Glyphs.Fill>
                </Canvas>
            </Canvas>
        </Canvas>
        <Canvas Name=" 20">
            <Path Name="_20_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
            StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
            L72 1056 L96 1032 L96 984 L0 984 L0 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#FF404040" />
                </Path.Stroke>
                <Path.Fill>
                    <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
                        <LinearGradientBrush.GradientStops>

```

```

        <GradientStop Color="#FFFAFAFA" />
        <GradientStop Color="#FFFFFF" Offset="1" />
    </LinearGradientBrush.GradientStops>
    </LinearGradientBrush>
    </Path.Fill>
</Path>
</Canvas>
</Canvas>
<Canvas
    Tag="\{&quot;type&quot;:&quot;2D&quot;,&quot;bounds&quot;:\{&quot;x:&quot;480,&quot;y:&quot;92,&quot;width:&quot;96,&quot;height:&quot;72\}\}" Name=" 25" RenderTransform="1, 0, 0, 1,
480, -492">
    <Canvas Name=" 26">
        <Canvas Tag="Shdw" RenderTransform="1, 0, 0, 1, 1.92, 1.92">
            <Path Name="S_26_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#7FDEDEDE" />
                </Path.Stroke>
                <Path.Fill>
                    <SolidColorBrush Color="#7FDEDEDE" />
                </Path.Fill>
            </Path>
        </Canvas>
        <Path Name=" 26_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M72 1056
L96 1056 L96 1032 L96 984 L0 984 L0 1056 L72 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#00404040" />
                </Path.Stroke>
                <Path.Fill>
                    <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
                        <LinearGradientBrush.GradientStops>
                            <GradientStop Color="#00FF00FF" />
                            <GradientStop Color="#00FF00FF" Offset="1" />
                        </LinearGradientBrush.GradientStops>
                    </LinearGradientBrush>
                </Path.Fill>
            </Path>
        </Canvas>
        <Canvas Name=" 27" RenderTransform="1, 0, 0, 1, 72, 0">
            <Path Name=" 27_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
L24 1056 L24 1032 L0 1056 Z">
                <Path.Stroke>
                    <SolidColorBrush Color="#FF404040" />
                </Path.Stroke>
                <Path.Fill>
                    <SolidColorBrush Color="#FF000000" />
                </Path.Fill>
            </Path>
        </Canvas>
        <Canvas Name=" 29">
            <Canvas.RenderTransform>
                <MatrixTransform Matrix="1, 0, 0, 1, 102, -16.688582" />
            </Canvas.RenderTransform>
            <Path Name=" 29_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.61 L1.92 1038.61 L1.92 1054.08 Z" />
            <Path Name=" 29_G1_P1" Data="M1.92 1054.08 L118.08 1054.08" />
            <Path Name=" 29_G0_P0_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.61 L1.92 1038.61 L1.92 1054.08">
                <Path.Stroke>
                    <SolidColorBrush Opacity="0" Color="#FF404040" />
                </Path.Stroke>
            </Path>
        </Canvas>
    </Canvas>

```

```

        <Path Name="_29_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
            <Path.Stroke>
                <SolidColorBrush Color="#FF404040" />
            </Path.Stroke>
        </Path>
        <TextBlock
            Tag="Left;Top;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889"
Height="0.16116" Visibility="Collapsed" Width="0.75625" RenderTransform="96, 0, 96, 1.92,
1038.608582" TextWrapping="Wrap">
            <Run Name="txt_29 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">LN </Run>
        </TextBlock>
        <Canvas>
            <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="LN">
                <Glyphs.Fill>
                    <SolidColorBrush Color="#FF000000" />
                </Glyphs.Fill>
            </Glyphs>
        </Canvas>
        <Canvas Name=" 30">
            <TextBlock
                Tag="Right;Center;;1.2;0.01388888888889;0.01388888888889;0.01388888888889;0.01388888888889
9" Height="0.16116" Visibility="Collapsed" Width="1.0386" RenderTransform="96, 0, 0, 96,
18.372717, 1038.608582" TextWrapping="Wrap">
                <Run Name="txt_30 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">turtle </Run>
            </TextBlock>
            <Canvas>
                <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="92.523" OriginY="1049.5" UnicodeString="turtle">
                    <Glyphs.Fill>
                        <SolidColorBrush Color="#FF000000" />
                    </Glyphs.Fill>
                </Glyphs>
            </Canvas>
        </Canvas>
        <Canvas Name="_31">
            <Canvas.RenderTransform>
                <MatrixTransform Matrix="1, 0, 0, 1, 102, -36" />
            </Canvas.RenderTransform>
            <Path Name="_31_G0_P0" Data="M1.92 1054.08 L118.08 1054.08 L118.08
1038.61 L1.92 1038.61 L1.92 1054.08 Z" />
            <Path Name="_31_G1_P1" Data="M1.92 1054.08 L118.08 1054.08" />
            <Path Name="_31_G0_P0 line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08 L118.08 1038.61 L1.92 1038.61 L1.92 1054.08">
                <Path.Stroke>
                    <SolidColorBrush Opacity="0" Color="#FF404040" />
                </Path.Stroke>
            </Path>
            <Path Name="_31_G1_P1_line" StrokeThickness="0.5" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="M1.92
1054.08 L118.08 1054.08">
                <Path.Stroke>
                    <SolidColorBrush Color="#FF404040" />
                </Path.Stroke>
            </Path>
        </TextBlock>
    <Run Name="txt_31 fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">FN </Run>
    </TextBlock>
    <Canvas>

```

```

        <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="3.2534" OriginY="1049.5" UnicodeString="FN">
            <Glyphs.Fill>
                <SolidColorBrush Color="#FF000000" />
            </Glyphs.Fill>
        </Glyphs>
    </Canvas>
    <Canvas Name="_32">
        <TextBlock
            Tag="Right;Center;;1.2;0.013888888888889;0.013888888888889;0.013888888888889;0.013888888888889
9" Height="0.16116" Visibility="Collapsed" Width="1.0343" RenderTransform="96, 0, 0, 96,
18.789465, 1038.608582" TextWrapping="Wrap">
            <Run Name="txt_32_fld0" FontFamily="Calibri" FontSize="0.11111"
Foreground="#FF000000">green </Run>
        </TextBlock>
        <Canvas>
            <Glyphs FontRenderingEmSize="10.667" FontUri="CommonFonts/4C1AABE5-
BA71-4F2C-8263-66731F995C4B.odttf" OriginX="91.789" OriginY="1049.5" UnicodeString="green">
                <Glyphs.Fill>
                    <SolidColorBrush Color="#FF000000" />
                </Glyphs.Fill>
            </Glyphs>
        </Canvas>
    </Canvas>
    <Canvas Name="_28">
        <Path Name="_28_G0" StrokeThickness="0.33333" StrokeDashCap="Round"
StrokeEndLineCap="Round" StrokeLineJoin="Round" StrokeStartLineCap="Round" Data="F0 M0 1056
L72 1056 L96 1032 L96 984 L0 984 L0 1056 Z">
            <Path.Stroke>
                <SolidColorBrush Color="#FF404040" />
            </Path.Stroke>
            <Path.Fill>
                <LinearGradientBrush StartPoint="0.5,0" EndPoint="0.5,1">
                    <LinearGradientBrush.GradientStops>
                        <GradientStop Color="#FFAFAFAFA" />
                        <GradientStop Color="#FFFFFFFFF" Offset="1" />
                    </LinearGradientBrush.GradientStops>
                </LinearGradientBrush>
            </Path.Fill>
        </Path>
    </Canvas>

```

4.4 GetRasterPage

In this scenario, the protocol client calls the **GetRasterPage** method (section [3.1.4.3](#)) on a protocol server named "ExampleServer". The protocol server responds with a **GetRasterPageResponse** element (section [3.1.4.3.2.2](#)). To request the raster formatted drawing page (section [1.3.2](#)) of a VSDX web drawing (section [1.3.1](#)), the protocol client constructs the following WSDL message.

```

<s:Body>
    <GetRasterPage xmlns="http://tempuri.org/">
        <rasterPageRequestContract
            xmlns:b="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer
" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">

```

```

<b:DataModeName>DynamicSafe</b:DataModeName>
<b:DataSources i:nil="true"></b:DataSources>
<b:EntityTag>
  <b:DataModeName>Static</b:DataModeName>
  <b:FileETag i:nil="true"></b:FileETag>
  <b:OutputETag i:nil="true"></b:OutputETag>
  <b:SequenceId i:nil="true"></b:SequenceId>
</b:EntityTag>
<b:FileUrl> http://ExampleServer/BasicDiagram.vsdx</b:FileUrl>
<b:PageId>-1</b:PageId>
<b:RefreshCookie i:nil="true"></b:RefreshCookie>
</rasterPageRequestContract>
</GetRasterPage>
</s:Body>

```

The protocol server responds with the following:

```

<s:Body>
  <GetRasterPageItemResponse xmlns="http://tempuri.org/">
    <GetRasterPageItemResult
      xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
      xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
      <d4p1:EntityTag>
        <d4p1:DataModeName>Static</d4p1:DataModeName>
        <d4p1:FileETag>{BFC23F51-DFCB-4C68-A3C0-E2422785F256},1</d4p1:FileETag>
      </d4p1:EntityTag>
      <d4p1:ItemData></d4p1:ItemData>
      <d4p1:ResponseCode>OK</d4p1:ResponseCode>
    </GetRasterPageItemResult>
  </GetRasterPageItemResponse>
</s:Body>

```

4.5 GetRasterPageItem

In this scenario, the protocol client calls the **GetRasterPageItem** method (section [3.1.4.4](#)) on a protocol server named "ExampleServer". The protocol server responds with a **GetRasterPageItemResponse** element (section [3.1.4.4.2.2](#)). The **GetRasterPageItem** operation retrieves an item, as specified in section [3.1.1](#), of a drawing page (section [1.3.2](#)) of a **VSDX** web drawing (section [1.3.1](#)) rendered in raster format.

To request the this item, the protocol client constructs the following WSDL message:

```

<s:Envelope>
  <s:Body>
    <GetRasterPageItem xmlns="http://tempuri.org/">
      <rasterPageItemRequestContract
        xmlns:b="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
        <b:EntityTag>
          <b:DataModeName>Static</b:DataModeName>
          <b:FileETag i:nil="true"></b:FileETag>
        </b:EntityTag>
        <b:FileUrl> http://ExampleServer/BasicDiagram.vsdx</b:FileUrl>
        <b:ItemId>ShapeInfo</b:ItemId>
        <b:SequenceId>363696e759d24d3aa58818e65c33b6dd</b:SequenceId>
      </rasterPageItemRequestContract>
    </GetRasterPageItem>
  </s:Body>
</s:Envelope>

```

The protocol server responds with the following for Drawing with Static **DataModeName** (section 3.1.4.3.3.1):

```
<s:Envelope>
  <s:Body>
    <GetRasterPageItemResponse xmlns="http://tempuri.org/">
      <GetRasterPageItemResult
        xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
          <d4p1:EntityTag>
            <d4p1:DataModeName>Static</d4p1:DataModeName>
            <d4p1:FileETag>{BFC23F51-DFCB-4C68-A3C0-E2422785F256},1</d4p1:FileETag>
          </d4p1:EntityTag>
          <d4p1:ItemData></d4p1:ItemData>
          <d4p1:ResponseCode>OK</d4p1:ResponseCode>
        </GetRasterPageItemResult>
      </GetRasterPageItemResponse>
    </s:Body>
  </s:Envelope>
```

The protocol server responds with the following for Drawing with Dynamic **DataModeName** (section 3.1.4.3.3.1):

```
<s:Envelope>
  <s:Body>
    <GetRasterPageItemResponse xmlns="http://tempuri.org/">
      <GetRasterPageItemResult
        xmlns:d4p1="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer" xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
          <d4p1:EntityTag>
            <d4p1:DataModeName>Dynamic</d4p1:DataModeName>
            <d4p1:FileETag>{E15A7F56-A0BC-44FB-9EE1-5B3DE24E3176},1</d4p1:FileETag>
          </d4p1:EntityTag>
          <d4p1:ItemData></d4p1:ItemData>
          <d4p1:ResponseCode>OK</d4p1:ResponseCode>
        </GetRasterPageItemResult>
      </GetRasterPageItemResponse>
    </s:Body>
  </s:Envelope>
```

In addition, for both Static & Dynamic DataModeName (for details on DataModeName see section 3.1.4.3.3.1), the protocol server responds with the following for returned image:

```
<s:Envelope>
  <s:Body>
    <GetRasterPageItemResponse xmlns="http://tempuri.org/">
      <GetRasterPageItemResult
        xmlns:b="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
        xmlns:i="http://www.w3.org/2001/XMLSchema-instance">
          <b:EntityTag>
            <b:DataModeName>Dynamic</b:DataModeName>
            <b:FileETag>{E15A7F56-A0BC-44FB-9EE1-5B3DE24E3176},1</b:FileETag>
          </b:EntityTag>
          <b:ImageData>iVBORw0KGgoAAAANSUhEUgAAAnkAAAHpCAYAAAGJgBrpAAAAAXNSR0IArs4c6QAAAARnQU1BAACxjwv8Y
QUAAAAJcEhZcwAADsMAAA7DAcdvqGQAACBxSURBVHhe7d3tbXVXegDwgBaSQEBWaiUgs0SEyPjQkpAFId7syKmREisB6i
pkq4gVQu6qzW5T0ipbuhASJVuR1260aVowGJZ2s0r1VJHSF6kfqNWu2mAbw4da6vf+ARvbGOxg4+15kO/KcbBJDPF9/6
u9GjuvNyZc34znDw+M3Nyyy0+BAgQIECAAEBCAgQIECAAECBAgQIECAAECBAgQIECAAIgYF2hqavp8oqipqbmm77AFu
tIIjIyPZRHa2vrWje6/7H8/NDSUTRTXAmxra7stUGpra5/98MPX1y7du1f1t3SZBW8d01SN1EEYILKrhcvVDdjX15dNF
AG4ZcuWlnnz5r22bNm9y64FtWjRomsrxjUnp6ebKLQBlbMZAciBAgQIECAAAECBAgQIECAAECBAgQIECAAAECBAgQIE
CAAECBAgQIECAAAECBAgQIECAAECBAgQIECAAECBAgQKL7AZKOqFb90JV6CyUZUK/Gif794k42mNln
p0thWL1dXV/+g+DUoYgkmG0ktjaD2v0ZRm+TkTDaKWvx7ty5f7NmzZp9XV1ddUU8x6V56M1GUCvNEisVAQIECBAgQIAA
AQIECBAgQIAAAQIECBAgQIAAAQIECBAgQIAAAQIECBAgQIAAAQIECBAgQIAAAQIECBAgQIAAAQIECBAgQIAAAQIECBAgQ
IAAAQIECBAgQIAAAQIECBAgQIAAAQIECB4jka2xU9ra+tbcAnckMDw8HA21chdfAsXLmxJBdg7b968N2
```


4.6 SaveComments

In this example, the protocol client calls the **SaveComments** method (section 3.1.4.5) on a protocol server named "ExampleServer". The protocol server responds with a **SaveCommentsResponse** element (section 3.1.4.5.2.2). To request the raster-formatted drawing page (section 1.3.2) of a **VSX** web drawing (section 1.3.1), the protocol client constructs the following WSDL message:

```
<s:Envelope>
  <s:Body>
    <SaveComments xmlns="http://tempuri.org/">
      <fileUrl> http://ExampleServer/BasicDiagram.vsdx</fileUrl>
      <commentData>
        <Comment Author='Name of Author' ResolutionID='&lt;resolutionId
provider=&quot;AD&quot;&gt;&lt;localId sid=&quot;s-1-5-21-2127521184-1604012920-1887927527-
2413478&quot;&gt;&lt;/resolutionId&gt;' PageID='0' ShapeID='-1'
Action='Add'>SampleCommentText</Comment>
      </commentData>
    </SaveComments>
  </s:Body>
```

```
</s:Envelope>
```

The protocol server responds with the following:

```
<s:Envelope>
<s:Body>
  <SaveCommentsResponse xmlns="http://tempuri.org/">
    <SaveCommentsResult>
      <Comment Action="Add" CommentID="0" Author="Name of Author" ShapeID="-1"
CreationDate="2012-08-28T22:21:53" ModifiedDate="2012-08-28T22:21:53"
Done="false">SampleCommentText</Comment>
    </SaveCommentsResult>
  </SaveCommentsResponse>
</s:Body>
</s:Envelope>
```

5 Security

5.1 Security Considerations for Implementers

None.

5.2 Index of Security Parameters

None.

Preliminary

6 Appendix A: Full WSDL

For ease of implementation, the full WSDL is provided in this appendix.

```
<?xml version="1.0" encoding="UTF-8"?>
<wsdl:definitions xmlns:soap="http://schemas.xmlsoap.org/wsdl/soap/"
  xmlns:tns2="http://tempuri.org/" xmlns:xs="http://www.w3.org/2001/XMLSchema"
  xmlns:wsaw="http://www.w3.org/2006/05/addressing/wsdl" targetNamespace="http://tempuri.org/"
  xmlns:wsdl="http://schemas.xmlsoap.org/wsdl/">
  <wsdl:types>
    <xss:schema xmlns:tns3="http://tempuri.org/Imports"
      targetNamespace="http://tempuri.org/Imports">
      <xss:import namespace="http://tempuri.org/" />
      <xss:import
        namespace="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er"/>
      <xss:import namespace="http://schemas.microsoft.com/2003/10/Serialization/" />
      <xss:import />
      <xss:import namespace="http://schemas.microsoft.com/2003/10/Serialization/Arrays" />
    </xss:schema>
  </wsdl:types>
  <wsdl:portType name="IVisioGraphicsService">
    <wsdl:operation name="GetRasterDiagram">
      <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterDiagram"
        message="tns2:IVisioGraphicsService_GetRasterDiagram_InputMessage" />
      <wsdl:output
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterDiagramResponse"
        message="tns2:IVisioGraphicsService_GetRasterDiagram_OutputMessage" />
      <wsdl:fault
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterDiagramVisioGraphicsServiceFau
        ltFault" name="VisioGraphicsServiceFaultFault"
        message="tns2:IVisioGraphicsService_GetRasterDiagram_VisioGraphicsServiceFaultFault_FaultMess
        age" />
    </wsdl:operation>
    <wsdl:operation name="GetVectorDiagram">
      <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetVectorDiagram"
        message="tns2:IVisioGraphicsService_GetVectorDiagram_InputMessage" />
      <wsdl:output
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetVectorDiagramResponse"
        message="tns2:IVisioGraphicsService_GetVectorDiagram_OutputMessage" />
      <wsdl:fault
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetVectorDiagramVisioGraphicsServiceFau
        ltFault" name="VisioGraphicsServiceFaultFault"
        message="tns2:IVisioGraphicsService_GetVectorDiagram_VisioGraphicsServiceFaultFault_FaultMess
        age" />
    </wsdl:operation>
    <wsdl:operation name="GetRasterPage">
      <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPage"
        message="tns2:IVisioGraphicsService_GetRasterPage_InputMessage" />
      <wsdl:output
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageResponse"
        message="tns2:IVisioGraphicsService_GetRasterPage_OutputMessage" />
      <wsdl:fault
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageVisioGraphicsServiceFaultF
        ault" name="VisioGraphicsServiceFaultFault"
        message="tns2:IVisioGraphicsService_GetRasterPage_VisioGraphicsServiceFaultFault_FaultMessage
        " />
    </wsdl:operation>
    <wsdl:operation name="GetRasterPageItem">
      <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageItem"
        message="tns2:IVisioGraphicsService_GetRasterPageItem_InputMessage" />
      <wsdl:output
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageItemResponse"
        message="tns2:IVisioGraphicsService_GetRasterPageItem_OutputMessage" />
      <wsdl:fault
        wsaw:Action="http://tempuri.org/IVisioGraphicsService/GetRasterPageItemVisioGraphicsServiceFa
        ultFault" name="VisioGraphicsServiceFaultFault"
```

```

message="tns2:IVisioGraphicsService_GetRasterPageItem_VisioGraphicsServiceFaultFault_FaultMessage"/>
    </wsdl:operation>
    <wsdl:operation name="SaveComments">
        <wsdl:input wsaw:Action="http://tempuri.org/IVisioGraphicsService/SaveComments"
message="tns2:IVisioGraphicsService_SaveComments_InputMessage"/>
        <wsdl:output
wsaw:Action="http://tempuri.org/IVisioGraphicsService/SaveCommentsResponse"
message="tns2:IVisioGraphicsService_SaveComments_OutputMessage"/>
        <wsdl:fault
wsaw:Action="http://tempuri.org/IVisioGraphicsService/SaveCommentsVisioGraphicsServiceFaultFault"
name="VisioGraphicsServiceFaultFault"
message="tns2:IVisioGraphicsService_SaveComments_VisioGraphicsServiceFaultFault_FaultMessage"
/>
    </wsdl:operation>
</wsdl:portType>
<wsdl:binding name="DefaultBinding_IVisioGraphicsService"
type="tns2:IVisioGraphicsService">
    <soap:binding transport="http://schemas.xmlsoap.org/soap/http"/>
    <wsdl:operation name="GetRasterDiagram">
        <soap:operation soapAction="http://tempuri.org/IVisioGraphicsService/GetRasterDiagram"
style="document"/>
        <wsdl:input>
            <soap:body use="literal"/>
        </wsdl:input>
        <wsdl:output>
            <soap:body use="literal"/>
        </wsdl:output>
        <wsdl:fault name="VisioGraphicsServiceFaultFault">
            <soap:fault use="literal" name="VisioGraphicsServiceFaultFault" namespace="" />
        </wsdl:fault>
    </wsdl:operation>
    <wsdl:operation name="GetVectorDiagram">
        <soap:operation soapAction="http://tempuri.org/IVisioGraphicsService/GetVectorDiagram"
style="document"/>
        <wsdl:input>
            <soap:body use="literal"/>
        </wsdl:input>
        <wsdl:output>
            <soap:body use="literal"/>
        </wsdl:output>
        <wsdl:fault name="VisioGraphicsServiceFaultFault">
            <soap:fault use="literal" name="VisioGraphicsServiceFaultFault" namespace="" />
        </wsdl:fault>
    </wsdl:operation>
    <wsdl:operation name="GetRasterPage">
        <soap:operation soapAction="http://tempuri.org/IVisioGraphicsService/GetRasterPage"
style="document"/>
        <wsdl:input>
            <soap:body use="literal"/>
        </wsdl:input>
        <wsdl:output>
            <soap:body use="literal"/>
        </wsdl:output>
        <wsdl:fault name="VisioGraphicsServiceFaultFault">
            <soap:fault use="literal" name="VisioGraphicsServiceFaultFault" namespace="" />
        </wsdl:fault>
    </wsdl:operation>
    <wsdl:operation name="GetRasterPageItem">
        <soap:operation soapAction="http://tempuri.org/IVisioGraphicsService/GetRasterPageItem"
style="document"/>
        <wsdl:input>
            <soap:body use="literal"/>
        </wsdl:input>
        <wsdl:output>
            <soap:body use="literal"/>
        </wsdl:output>
        <wsdl:fault name="VisioGraphicsServiceFaultFault">
            <soap:fault use="literal" name="VisioGraphicsServiceFaultFault" namespace="" />
        </wsdl:fault>
    </wsdl:operation>

```

```

    </wsdl:operation>
    <wsdl:operation name="SaveComments">
        <soap:operation soapAction="http://tempuri.org/IVisioGraphicsService/SaveComments"
style="document"/>
        <wsdl:input>
            <soap:body use="literal"/>
        </wsdl:input>
        <wsdl:output>
            <soap:body use="literal"/>
        </wsdl:output>
        <wsdl:fault name="VisioGraphicsServiceFaultFault">
            <soap:fault use="literal" name="VisioGraphicsServiceFaultFault" namespace="" />
        </wsdl:fault>
    </wsdl:operation>
</wsdl:binding>
<wsdl:message name="IVisioGraphicsService_GetRasterDiagram_InputMessage">
    <wsdl:part name="parameters" element="tns2:GetRasterDiagram"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService GetRasterDiagram OutputMessage">
    <wsdl:part name="parameters" element="tns2:GetRasterDiagramResponse"/>
</wsdl:message>
<wsdl:message
name="IVisioGraphicsService GetRasterDiagram VisioGraphicsServiceFaultFault FaultMessage">
    <wsdl:part
xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
er" name="detail" element="tns:VisioGraphicsServiceFault"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_GetRasterPage_InputMessage">
    <wsdl:part name="parameters" element="tns2:GetRasterPage"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService GetRasterPage OutputMessage">
    <wsdl:part name="parameters" element="tns2:GetRasterPageResponse"/>
</wsdl:message>
<wsdl:message
name="IVisioGraphicsService_GetRasterPage_VisioGraphicsServiceFaultFault_FaultMessage">
    <wsdl:part
xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
er" name="detail" element="tns:VisioGraphicsServiceFault"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_GetRasterPageItem_InputMessage">
    <wsdl:part name="parameters" element="tns2:GetRasterPageItem"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_GetRasterPageItem_OutputMessage">
    <wsdl:part name="parameters" element="tns2:GetRasterPageItemResponse"/>
</wsdl:message>
<wsdl:message
name="IVisioGraphicsService_GetRasterPageItem_VisioGraphicsServiceFaultFault_FaultMessage">
    <wsdl:part
xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
er" name="detail" element="tns:VisioGraphicsServiceFault"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_GetVectorDiagram_InputMessage">
    <wsdl:part name="parameters" element="tns2:GetVectorDiagram"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_GetVectorDiagram_OutputMessage">
    <wsdl:part name="parameters" element="tns2:GetVectorDiagramResponse"/>
</wsdl:message>
<wsdl:message
name="IVisioGraphicsService GetVectorDiagram VisioGraphicsServiceFaultFault FaultMessage">
    <wsdl:part
xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
er" name="detail" element="tns:VisioGraphicsServiceFault"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_SaveComments_InputMessage">
    <wsdl:part name="parameters" element="tns2:SaveComments"/>
</wsdl:message>
<wsdl:message name="IVisioGraphicsService_SaveComments_OutputMessage">
    <wsdl:part name="parameters" element="tns2:SaveCommentsResponse"/>
</wsdl:message>

```

```
<wsdl:message  
name="IVisioGraphicsService_SaveComments_VisioGraphicsServiceFaultFault_FaultMessage">  
  <wsdl:part  
  xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ  
er" name="detail" element="tns:VisioGraphicsServiceFault"/>  
</wsdl:message>  
</wsdl:definitions>
```

Preliminary

7 Appendix B: Full XML Schema

| Schema name | Prefix | Section |
|--|--------|---------------------|
| http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer | tns | 7.1 |
| http://schemas.microsoft.com/2003/10/Serialization/Arrays | q1 | 7.2 |
| http://schemas.microsoft.com/2003/10/Serialization/ | tns1 | 7.3 |
| http://tempuri.org/ | tns2 | 7.4 |

For ease of implementation, the following sections provide the full XML schema for this protocol.

7.1 http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer Schema

```
<?xml version="1.0" encoding="UTF-8"?>
<xss:schema
  xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
  elementFormDefault="qualified"
  targetNamespace="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
  xmlns:xss="http://www.w3.org/2001/XMLSchema">
  <xss:complexType name="RasterDiagramRequestContract">
    <xss:complexContent mixed="false">
      <xss:extension base="tns:BaseRequestContract">
        <xss:sequence>
          <xss:element minOccurs="0" name="Resolution" type="xss:int"/>
        </xss:sequence>
      </xss:extension>
    </xss:complexContent>
  </xss:complexType>
  <xss:element name="RasterDiagramRequestContract" nillable="true"
    type="tns:RasterDiagramRequestContract"/>
  <xss:complexType name="BaseRequestContract">
    <xss:sequence>
      <xss:element minOccurs="0" name="DataSources" nillable="true"
        type="tns:ArrayOfAddonDataSource"/>
      <xss:element minOccurs="0" name="DisableRefresh" type="xss:boolean"/>
      <xss:element minOccurs="0" name="FileUri" nillable="true" type="xss:anyURI"/>
      <xss:element minOccurs="0" name="PageNumber" type="xss:int"/>
      <xss:element minOccurs="0" name="TimeLastModified" type="xss:dateTime"/>
    </xss:sequence>
  </xss:complexType>
  <xss:element name="BaseRequestContract" nillable="true" type="tns:BaseRequestContract"/>
  <xss:complexType name="ArrayOfAddonDataSource">
    <xss:sequence>
      <xss:element minOccurs="0" maxOccurs="unbounded" name="AddonDataSource" nillable="true"
        type="tns:AddonDataSource"/>
    </xss:sequence>
  </xss:complexType>
  <xss:element name="ArrayOfAddonDataSource" nillable="true"
    type="tns:ArrayOfAddonDataSource"/>
  <xss:complexType name="AddonDataSource">
    <xss:sequence>
      <xss:element minOccurs="0" name="ConnectionString" nillable="true" type="xss:string"/>
      <xss:element minOccurs="0" name="Data" nillable="true">
        <xss:complexType>
          <xss:sequence>
            <xss:element ref="xss:schema"/>
            <xss:any/>
          </xss:sequence>
        </xss:complexType>
      </xss:element>
    </xss:sequence>
  </xss:complexType>
</xss:schema>
```

```

        </xs:complexType>
    </xs:element>
    <xs:element minOccurs="0" name="Id" type="xs:int"/>
    <xs:element minOccurs="0" name="QueryString" nillable="true" type="xs:string"/>
</xs:sequence>
</xs:complexType>
<xs:element name="AddonDataSource" nillable="true" type="tns:AddonDataSource"/>
<xs:complexType name="RasterDiagram">
    <xs:complexContent mixed="false">
        <xs:extension base="tns:DiagramBase">
            <xs:sequence>
                <xs:element minOccurs="0" name="AreaMaps" nillable="true" type="xs:string"/>
                <xs:element minOccurs="0" name="Image" nillable="true" type="xs:base64Binary"/>
                <xs:element minOccurs="0" name="ShapeInfo" nillable="true" type="xs:string"/>
            </xs:sequence>
        </xs:extension>
    </xs:complexContent>
</xs:complexType>
<xs:element name="RasterDiagram" nillable="true" type="tns:RasterDiagram"/>
<xs:complexType name="DiagramBase">
    <xs:sequence>
        <xs:element minOccurs="0" name="CacheAge" type="xs:int"/>
        <xs:element minOccurs="0" name="DataSources" nillable="true"
type="tns:ArrayOfAddonDataSource"/>
    </xs:sequence>
</xs:complexType>
<xs:element name="DiagramBase" nillable="true" type="tns:DiagramBase"/>
<xs:complexType name="VisioGraphicsServiceFault">
    <xs:sequence>
        <xs:element minOccurs="0" name="Details" nillable="true" type="xs:string"/>
        <xs:element minOccurs="0" name="Error" type="tns:FaultCode"/>
        <xs:element minOccurs="0" name="Flags" type="xs:int"/>
    </xs:sequence>
</xs:complexType>
<xs:element name="VisioGraphicsServiceFault" nillable="true"
type="tns:VisioGraphicsServiceFault"/>
<xs:simpleType name="FaultCode">
    <xs:restriction base="xs:string">
        <xs:enumeration value="DataConnectivityError"/>
        <xs:enumeration value="DataSourceConnectionError"/>
        <xs:enumeration value="DataSourcePermissionError"/>
        <xs:enumeration value="EmptyRasterDiagramRequest"/>
        <xs:enumeration value="EmptyVectorDiagramRequest"/>
        <xs:enumeration value="OfficeDataConnectionFileNotFoundException"/>
        <xs:enumeration value="OfficeDataConnectionFileRetrievalError"/>
        <xs:enumeration value="OfficeDataConnection FileAccessDenied"/>
        <xs:enumeration value="IncompatibleDomain"/>
        <xs:enumeration value="WssViewAccessDenied"/>
        <xs:enumeration value="WssListAccessDenied"/>
        <xs:enumeration value="InvalidPageNumber"/>
        <xs:enumeration value="InvalidResolution"/>
        <xs:enumeration value="InvalidImageUrl"/>
        <xs:enumeration value="RasterizationError"/>
        <xs:enumeration value="InvalidFileExtension"/>
        <xs:enumeration value="EmptyServerData"/>
        <xs:enumeration value="OpenServerFileFailed"/>
        <xs:enumeration value="NoReadPermissionToFile"/>
        <xs:enumeration value="KeyNotFoundFromCollection"/>
        <xs:enumeration value="ExceededMaxDiagramSize"/>
        <xs:enumeration value="IncompatibleVersion"/>
        <xs:enumeration value="DataProviderNotTrusted"/>
        <xs:enumeration value="DataBindingConflict"/>
        <xs:enumeration value="UnableToGetExternalDataSourceCredentials"/>
        <xs:enumeration value="UnattendedAccountTypeMismatch"/>
        <xs:enumeration value="RecalcTimedOut"/>
        <xs:enumeration value="LicenseExpired"/>
        <xs:enumeration value="InvalidZoomLevel"/>
        <xs:enumeration value="VSDXFfileLoadGenericError"/>
        <xs:enumeration value="VSDXFfileLoadPermissionError"/>
    </xs:restriction>
</xs:simpleType>

```

```

<xs:enumeration value="VSDXFileSizeError"/>
<xs:enumeration value="WebPartConfigError"/>
<xs:enumeration value="EmptyRasterPageRequest"/>
<xs:enumeration value="EmptyRasterPageItemRequest"/>
<xs:enumeration value="VDWNotSupportExternalList"/>
<xs:enumeration value="ExternalListConfigurationNotSupported"/>
<xs:enumeration value="IncompatibleDomain_15"/>
<xs:enumeration value="FileNotLockedOnServer"/>
<xs:enumeration value="FileAlreadyCheckedOutOnServer"/>
<xs:enumeration value="FileAlreadyLockedOnServer"/>
<xs:enumeration value="DocumentCheckoutRequired"/>
<xs:enumeration value="ExcelFileNotInSharePoint"/>
<xs:enumeration value="PageDrawingAreaSizeUnsupported"/>
<xs:enumeration value="PageImageSizeUnsupported"/>
<xs:enumeration value="PageFailToRaster"/>
<xs:enumeration value="CannotRetrieveExternalListData"/>
</xs:restriction>
</xs:simpleType>
<xs:element name="FaultCode" nillable="true" type="tns:FaultCode"/>
<xs:complexType name="VectorDiagramRequestContract">
    <xs:complexContent mixed="false">
        <xs:extension base="tns:BaseRequestContract">
            <xs:sequence/>
        </xs:extension>
    </xs:complexContent>
</xs:complexType>
<xs:element name="VectorDiagramRequestContract" nillable="true"
type="tns:VectorDiagramRequestContract"/>
<xs:complexType name="VectorDiagram">
    <xs:complexContent mixed="false">
        <xs:extension base="tns:DiagramBase">
            <xs:sequence>
                <xs:element minOccurs="0" name="OutputPage" nillable="true"
type="tns:RenderedPage"/>
            </xs:sequence>
        </xs:extension>
    </xs:complexContent>
</xs:complexType>
<xs:element name="VectorDiagram" nillable="true" type="tns:VectorDiagram"/>
<xs:complexType name="RenderedPage">
    <xs:sequence>
        <xs:element minOccurs="0" name="Resources" nillable="true"
type="tns:ArrayOfDiagramResource"/>
        <xs:element minOccurs="0" name="ShapeInfo" nillable="true" type="xs:string"/>
        <xs:element minOccurs="0" name="Xaml" nillable="true" type="xs:string"/>
    </xs:sequence>
</xs:complexType>
<xs:element name="RenderedPage" nillable="true" type="tns:RenderedPage"/>
<xs:complexType name="ArrayOfDiagramResource">
    <xs:sequence>
        <xs:element minOccurs="0" maxOccurs="unbounded" name="DiagramResource" nillable="true"
type="tns:DiagramResource"/>
    </xs:sequence>
</xs:complexType>
<xs:element name="ArrayOfDiagramResource" nillable="true"
type="tns:ArrayOfDiagramResource"/>
<xs:complexType name="DiagramResource">
    <xs:sequence>
        <xs:element minOccurs="0" name="ByteData" nillable="true" type="xs:base64Binary"/>
        <xs:element minOccurs="0" name="Name" nillable="true" type="xs:string"/>
    </xs:sequence>
</xs:complexType>
<xs:element name="DiagramResource" nillable="true" type="tns:DiagramResource"/>
<xs:complexType name="RasterPageRequest">
    <xs:sequence>
        <xs:element minOccurs="0" name="DataModeName" nillable="true" type="xs:string"/>
        <xs:element minOccurs="0" name="DataSources" nillable="true"
type="tns:ArrayOfAddonDataSource"/>
        <xs:element minOccurs="0" name="EntityTag" nillable="true" type="tns:RasterPageTag"/>
    </xs:sequence>
</xs:complexType>

```

```

<xs:element minOccurs="0" name="FileUrl" nillable="true" type="xs:anyURI"/>
<xs:element minOccurs="0" name="PageId" type="xs:long"/>
<xs:element minOccurs="0" name="RefreshCookie" nillable="true" type="xs:string"/>
</xs:sequence>
</xs:complexType>
<xs:element name="RasterPageRequest" nillable="true" type="tns:RasterPageRequest"/>
<xs:complexType name="RasterPageTag">
<xs:sequence>
<xs:element minOccurs="0" name="DataModeName" nillable="true" type="xs:string"/>
<xs:element minOccurs="0" name="FileETag" nillable="true" type="xs:string"/>
<xs:element minOccurs="0" name="OutputETag" nillable="true" type="xs:string"/>
<xs:element minOccurs="0" name="SequenceId" nillable="true" type="xs:string"/>
</xs:sequence>
</xs:complexType>
<xs:element name="RasterPageTag" nillable="true" type="tns:RasterPageTag"/>
<xs:complexType name="RasterPageResponse">
<xs:sequence>
<xs:element minOccurs="0" name="DataSources" nillable="true"
type="tns:ArrayOfAddonDataSource"/>
<xs:element minOccurs="0" name="EntityTag" nillable="true" type="tns:RasterPageTag"/>
<xs:element minOccurs="0" name="PageInfo" nillable="true" type="tns:Raster PageInfo"/>
<xs:element minOccurs="0" name="ResponseCode" type="tns:RasterPageResponseCode"/>
</xs:sequence>
</xs:complexType>
<xs:element name="RasterPageResponse" nillable="true" type="tns:RasterPageResponse"/>
<xs:complexType name="Raster PageInfo">
<xs:sequence>
<xs:element xmlns:q1="http://schemas.microsoft.com/2003/10/Serialization/Arrays"
minOccurs="0" name="ZoomValues" nillable="true" type="q1:ArrayOfint"/>
</xs:sequence>
</xs:complexType>
<xs:element name="Raster PageInfo" nillable="true" type="tns:Raster PageInfo"/>
<xs:simpleType name="RasterPageResponseCode">
<xs:restriction base="xs:string">
<xs:enumeration value="NotModified"/>
<xs:enumeration value="OK"/>
<xs:enumeration value="DataSources"/>
</xs:restriction>
</xs:simpleType>
<xs:element name="RasterPageResponseCode" nillable="true"
type="tns:RasterPageResponseCode"/>
<xs:complexType name="RasterPageItemRequest">
<xs:sequence>
<xs:element minOccurs="0" name="EntityTag" nillable="true"
type="tns:RasterPageItemTag"/>
<xs:element minOccurs="0" name="FileUrl" nillable="true" type="xs:anyURI"/>
<xs:element minOccurs="0" name="ItemName" nillable="true" type="xs:string"/>
<xs:element minOccurs="0" name="SequenceId" nillable="true" type="xs:string"/>
</xs:sequence>
</xs:complexType>
<xs:element name="RasterPageItemRequest" nillable="true" type="tns:RasterPageItemRequest"/>
<xs:complexType name="RasterPageItemTag">
<xs:sequence>
<xs:element minOccurs="0" name="DataModeName" nillable="true" type="xs:string"/>
<xs:element minOccurs="0" name="FileETag" nillable="true" type="xs:string"/>
</xs:sequence>
</xs:complexType>
<xs:element name="RasterPageItemTag" nillable="true" type="tns:RasterPageItemTag"/>
<xs:complexType name="RasterPageItemResponse">
<xs:sequence>
<xs:element minOccurs="0" name="EntityTag" nillable="true"
type="tns:RasterPageItemTag"/>
<xs:element minOccurs="0" name="ItemData" nillable="true" type="xs:base64Binary"/>
<xs:element minOccurs="0" name="ResponseCode" type="tns:RasterPageItemResponseCode"/>
</xs:sequence>
</xs:complexType>
<xs:element name="RasterPageItemResponse" nillable="true"
type="tns:RasterPageItemResponse"/>
<xs:simpleType name="RasterPageItemResponseCode">

```

```

<xs:restriction base="xs:string">
    <xs:enumeration value="NotModified"/>
    <xs:enumeration value="OK"/>
</xs:restriction>
</xs:simpleType>
<xs:element name="RasterPageItemResponseCode" nillable="true"
type="tns:RasterPageItemResponseCode"/>
<xs:import namespace="http://schemas.microsoft.com/2003/10/Serialization/" />
<xs:import namespace="http://schemas.microsoft.com/2003/10/Serialization/Arrays" />
</xs:schema>

```

7.2 http://schemas.microsoft.com/2003/10/Serialization/Arrays Schema

```

<?xml version="1.0" encoding="UTF-8"?>
<xs:schema xmlns:q1="http://schemas.microsoft.com/2003/10/Serialization/Arrays"
elementFormDefault="qualified"
targetNamespace="http://schemas.microsoft.com/2003/10/Serialization/Arrays"
xmlns:xs="http://www.w3.org/2001/XMLSchema">
    <xs:complexType name="ArrayOfint">
        <xs:sequence>
            <xs:element minOccurs="0" maxOccurs="unbounded" name="int" type="xs:int"/>
        </xs:sequence>
    </xs:complexType>
    <xs:element name="ArrayOfint" nillable="true" type="q1:ArrayOfint"/>
</xs:schema>

```

7.3 http://schemas.microsoft.com/2003/10/Serialization/ Schema

```

<?xml version="1.0" encoding="UTF-8"?>
<xs:schema xmlns:tns1="http://schemas.microsoft.com/2003/10/Serialization/"
attributeFormDefault="qualified" elementFormDefault="qualified"
targetNamespace="http://schemas.microsoft.com/2003/10/Serialization/"
xmlns:xs="http://www.w3.org/2001/XMLSchema">
    <xs:element name="anyType" nillable="true" type="xs:anyType"/>
    <xs:element name="anyURI" nillable="true" type="xs:anyURI"/>
    <xs:element name="base64Binary" nillable="true" type="xs:base64Binary"/>
    <xs:element name="boolean" nillable="true" type="xs:boolean"/>
    <xs:element name="byte" nillable="true" type="xs:byte"/>
    <xs:element name="dateTime" nillable="true" type="xs:dateTime"/>
    <xs:element name="decimal" nillable="true" type="xs:decimal"/>
    <xs:element name="double" nillable="true" type="xs:double"/>
    <xs:element name="float" nillable="true" type="xs:float"/>
    <xs:element name="int" nillable="true" type="xs:int"/>
    <xs:element name="long" nillable="true" type="xs:long"/>
    <xs:element name="QName" nillable="true" type="xs:QName"/>
    <xs:element name="short" nillable="true" type="xs:short"/>
    <xs:element name="string" nillable="true" type="xs:string"/>
    <xs:element name="unsignedByte" nillable="true" type="xs:unsignedByte"/>
    <xs:element name="unsignedInt" nillable="true" type="xs:unsignedInt"/>
    <xs:element name="unsignedLong" nillable="true" type="xs:unsignedLong"/>
    <xs:element name="unsignedShort" nillable="true" type="xs:unsignedShort"/>
    <xs:element name="char" nillable="true" type="tns1:char"/>
    <xs:simpleType name="char">
        <xs:restriction base="xs:int"/>
    </xs:simpleType>
    <xs:element name="duration" nillable="true" type="tns1:duration"/>
    <xs:simpleType name="duration">
        <xs:restriction base="xs:duration">
            <xs:pattern value="-?P(\d*D)?(T(\d*H)?(\d*M)?(\d*(\.\d*)?S)?)?" />
            <xs:minInclusive value="-P10675199DT2H48M5.4775808S"/>
            <xs:maxInclusive value="P10675199DT2H48M5.4775807S"/>
        </xs:restriction>
    </xs:simpleType>
    <xs:element name="guid" nillable="true" type="tns1:guid"/>
    <xs:simpleType name="guid">

```

```

<xs:restriction base="xs:string">
  <xs:pattern value="[\da-fA-F]{8}-[\da-fA-F]{4}-[\da-fA-F]{4}-[\da-fA-F]{4}-[\da-fA-F]{12}" />
</xs:restriction>
</xs:simpleType>
<xs:attribute name="FactoryType" type="xs:QName"/>
<xs:attribute name="Id" type="xs:ID"/>
<xs:attribute name="Ref" type="xs:IDREF"/>
</xs:schema>

```

7.4 http://tempuri.org/ Schema

```

<?xml version="1.0" encoding="UTF-8"?>
<xs:schema elementFormDefault="qualified" targetNamespace="http://tempuri.org/">
  xmlns:xs="http://www.w3.org/2001/XMLSchema">
    <xs:import
      namespace="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"/>
    <xs:element name="GetRasterDiagram">
      <xs:complexType>
        <xs:sequence>
          <xs:element
            xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
            minOccurs="0" name="rasterDiagramRequestContract" nillable="true"
            type="tns:RasterDiagramRequestContract"/>
        </xs:sequence>
      </xs:complexType>
    </xs:element>
    <xs:element name="GetRasterDiagramResponse">
      <xs:complexType>
        <xs:sequence>
          <xs:element
            xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
            minOccurs="0" name="GetRasterDiagramResult" nillable="true" type="tns:RasterDiagram"/>
        </xs:sequence>
      </xs:complexType>
    </xs:element>
    <xs:element name="GetVectorDiagram">
      <xs:complexType>
        <xs:sequence>
          <xs:element
            xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
            minOccurs="0" name="vectorDiagramRequest" nillable="true"
            type="tns:VectorDiagramRequestContract"/>
        </xs:sequence>
      </xs:complexType>
    </xs:element>
    <xs:element name="GetVectorDiagramResponse">
      <xs:complexType>
        <xs:sequence>
          <xs:element
            xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
            minOccurs="0" name="GetVectorDiagramResult" nillable="true" type="tns:VectorDiagram"/>
        </xs:sequence>
      </xs:complexType>
    </xs:element>
    <xs:element name="GetRasterPage">
      <xs:complexType>
        <xs:sequence>
          <xs:element
            xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer"
            minOccurs="0" name="rasterPageRequestContract" nillable="true"
            type="tns:RasterPageRequest"/>
        </xs:sequence>
      </xs:complexType>
    </xs:element>
    <xs:element name="GetRasterPageResponse">

```

```
<xs:complexType>
  <xs:sequence>
    <xs:element
      xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
      er" minOccurs="0" name="GetRasterPageResult" nillable="true" type="tns:RasterPageResponse"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
<xs:element name="GetRasterPageItem">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er" minOccurs="0" name="rasterPageItemRequestContract" nillable="true"
        type="tns:RasterPageItemRequest"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
<xs:element name="GetRasterPageItemResponse">
  <xs:complexType>
    <xs:sequence>
      <xs:element
        xmlns:tns="http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServ
        er" minOccurs="0" name="GetRasterPageItemResult" nillable="true"
        type="tns:RasterPageItemResponse"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
<xs:element name="SaveComments">
  <xs:complexType>
    <xs:sequence>
      <xs:element minOccurs="0" name="fileUrl" nillable="true" type="xs:anyURI"/>
      <xs:element minOccurs="0" name="commentData" nillable="true" type="xs:string"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
<xs:element name="SaveCommentsResponse">
  <xs:complexType>
    <xs:sequence>
      <xs:element minOccurs="0" name="SaveCommentsResult" nillable="true"
        type="xs:string"/>
    </xs:sequence>
  </xs:complexType>
</xs:element>
</xs:schema>
```

pre

8 Appendix C: Product Behavior

The information in this specification is applicable to the following Microsoft products or supplemental software. References to product versions include released service packs.

- Microsoft SharePoint Server 2010
- Microsoft SharePoint Server 2013
- Microsoft SharePoint Server 2016 Preview

Exceptions, if any, are noted below. If a service pack or Quick Fix Engineering (QFE) number appears with the product version, behavior changed in that service pack or QFE. The new behavior also applies to subsequent service packs of the product unless otherwise specified. If a product edition appears with the product version, behavior is different in that product edition.

Unless otherwise specified, any statement of optional behavior in this specification that is prescribed using the terms SHOULD or SHOULD NOT implies product behavior in accordance with the SHOULD or SHOULD NOT prescription. Unless otherwise specified, the term MAY implies that the product does not follow the prescription.

[<1> Section 2.2.9.1](#): This element and its complex types are available only in SharePoint Server 2013.

[<2> Section 2.2.9.2](#): This element and its complex types are available only in SharePoint Server 2013.

[<3> Section 2.2.9.3](#): This element and its complex types are available only in SharePoint Server 2013.

[<4> Section 2.2.9.4](#): This element and its complex types are available only in SharePoint Server 2013.

[<5> Section 3.1.1](#): This model is available only in SharePoint Server 2013.

[<6> Section 3.1.2](#): This timer is available only in SharePoint Server 2013.

[<7> Section 3.1.4](#): The **GetRasterPage** operation is available only in SharePoint Server 2013.

[<8> Section 3.1.4](#): The **GetRasterPageItem** operation is available only in SharePoint Server 2013.

[<9> Section 3.1.4](#): This operation is available only in SharePoint Server 2013.

[<10> Section 3.1.4.3](#): The **GetRasterPage** operation is available only in SharePoint Server 2013.

[<11> Section 3.1.4.4](#): The **GetRasterPageItem** operation is available only in SharePoint Server 2013.

[<12> Section 3.1.4.4](#): In SharePoint Server 2010 and SharePoint Server 2013, the server responds with a **VisioGraphicsServiceFault** complex type SOAP fault only when the request message is null.

[<13> Section 3.1.4.5](#): This operation is available only in SharePoint Server 2013.

[<14> Section 3.1.5](#): This timer event is available only in SharePoint Server 2013.

9 Change Tracking

This section identifies changes that were made to this document since the last release. Changes are classified as New, Major, Minor, Editorial, or No change.

The revision class **New** means that a new document is being released.

The revision class **Major** means that the technical content in the document was significantly revised. Major changes affect protocol interoperability or implementation. Examples of major changes are:

- A document revision that incorporates changes to interoperability requirements or functionality.
- The removal of a document from the documentation set.

The revision class **Minor** means that the meaning of the technical content was clarified. Minor changes do not affect protocol interoperability or implementation. Examples of minor changes are updates to clarify ambiguity at the sentence, paragraph, or table level.

The revision class **Editorial** means that the formatting in the technical content was changed. Editorial changes apply to grammatical, formatting, and style issues.

The revision class **No change** means that no new technical changes were introduced. Minor editorial and formatting changes may have been made, but the technical content of the document is identical to the last released version.

Major and minor changes can be described further using the following change types:

- New content added.
- Content updated.
- Content removed.
- New product behavior note added.
- Product behavior note updated.
- Product behavior note removed.
- New protocol syntax added.
- Protocol syntax updated.
- Protocol syntax removed.
- New content added due to protocol revision.
- Content updated due to protocol revision.
- Content removed due to protocol revision.
- New protocol syntax added due to protocol revision.
- Protocol syntax updated due to protocol revision.
- Protocol syntax removed due to protocol revision.
- Obsolete document removed.

Editorial changes are always classified with the change type **Editorially updated**.

Some important terms used in the change type descriptions are defined as follows:

- **Protocol syntax** refers to data elements (such as packets, structures, enumerations, and methods) as well as interfaces.
- **Protocol revision** refers to changes made to a protocol that affect the bits that are sent over the wire.

The changes made to this document are listed in the following table. For more information, please contact dochelp@microsoft.com.

| Section | Tracking number (if applicable) and description | Major change (Y or N) | Change type |
|--|---|-----------------------|---|
| 8 Appendix C: Product Behavior | Updated list of supported products. | Y | Content updated due to protocol revision. |

10 Index

A

Abstract data model
 common 38
[AddonDataSource complex type](#) 18
[Applicability](#) 15
[ArrayOfAddonDataSource complex type](#) 18
[Attribute groups](#) 24
[Attributes](#) 24

B

[BaseRequestContract complex type](#) 19

C

[Capability negotiation](#) 15
[Change tracking](#) 106
Client
 GetRasterDiagram operation ([section 3.1.4](#) 38, [section 3.1.4.1](#) 39)
 GetRasterPage operation ([section 3.1.4](#) 38, [section 3.1.4.3](#) 49)
 GetRasterPageItem operation ([section 3.1.4](#) 38, [section 3.1.4.4](#) 56, [section 4.5](#) 88)
 GetVectorDiagram operation ([section 3.1.4](#) 38, [section 3.1.4.2](#) 44)
 SaveComments operation ([section 3.1.4](#) 38, [section 3.1.4.5](#) 62)
[Client details](#) 36
[Comment](#) 14
[CommentData common data structure](#) 33
[CommentResult common data structure](#) 34
[Comments common data structure](#) 32
Common
 [abstract data model](#) 38
 initialization 38
 local events 65
 message processing 38
 sequencing rules 38
 timer events 65
 timers 38
[Common data structures](#) 24
 [CommentData](#) 33
 [CommentResult](#) 34
 [Comments](#) 32
 [ShapeInfo](#) 25
[Common details](#) 36
[Complex types](#) 17
 [AddonDataSource](#) 18
 [ArrayOfAddonDataSource](#) 18
 [BaseRequestContract](#) 19
 [DiagramBase](#) 19
 [VisioGraphicsServiceFault](#) 20

D

Data model - abstract
 common 38
Details
 [ShapeInfo XML part](#) 25

[DiagramBase complex type](#) 19
[Drawing page](#) 13

E

Elements
 [VisioGraphicsServiceFault](#) 17

Events
 [local - common](#) 65
 [timer - common](#) 65

Examples
 GetRasterDiagram ([section 4.1](#) 66, [section 4.4](#) 87, [section 4.5](#) 88, [section 4.6](#) 91)
 [GetVectorDiagram](#) 71
 [GetVectorDiagram with AddonDataSource](#) 73
 [overview](#) 66

F

[FaultCode simple type](#) 21
[Fields - vendor-extensible](#) 15
[Full WSDL](#) 94
[Full XML schema](#) 98

<http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer Schema>
98

<http://schemas.microsoft.com/2003/10/Serialization/ Schema> 102

<http://schemas.microsoft.com/2003/10/Serialization/Arrays Schema> 102
<http://tempuri.org/ Schema> 103

G

GetRasterDiagram example ([section 4.1](#) 66, [section 4.4](#) 87, [section 4.5](#) 88, [section 4.6](#) 91)
[GetVectorDiagram example](#) 71
[GetVectorDiagram with AddonDataSource example](#)
73
[Glossary](#) 9
[Groups](#) 24

I

[Implementer - security considerations](#) 93
[Index of security parameters](#) 93
[Informative references](#) 12
Initialization
 common 38
[Introduction](#) 9

L

Local events
 common 65

M

| | |
|---|---|
| Message processing | implementer considerations 93 |
| common 38 | |
| Messages | parameter index 93 |
| AddonDataSource complex type 18 | |
| ArrayOfAddonDataSource complex type 18 | |
| attribute groups 24 | |
| attributes 24 | |
| BaseRequestContract complex type 19 | |
| common data structures 24 | |
| complex types 17 | |
| DiagramBase complex type 19 | |
| elements 17 | |
| enumerated 17 | |
| FaultCode simple type 21 | |
| groups 24 | |
| namespaces 16 | |
| simple types 21 | |
| syntax 16 | |
| transport 16 | |
| VisioGraphicsServiceFault complex type 20 | |
| VisioGraphicsServiceFault element 17 | |
| N | |
| Namespaces | 16 |
| Normative references | 12 |
| O | |
| Operations | |
| GetRasterDiagram (section 3.1.4 | 38, section 3.1.4.1 39) |
| GetRasterPage (section 3.1.4 | 38, section 3.1.4.3 49) |
| GetRasterPageItem (section 3.1.4 | 38, section 3.1.4.4 56, section 4.5 88) |
| GetVectorDiagram (section 3.1.4 | 38, section 3.1.4.2 44) |
| SaveComments (section 3.1.4 | 38, section 3.1.4.5 62) |
| Overview (synopsis) | 13 |
| drawing page | 13 |
| shape | 14 |
| Web drawing | 13 |
| P | |
| Parameters - security index | 93 |
| Preconditions | 14 |
| Prerequisites | 14 |
| Product behavior | 105 |
| Protocol Details | |
| overview | 36 |
| R | |
| References | 11 |
| informative | 12 |
| normative | 12 |
| Relationship to other protocols | 14 |
| S | |
| Security | |
| Sequencing rules | |
| common 38 | |
| Shape | 14 |
| Shape data | 14 |
| ShapeInfo common data structure | 25 |
| ShapeInfo XML part | 25 |
| Simple types | 21 |
| FaultCode 21 | |
| Standards assignments | 15 |
| Structures | |
| comment 14 | |
| shape data 14 | |
| ShapeInfo XML part 25 | |
| Syntax | |
| messages - overview 16 | |
| T | |
| Timer events | |
| common 65 | |
| Timers | |
| common 38 | |
| Tracking changes | 106 |
| Transport | 16 |
| Types | |
| complex 17 | |
| simple 21 | |
| V | |
| Vendor-extensible fields | 15 |
| Versioning | 15 |
| VisioGraphicsServiceFault complex type | 20 |
| VisioGraphicsServiceFault element | 17 |
| W | |
| Web drawing | 13 |
| WSDL | 94 |
| X | |
| XML parts | |
| ShapeInfo 25 | |
| XML schema 98 | |
| http://schemas.datacontract.org/2004/07/Microsoft.Office.Visio.Server.GraphicsServer Schema | |
| 98 | |
| http://schemas.microsoft.com/2003/10/Serialization/ Schema | |
| 102 | |
| http://schemas.microsoft.com/2003/10/Serialization/Arrays Schema | |
| 102 | |
| http://tempuri.org/ Schema | |
| 103 | |
| S | |
| Security | |